

PLAN VIEW DISCHARGE MORTAR CONCRETE (MIN. SI OPE

PRECAST

REINFORCED

CONCRETE WITH

INTEGRAL BASE

SECTION A-A

SEPARATE PRECAST REINFORCED

CONCRETE BASE OPTION


1 IN./FT.)

KEYWAY

DISCHARGE

PLAN VIEW

RISER JOINTS TO BE SEALED WITH A BUTYL RUBBER SEAL PER SEALANT MANUFACTUERS RECOMMENDATIONS CONFORMING TO ASTM C 990 (TYP)



SECTION B-B

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

UNLESS OTHERWISE AUTHORIZED IN WRITING BY THE ENGINEER, THE CONTRACTOR SHALL NOT ORDER AND DELIVER PRECAST INLET UNITS REQUIRED FOR THE PROJECT UNTIL A LIST OF SIZES IS FURNISHED BY THE

DETAILED DRAWINGS FOR PROPOSED ALTERNATE DESIGNS FOR UNDERGROUND DRAINAGE STRUCTURES SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PROVIDING THAT SUCH ALTERNATE DESIGNS MAKE PROVISION FOR EQUIVALENT CAPACITY AND STRENGTH.

ALL PRECAST INLET UNITS SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF ASTM C 913.

ALL DRAINAGE STRUCTURES ARE DESIGNATED ON THE PLANS AS "MANHOLES 3X3-L", "CATCH BASINS 4-B", "INLETS 2X3-H", ETC. THE FIRST NUMBERS DESIGNATES THE SIZE OF THE STRUCTURE, AND THE FOLLOWING LETTER DESIGNATES THE TYPE OF COVER TO BE USED TO COMPRISE THE COMPLETE UNIT.

BASES SHALL BE PLACED ON A BED OF MATERIAL AT LEAST 6 INCHES IN DEPTH, WHICH MEETS THE REQUIREMENTS OF FOUNDATION BACKFILL. THIS BEDDING SHALL BE COMPACTED AND PROVIDE UNIFORM SUPPORT FOR THE ENTIRE AREA OF THE BASE.

ALL BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

PRECAST REINFORCED RISERS SHALL HAVE A TONGUE AND GROOVE JOINT WITH TONGUE UP OR DOWN.

- 4" OVERHANGING BASES ARE REQUIRED FOR CAST-IN-PLACE REINFORCED CONCRETE AND CONCRETE BLOCK INSTALLATIONS. 4" OVERHANG IS REQUIRED WHEN SEPARATE PRECAST BASE IS PROVIDED. OVERHANG IS NOT REQUIRED ON PRECAST STRUCTURES WITH AN INTEGRAL OR MONOLITHIC BASE.

MAXIMUM INSIDE PIPE DIAMETER DETERMINED BY 3 INCH CLEARANCE ON EACH SIDE OF THE OUTSIDE WALL OF THE PIPE. SEE DETAIL "A". ASSUMES PIPE ENTERS PERPENDICULAR TO THE STRUCTURE.


- 1) FOR PRECAST INLETS PROVIDE REINFORCING STEEL IN ACCORDANCE TO ASTM C 913.
- (2) CONTRACTOR TO PROVIDE DRAWING(S) STAMPED BY A PROFESSIONAL ENGINEER FOR STEEL REINFORCING DESIGN FOR CAST-IN-PLACE STRUCTURES.

INLET COVER MATRIX

INLET SIZE		INLET COVER TYPE	ALL A'S	ALL B'S	BW	F	ALL H'S	S	т	٧	WM
	WIDTH (W) (FT)	LENGTH (L) (FT)									
2X2-FT	2	2	Х	х				Х		х	
2X2.5-FT	2	2.5			Х			Х	Х	Х	Х
2X3-FT	2	3					Х				
2.5X3-FT	2.5	3				Х					

PIPE MATRIX

	MAXIMUM INSIDE PIPE DIAMETER					
INLET SIZE	WIDTH (IN)	LENGTH (IN)				
2X2-FT	12	12				
2X2.5-FT	12	18				
2X3-FT	12	24				
2.5X3-FT	18	24				



DETAIL "A"

INLETS 2X2-FT, 2X2.5-FT,

6" MIN. ← CONCRETE

INLETS 2X2-FT, 2X2.5-FT, 2X3-FT AND 2.5X3-FT

2X3-FT AND 2.5X3-FT STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION ∞ APPROVED Sept., 2016 /S/ Rodney Taylor DATE ROADWAY STANDARDS DEVELOPMENT Δ UNIT SUPERVISOR

√5"

PRECAST

REINFORCED

CONCRETE WITH

MONOLITHIC BASE

PRECAST WALL

BED OF MORTAR

Standard Detail Drawing 8C7

October 3, 2016

Inlets 2x2-FT, 2x2.5-FT, 2x3-FT, and 2.5x3-FT

References:

FDM 13-25-30

Bid items associated with this drawing:

ITEM NUMBER	<u>DESCRIPTION</u>	<u>UNIT</u>
611.3220	Inlets 2x2-FT	EACH
611.3225	Inlets 2x2.5-FT	EACH
611.3230	Inlets 2x3-FT	EACH
611.3253	Inlets 2.5x3-FT	EACH

Standardized Special Provisions associated with this drawing:

STSP NUMBER TITLE NONE

Other SDDs associated with this drawing:

SDD 8A5 Inlet cover sheets "a", "b", "c" and "d".
SDD 8D17 Manholes, Manhole and Inlet Covers

Design Notes:

Guidelines for matching inlet opening size and inlet covers are provided on the front side of this SDD.

A pipe matrix on the front side of this SDD provides guidance for selecting the maximum inside pipe diameter. The inside pipe diameter was determined by the pipe entering perpendicular to the structure at 90°. Pipes entering at a skewed angle should be evaluated on a case by case basis.

Inlets should be kept as shallow as possible to reduce cost.

Contact Person:

Ed Lilla (608) 266-2312