



SDD 15D29 Traffic Control, Vehicle Entrance/Exit or Haul Road

LEGEND

- SIGN ON TEMPORARY SUPPORT
- SIGN ON PERMANENT SUPPORT
- TYPE III BARRICADE
- TYPE III BARRICADE WITH ATTACHED SIGN
- TYPE "A" WARNING LIGHT (FLASHING)
- DIRECTION OF TRAFFIC
- FLAGGER, EQUIPPED WITH STOP/SLOW PADDLE FASTENED ON SUPPORT STAFF

POSTED SPEED LIMIT PRIOR TO WORK STARTING (MPH)	ADVANCE WARNING SIGN SPACING (A) FEET
0-30	200'
35-40	350'
45-55	500'

GENERAL NOTES


- ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED.
- "WO" SIGN IS THE SAME AS "W" SIGN EXCEPT THE BACKGROUND IS ORANGE.
- THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.
- WARNING SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.
- WHEN ACTIVITY REFLECTED BY THE SIGN IS NOT CURRENTLY TAKING PLACE, THE HIGHWAY SHALL BE RESTORED TO NORMAL CONDITION AND THE SIGNS SHALL BE REMOVED, COVERED OR TURNED AWAY FROM TRAFFIC.
- WHEN A SIDE ROAD OR RAMP INTERSECTS WITHIN THE ADVANCE SIGNING AREA, ADDITIONAL TRAFFIC CONTROLS SHALL BE PROVIDED AS SPECIFIED IN THE PLANS AND / OR THE SPECIAL PROVISIONS OR AS APPROVED BY THE ENGINEER.
- PLACE SIGNS ON BOTH SIDES IF USED ON DIVIDED HIGHWAY.
- ① THESE SIGNS ARE TO BE USED ONLY WHEN VEHICLE ENTRANCE / EXIT CONDITIONS ARE SEPARATED BY MORE THAN TWO MILES FROM PREVIOUS WORK AREA OR SIGNING OR AS DIRECTED BY THE ENGINEER.

6

6

SDD 15D29 - 06

SDD 15D29 - 06



THIS DETAIL TO BE USED WHEN CONSTRUCTION WORK INCLUDING TRUCKING ACTIVITY REQUIRES MAINLINE TRAFFIC TO BE TEMPORARILY STOPPED IN ONE OR BOTH DIRECTIONS. DELAY TO HIGHWAY TRAFFIC SHALL BE MINIMIZED.

TRAFFIC CONTROL, VEHICLE ENTRANCE/EXIT OR HAUL ROAD

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2020 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER

FHWA

*Traffic Control, Vehicle Entrance/Exit or Haul Road***References:**

Part VI of the Wisconsin Manual on Uniform Traffic Control Devices (WMUTCD)
[FDM 11-50-20](#)

Bid items associated with this drawing:

<u>ITEM NUMBER</u>	<u>DESCRIPTION</u>	<u>UNIT</u>
643.0420	Traffic Control Barricades Type III	DAY
643.0705	Traffic Control Warning Lights Type A	DAY
643.0900	Traffic Control Signs.....	DAY
643.1050	Traffic Control Signs PCMS (if included in contract).....	DAY

Standardized Special Provisions associated with this drawing:

None

Other SDDs associated with this drawing:

SDD 15C11	Traffic Control, Channelizing Devices – Drums, Cones, Barricades and Vertical Panel
SDD 15C4	Traffic Control, Advance Warning Signs 45 M.P.H. or Greater, Two Way Undivided Road Open to Traffic
SDD 15C5	Traffic Control, Advance Warning Signs 40 M.P.H. or Less, Two Way Undivided Road Open to Traffic
SDD 15D28	Traffic Control, Work on Shoulder or Parking Lane, Undivided Roadway

Design Notes:

Additional channelizing devices and signs may be needed on the approaches, such as those shown on the Standard Detail Drawing for Work on Shoulder or Parking Lane.

Portable Changeable Message Signs (Item 643.1050) also may be used, especially where flaggers would be unexpected

Contact Person:

Andrew Heidtke (414) 220-6802