











FINAL DESIGN PHASE

PUBLIC INVOLVEMENT MEETING

Aaron Bowe, P.E. HNTB Corporation

November 1, 2022 Moxie's Hotel, La Crosse





PUBLIC INVOLVEMENT MEETING AGENDA

- 1 TCMC PROJECT OVERVIEW
- 2 AREAS OF IMPROVEMENT

3 NEXT STEPS










TCMC ROUTE

Route Key



O Train Stations

Intercity Bus Service

Commercial Airports

State Borders









TCMC FEATURES and BENEFITS



FREQUENCY 2 ROUND TRIPS

per day with TCMC & Empire Builder/ Hiawatha Services



ROUTE 411 MILES

Saint Paul to Chicago



SPEED

79 MPH

maximum speed in corridor



RIDERS

124,200 PEOPLE

are projected to ride the new trains the first year of full service



SCHEDULE MORNING & MIDDAY

departures from Saint Paul and Chicago



TRAVEL TIME

7.5 HOURS

Saint Paul to Chicago



SERVICE

2023

second daily round trip will begin as soon as 2023



STATIONS 13 LOCATIONS

already in service corridor

ENEFITS



improved due to rail & siding improvements



FREIGHT DELAYS **REDUCED**

with rail upgrades that minimize congestion for quicker and smoother travel



through the leverage of convenient rail service



ECONOMIC DEVELOPMENT

supported through increased tourism








PROJECT TIMELINE







Improvement Map Key





State Borders



- Siding Extension
- Communications and Signal Upgrades
- Install Crossover
- At-Grade Crossing Improvements










LA CROSSE

DEPOT AREA

- Restore a second mainline track
- Extend yard lead west and add signals to re-establish old second mainline track through the La Crosse Depot
- Remove portion of existing platform for restored second track
- Reconstruct platform
- Improve at-grade crossings at Saint Cloud/Liberty streets and Avon/Hagar streets









LA CRESCENT MISSISSIPPI RIVER BRIDGE

- Realign track curve approaches at west end
- Upgrade moveable joints on swing bridge over Mississippi River
- These improvements will increase the freight speed across the bridge from 10 mph to 15 mph










LA CRESCENT

RIVER JUNCTION YARD

- Convert yard track to a second mainline track to accommodate increased speeds
- Modify the wye turnout alignment to increase mainline track speeds to 25 mph
- Construct new mainline track, turnouts, and yard tracks









WINONA

WINONA SIDING

- Rehabilitate two miles of existing siding track
- Install two power turnouts and railroad signals for more efficient train movements
- At-grade crossing improvements









WINONA TOWER CK

- Construct new track to connect mainline track to CPR Waseca Subdivision
- Add power switches and railroad signals for more efficient train movements
- Minimizes freight and passenger train passing conflicts
- Bierce Street/Prairie Island Road at-grade crossing modifications











Review Public Meeting Comments – winter 2022



Additional Public Outreach – spring 2023



Complete Final Design Plans – summer 2023



Start Construction – Start of 2024



Train Service Begins – 2023-2025





THANK YOU

For more information or to leave a comment, please visit one of our TCMC project webpages.





Thomas Kratt Project Manager, WisDOT (608) 789-7874 thomas.kratt@dot.wi.gov

tinyurl.com/WisDOT-TCMC

Greg Mathis
Project Manager, MnDOT
(651) 366-4292
greg.mathis@state.mn.us



tinyurl.com/MnDOT-TCMC