

WisDOT Structural Engineers Symposium

Program Agenda May 22, 2018

8:30 a.m.	Welcome & BOS Director's
	Perspective – Scot Becker

8:00 a.m. Registration

- 8:45 a.m. Contract Plans & Fabrication Shop Drawing Review Changes – Najoua Ksontini, Kristin Revello
- 9:10 a.m. Wind Loaded Structures Initiative Andrew Smith, Mark Maday (CH2M/Jacobs)
- 9:30 a.m. Removing Old Structure Over Waterways – *Bill Dreher*
- 9:45 a.m. Small Group (table) Discussion All
- 10:00 a.m. Timeliness of Consultant Plan Submittals – *Najoua Ksontini*
- 10:15 a.m. Break (Beverages and Snacks)
- 10:35 a.m. Automation, Policy, and Standards – Dave Kiekbusch, James Luebke
- 11:15 a.m. Complex Structures Andrew Smith
- 11:35 a.m. SCC Prestressed Girders Steve Doocy

- 11:50 a.m. Lunch
- 12:50 p.m. Misc. Geotechnical/Structural Topics - Jeff Horsfall (Bureau of Tech Services)
- 1:20 p.m. BOS Overlay Policy, Marquette Interchange PPC Overlays – James Luebke, Jason Sadowski (Michael Baker)
- 1:50 p.m. 3D Design & Modeling, BIM for Structures – Danielle DeTennis, Adam Swierczek
- 2:05 p.m. 194 N-S Frank Pritzlaff (SE Region PM), Aaron Bonk
- 2:35 p.m. Break (Beverages and Snacks)
- 2:55 p.m. Strengthening Program for Local Load Posted Bridges – Alex Pence, Josh Dietsche
- 3:20 p.m. Small Group (table) Discussion All
- 3:35 p.m. Interactive Survey & Q/A
- 4:00 p.m. Adjourn

Conference Location: University of Wisconsin-Madison Union South 1308 West Dayton Street Madison, WI 53715

For today's presentations, agenda, and proof of attendance, please visit:

Welcome - 2018 Symposium

Scot Becker

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI

Perspective Over View

• Welcome

Agenda Highlight

What's new!Continuing Progress

Todays Discussion - Focus Interactive

- Third Symposium 2014,16,18
- Spend Time Today Discussing Issues, Clarifying Polices, Sharing Innovations, Questions or Concerns

What's New -	 Fabrication Library 								
	Part al	Structures Construction Recon	di						
New Fabrication Improved	1	Toke d'Anna Gine Bine	malaat Mariy Societ	-		-			

	10.0441	Time of Second Libro Blass					Inces
New Fabrication Improved	14	[] Musichias	States Second	dame.	100.00	Parlian fa-	1 heard
		C. In the last of the last set of the	-	density .			-
SharePoint Library Includes	14	G delivers being in.	tracine as	dates 1	1000	444 (Mex. 20)	in teache
		E to the laboration	1000	in the second second		ine lain W	where the
Ancillary Structures	2.44	12 CO. Contraction and	marinew.	-			1000
		in the second strategy and	-	-		Contraction Print (see	179800
		E U.S. Same Dataset In-	-	-	1.00	44.144.00	11414
	- 14	12 Internative	And Designed	Acres 1	100.00	Company Instant.	1 igen
	-	E RETURN		-		maxime man	
	1.4	Di maranak	444,014	+			
	-	II BETTA		-	1.0.0	man for dealer.	
	14	ii Ammud	-	-	1000	take her danse.	
		il estinat	10000	-		true lost them.	
	1.4	E reinet	-	-			
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	COMPANY AND INCOME IN CO.	-	1000	1004	and the local	

What's New – SCC in Prestress Girders

- Self-Consolidating Concrete (SCC) for Prestressed Bridge Girders
- Moving Forward with SCC











What's New – St. Croix Bridge	
BLIFEAU OF Welcome - 2018 Symposium	






What's New – Local Bridge Program Changes

- Local Bridge Program Changes
- Fed State Money Swap
- Replace in Kind Policy

BUREAU OF BIRUCIURES

Minimum Standards Based on Engineering Evaluation





Closing Request

I will repeat myself from 2016 if you recall 🙂

- •We want your Feedback and Input
- BOS How are we doing? 4th Symposium? Innovations? Issues?

Contract Plans- Review changes

Najoua Ksontini. P.E.

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI

Goals of presentation

- Discuss changes to review processes for various types of submittals and various types of structures

Stream Crossing and Grade Separation Preliminary Structure Plans

- No review process changes
 - Reviewers may provide comments and reviewed with focus on provide concurrence on Type, Size, and Location
 Reviewers may provide comments on details contained on the preliminary plans

 - Contact BOS if you need input regarding proposed unusual and non-standard details

Stream Crossing and Grade Separation Final Structure Plans

• No review process changes

- BOS will perform a Quality Assurance review on a select number of final structure plan submittals

- Contact BOS if you need input regarding proposed unusual and non-standard details

BUREAU OF SIRUCIURES

Rehabilitation Preliminary Structure Plans

• Review Process changes:

- BOS may not provide comments on preliminary plans for certain types of rehabilitation work such as superstructure
 BOS may not provide comments on preliminary plans for certain types of rehabilitation work such as painting and Polymer overlays

SIRUCIURES

Rehabilitation Final Structure Plans

• Review Process changes:

- BOS will continue to perform Quality Assurance reviews on a select number of final structure plan submittals for rehabilitation work

Retaining Wall Preliminary and Final Structure Plans

• Review Process changes:

- BOS will provide comments only on a select number of retaining wall <u>preliminary</u> and <u>final</u> structure plans
 Focus will be on non-proprietary retaining walls, plans with unusual or non-standard details and complex geometry
- Designers will be notified if comments on preliminary plans will not be provided

BUREAU OF

Sign Structure Preliminary and Final Plans

• Review Process changes:

- structure <u>preliminary</u> and <u>final</u> plans
 Contact BOS if you need input regarding non-standard sign structure details

STRUCTURE



Fabrication Shop Drawing Review & Process Changes Kristin Revello, P.E.

Structural Metals and Fabrication QA Inspection Unit Supervisor

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI

May 22, 2018

Presentation Goals

- To provide background on the Bureau of Structures Fabrication Initiatives
- Discuss the outcomes of each Fabrication Initiative, and highlight upcoming changes
- Address how these changes may affect you as designers of structures with fabricated items

STRUCTURE

Bureau of Structures Fabrication Initiatives Overview Tier 1 Tier 2 • Began Summer 2014 • Began Winter 2017 • Area of Focus • Began Winter 2017 • Steel Fabrication • 4 Areas of Focus • Creation of BOS Teams (Steering and Oversight) • Began Structures • URS • Secondary Fabrication Items

Creation of BOS Teams
Michael Baker International

Wisconsin Department of Transportation

Bureau of Structures Fabrication Initiatives Overview

- · Interviews and Surveys were conducted regarding current processes, areas that worked well, and areas where improvements could be made = Fabricators = 8teel Producers = Other state DOTe
- Other DOT specifications and processes were researched

BUREAU OF

Bureau of Structures Fabrication Initiatives Overview

- For each area of focus, the current policy and practices were documented.
- Results of the interviews and surveys were documented, including current shop drawing review practices in other states
- A report for each initiative with findings and recommendations was created by the Consultant with input from the BOS Steering and Oversight Teams.
- Based on the report findings, BOS created an implementation plan for the outcomes that will be covered today.

SIRUCIURES

Bureau of Structures Fabrication Initiatives

- The creation of the Contractor Certificate of Shop Drawing QC Form, DT 2333 for primary steel members.
- A P.E. is required to review the shop drawing and stamp the form, and a Contractor must sign certifying the review has occurred.
- The creation of the SharePoint Fabrication Library to receive steel shop
- drawings and fabrication documents
- The requirement of weekly Fabricator Progress Reports for primary steel members

• A reduction in the percentage of steel shop drawing reviews performed



BUREAU OF SIRUCIURES

WisDOT Fabrication Quality Assurance Program

Program Goal: To consistently enforce submittal of required documentation and enact Quality Assurance

- Provide electronic submittal requirements for fabrication documents
- Provide guidance for roles and responsibilities for all parties
 involved
- Ensure department quality assurance and contractor quality control roles
- Modify standard specifications and CMM for clarity and enforcement
- Clarify approved fabricator requirements

SIRUCIURES

The WisDOT Fabrication Library Expansion

The Goal: A single comprehensive library for the submittal of all fabrication documents, accessible to all parties (as appropriate).

In March 2018, the new Fabrication Library went live for our users.

For December 2018 Let and beyond, this will be the mechanism to receive all structure shop drawings and fabrication documents.

Roles and Responsibilities - Reference Guide

Fabrication QA Program Reference Guide

	THE OWNER AND ADDRESS OF TAXABLE PARTY.				
	second and all of the second second	maker Second	2101.520	-	in second
	in rack's in Rehabilities.		and the		
		tere parts		Constant (and	- Andrew State
		14074	As enjoyed by		-
	and a second second second				
Parameter and a second second	tale all many methods seems in a part of				Addition Constrainty
A REAL PROPERTY.	AND DESCRIPTION OF A DE	- L'			
Autor Paper	Annual Annua	-	and and a second	arts but	
Sub-Lange and	berth 17 berthouse		and the second second	a factor of a	
71 71		Andre Winger Phone Administration	erin in Aeren		A set is very sup-
		Dentel	Martin	- Bearing	Sec.
		The Summer Security	A set of a		
		within the lot of the lot of		-	
		140,100	-		CECE.
		- No. of the local diversion of the local div	A sector		And and a state of the state of
		Thing Sector particular	Surgeon a		
		Transmission, Parameter	-		A STATE OF STREET
		Telephone Ballings	10000		
		CONTRACTOR OF THE OWNER OWNER OF THE OWNER OWNE OWNER OWNE OWNER OWNER OWNER OWNER OWNER OWNE OWNER OWNE OWNE OWNER OWNE OWNER OWNE OWNER OWNE OWNE OWNE OWNER OWNE OWNE OWNE OWNE OWNE OWNE OWNE OWNE	10000		
		and other	1.000		

BUREAU OF SIRUCIURES

QA vs QC

- Although the Department intended to perform QA review of shop drawings, the reality was that we were performing QC in many areas.

 - In some cases we were correcting errors, and essentially performing QC for the fabricator and contractor
- The decision was made to realign our processes with QA

 - Reducing the percentages of Department review
 Look to place the responsibility of shop drawing QC on the contractor and fabricator

SIRUCIURES

QA vs QC

- The percentages of review, and criteria of selection for each type of shop drawing will be determined by BOS.
 Project staff will be notified when a shop drawing has been selected for
- In the Fabrication Library, there is shop drawing status flag to indicate whether the shop drawing has been selected for review, if was reviewed and it needs to be resubmitted, or if it has been accepted.

Draft	Forms	Construction of the second sec
Sign Structures and Overhead		
Sign Supports Retaining Walls	English setting integring the setting of the set of the	Latence in a case of processing in a case of the second se
Fabricated Bridge Components	Anno balati bana bana bana bana bana bana bana ban	Contrast operation and when the set of
 Prestressed Concrete Girders Mesh substitutions are still being evaluated 	All and a second section of the second section of the second section of the second section of the second seco	
	Frankriker Standerstater Standerstater	Contra de senseres

Modified WisDOT Approved Fabricator List



PPROVED FABRICATIONS, ERDIDE NETAL 3	CONDARY #ASSOCATIO
Isla tast edited. 12/21/2017	
Approved Fabricator	Location
lars Patricators	Sett22 Norway Pt
	Online WV 5522
	218-585-7121
Central of Marbara Inc.	3100 (200 LA NO
	IST \$20,9480
Commercial Fabricators	Dridoeview, IL
ON-SETTA INC.	252 Intentate P
	Drummelck, Ort 6
adger Ralling	Minutes W
5. Drowni Lawis Engineering Civisioni	Chanka, MN
SPO Engineering	545 WDDW2V DC
	Wilcology II.
	50-1912020
35 protests	Minneapolia, Min
onitionite (Senergies, LLC)	PO 5cc 620
	10000 industry A
	Dector, MN 5528
	702-202-4700
mise General Contractors, Inc.	1223 Street Villem
	chere or ser-
	Phone: 715/257.7
ACAL LLC / Paper Calumenters	at Paul NY
EMOVED FROM LIST 3/342015	
Jertec Inc. ¹⁷	1000 Cast Street
	Sloughton, W 52
EMOVED FROM LIST DOMOSIS	408-677-0887
Up Engineering, Inc.	3125 W. LUND RV
	CONTINUES, EL COCI
	101-120-1000
tellty Sales and Supply, Inc.	20200 West Thor
-	Longito, Mon 2020
	412-045-7523
an Lanen Wits, Inc.	\$205 \$7.9.29
**	Denmark, Wil Sci
	120-063-0705

Modified WisDOT Approved	Fabrica	ator L	.ist	
2019 Standard Specification List: Fabricated Bridge Components	gevende same and a const barra - shall the const from the same	LED Santasi Siccionalitat LEDS REVILL®	Con Series The Martin	Approxi (etc.)
Railings Bearings Expansion Devices	Second Se	keeting uith Miller Surf Scribb	Here harde	Sature in Indiana in T
Structural Steel Diaphragms Section 3000 Dates Section 3000 Dates Section 3000 Dates Section 3000 Dates	Provide March Net: Provide March Net: Provid	200 Donte from 8 marine Part Adv 80000	How Kenne 2011 (HA 1967) 2011 (HA 1967) 2012 (HA 1967) 2012 (HA 1967) 2013 (HA 1967)	Internal and

Wisconsin Department of Transportation

New WisDOT Approved Fabricator Lists

Effective with the 2019 Standard Specification

- WisDOT will be creating 2 new Approved Fabricator Lists
- In order to fabricate these items, the fabricator will need to be on the appropriate APL prior to the Let.
- Fabricator requirements to be added to these lists and the
- application & renewal process will be clearly defined for all parties.

BUREAU OF

Fabrication Progress Reports

• The weekly requirement of Fabrication Progress Reports submitted to the Fabrication Library for prestressed girders, fabricated bridge components, sign structures, and overhead sign supports

L		·													
	1. Harager - 1 1	-													
Manufacture Contractor	Company for														
		 -	-												
-		 Logen Jone			 -		-0.	0.00	-	-		*		1713	
-	****	 Adaptives Analitest-Aste		entites.	 1	-	-	And the set of	1	111	ł	H	-	-	-
	-														

Upcoming Changes to Retaining Wall SPVs For the August 1st 2018 PSE

- Changes will include updates to retaining wall system preapproval process information
- Added requirement of Contractor Certificate of Shop Drawing QC for retaining walls
- Adding requirement for Fabrication Library Submittal
- Updated SPVs to be available prior to June 1st for inclusion in August 2018 PSE projects

BUREAU OF

Mail Concesso P 4. Account of the second se

The second process distribution for another second second process (2007) the inclusional field and first field index A scale second process process or related in all another activities process control separates, sampling and realing and increases advantance is in a more loss are similar to the conservence of the loss, realised processors are similar to the conservence of the loss of sole and realised and the access loss are similar to the conservence of the loss of sole and sole accessors are similar to the conservence of the loss of sole and processors are similar to the conservence of the loss of the loss of sole and processors are similar to the loss of the l The special previous disorders control paths control GC2 compliant per brance for build 2 shorts using disconsister first tracks, and disconsister plant available and planteet previous damps. The special previous data for the limit in dependent paths and planteet previous damps. Date 1 of he baselent's control of annual total (2000 percits attained annual contact for 30P tota and dentities angles; and return

To be elastic for any on the second a rooma must have been from all features and along in the last pice to the had instance.

2019 Standard Specification Upcoming Changes

- Working to remove cross-referencing across the structure sections, eliminating conflicts
 - Unique requirements (Such as DT2333 for primary steel members) will b included in the specific structure section
 - Under 105.2 Supplemental Plans and Drawings, adding guidance regarding Fabrication Library Submittal Requirements
- Added requirement of Contractor Certificate of Shop Drawing QC
- Requirement of weekly Fabrication Progress Reports

BUREAU OF

2019 Standard Specification Upcoming Changes

- Added clarification in 506.3.1 regarding steel primary members
- Renamed secondary fabricated items "fabricated bridge components" and revised definition
- Requirements to use an approved fabricator from the Department's APL for primary members, sign structures, and overhead sign supports

STRUCTURE

The Importance of Designer QA/QC "The Big Picture"

Consultant Review Unit

Performs OA reviews on a percentage of the design plans we receive
 Structural Metals and Fabrication QA Inspection Unit

Performs QA reviews on a percentage of the shop drawings we receive

There is a possibility that your design plan and the associated shop drawings may not be reviewed. Any plan errors may not be caught.

The Importance of Designer QA/QC "The Big Picture"

- RFIs will be the mechanism for the Contractor and Fabricator to clarify possible issues with design plans
- There is a potential increased chance of Errors and Omissions
- Keeping this in mind when preparing design plans, and following your firm's QA/QC plan will help you avoid any potential issues

SIRUCTURES



Wind Loaded Structures Initiative Andrew Smith/WisDOT Mark Maday/Jacobs WisDOT Structural Engineers Symposium May 22, 2018

Wind Loaded Structure Initiative

- Primary Purpose
- Transition to LRFD
- •While we are at it
- Process improvement

• Current Challenges

- Multiple processes but one design spec.
- Getting plans in HSI



JACOBS ch2m

Wind Loaded Structure Initiative

•Wind Loaded Structures Include:

- Sign Bridge, Cantilever and Butterfly Sign Structures
- Overhead Sign Supports
- High Mast Lighting
- Associated Support Foundations and Anchorages

• Phase 1 - Evaluation:

Evaluating Process, Policy, Standards, and Specifications
 Develop Recommendations for Improvements and Updates

Wind Loaded Structure Initiative

Phase 2 - Implementation

Goals and Anticipated Work Products:

- Clarified / Updated Process
- Increased Uniformity / Consistency
- Transition to LRFD Design
- Design Manual Updates (BM, FDM, CIM)
- Specification Updates (Standard Specifications and / or STSPs)

Team

 WisDOT Work Group:

 Andrew Smith – PM
 Andrew.Smith@dot.wi.gov

 Alexander Crabtree – Design
 Alexander.Crabtree@dot.wi.gov

 Steve Doocy – Design
 Steve.Doocy@dot.wi.gov

 Jeff Horsfall – Geotechnical
 Jeffrey.Horsfall@dot.wi.gov

 David Nelson – Development
 David1.Nelson@dot.wi.gov

 William Oliva – Oversite
 William.Oliva@dot.wi.gov

 Carla Principe – Fabrication
 Carla.Principe@dot.wi.gov

 Matt Rauch – Traffic Ops
 Matt.Rauch@dot.wi.gov

 Vu Thao – Design
 Vu.Thao@dot.wi.gov



Schedule Kick-Off: June 2017 Phase 1 Completion: August 2017 •Evaluation of Current Process •Stakeholder Outreach •Evaluation of Other DOT Processes •Develop Recommendations: •Improving Uniformity •General Standards Updates •Transition to LRFD Design •Specification Updates •Design Software

Schedule

Phase 2 Completion: June 2019

- Design Manual Updates
- Revised Standard Detail Drawings and Insert Sheets
- Standard Specifications, STSP Updates
- Outreach and Training Presentations

Tasks & Progress to Date

Review of Current Process:

- Solicited Input from All WisDOT Regions and Central Office
- Identify What Works; Best Practices
- Identify Areas for Improvement

Tasks & Progress to Date

Stakeholder Outreach: • Solicited Input From: Sign Structures Suppliers / Fabricators Contractors DOT Designers (BOS) Consultant Designers

Tasks & Progress to Date

Review of Other State DOT's:

Received Input from 10 State DOTs: Florida, Indiana, Iowa, Michigan, Utah, Texas North Dakota, Michigan, Virginia, Washington

Three States Using LRFD for Sign Structure Design: Minnesota, Florida, Washington

Tasks & Progress to Date

Initial Recommendations:

- Revised / Improved Process
 - Clarify Process
 - Emphasize Follow Through / Completing All Steps
- Improving Uniformity
- Clarification / Concise Direction In BM
- Consistency Between Manuals, Standards and Specifications
- General Standard Updates
- Standard for Each Structure TypeInclude Foundations

Current / Upcoming Activity

Recommendations:

- Transition to LRFD Design
- Specification Updates
- Design Software

Phase 1 Completion - Summary Report

It's Not Too Late!

We Welcome Your Input... • Any Ideas, Comments or Suggestions? • Contact Andrew or Any Member of the Work Group

Andrew Smith / WisDOT

Office: (608) 266-0989 Email: <u>Andrew.Smith@dot.wi.gov</u>

Mark Maday / Jacobs

Cell: (414) 975-6129 Email: <u>Mark.Maday@Jacobs.com</u>



Removing Old Structure Over Waterway

Bill Dreher, P.E.

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI May 22, 2018





Page #

Standard Specification
 + 3 choices with varying levels of restrictions

Table of Con



Standard Specification

• Section 203 Removing Old Culverts and Bridges

- 203.3.2.2 Removal Operations: Minimize debris falling onto water surfaces and wetlands as the contract specifies in 107.18 or in the special provisions.

BUREAU OF

Standard Specification

Section 107 Legal Relations and Responsibility to the Public

- Take all necessary precautions to prevent pollution of streams... Conduct work operations to avoid or minimize siltation of streams... Remove existing structures in large pieces, minimizing the number of smaller pieces that drop into the water. Remove all steel and all

STRUCTURES

Standardized Special Provisions (STSP's)

• Designer should coordinate with regional environmental coordinator and DNR to reach consensus on which special to use for the removal.

- The lowest level of care is for situations where there is little
- choice but to drop the structure into the waterway.The highest level of care requires a debris capture system to prevent virtually all debris from falling into the waterway.

BUREAU OF

Standardized Special Provisions (STSP's)

• STSP 203-015: Removing Old Structure Over Waterway

Use this special provision where it is not possible to remove the structure without dropping it, or a portion of it, into a waterway or wetland; and that waterway or wetland is not highly environmentally

SIRUCIURE

Standardized Special Provisions (STSP's)

• STSP 203-015: Removing Old Structure Over Waterway

- This special provision is typically appropriate for removing the following structure types:
 Slab spans, voided slabs

• STSP 203-015: Removing Old Structure Over Waterway

- Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland.
- Remove large pieces of the structure within 36 hou
- The contractor may leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows.

BUREAU OF

Standardized Special Provisions (STSP's)

• STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris

 Use this special provision where it is possible to remove the structure without dropping it, or a portion of it, into a waterway or wetland; and that waterway or wetland is not highly environmentally sensitive.

STRUCTURE

Standardized Special Provisions (STSP's)

• STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris

- This special provision is typically appropriate for removing a structures types except for the following:
- Slab spans, voided slabs
- Cast-in-place girder bridges
- Earth-filled bridges
- Some large trestle bridges

 STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris

This special provision will likely be used for most removals

Standardized Special Provisions (STSP's)

 STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris

- Remove the existing structure in large section:
- Prevent all large pieces and minimize the number of small pieces from entering the waterway or wetland.

SIRUCIURE

Standardized Special Provisions (STSP's)

- STSP 203-020: Removing Old Structure Over Waterway With Minimal Debris
 - Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland.
 - The contractor may leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows.







• STSP 203-025: Removing Old Structure Over Waterway With Debris Capture System

- Consider using this special provision where a waterway or wetland is highly environmentally sensitive.
- Consult with the department's regional environmental coordinator to determine if the affected waterway or wetland is highly environmentally sensitive and if this special provision is appropriate.

BUREAU OF


Standardized Special Provisions (STSP's)

- STSP 203-025: Removing Old Structure Over Waterway With Debris Capture System
 - Remove the existing structure in large section
 - Due to the very sensitive nature of the waterway name, provide a debris capture and containment system that prevents all large pieces and virtually all other debris, including fine particles and slurry, from entering the waterway or wetland.

SIRUCIURES

	515P 201-015 Removing Old Structure Over Waterway	STSP 203-020 Removing Old Structure Over Waterway With Minimal Debris	515# 203-025 Removing Old Structure Over Waterway With Debris Capture System
Environmental Sensitivity of waterway	Not high	Not high	High
Allowable Debris		Prevent all large pieces and minimize the number of small pieces from entering the waterway or wetland	Prevent all large pieces and virtually all other debris, including fine particles and slurry, fro entering the waterway or wetland.
	Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland.		
	Remove large pieces of the structure within 36 hours.		
	May leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows	May leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows	
Removal Restrictions	The second state of the second s	Remove in large sections	Remove in large sections
Applicable Structure Type	Where it is not possible to remove the structure without dropping it	Where it is possible to remove the structure without dropping it, or a portion of it, into a waterway or wetland	
	For removing slab spans; voided slabs; cast-in- place girder bridges; earth-filled bridges; large trestle bridges.	For removing all structures types except for slab spans; voided slabs; cast-in-place girder bridges; earth-filled bridges; large trestle bridges.	





How Do I Choose?

- Review all 3 specials and coordinate with regional environmental coordinator and DNR to reach consensus on which special to use for the removal.
- The special provision language is intended to be a reasonable starting point; however, it may need to be expanded to address additional DNR or other concerns.

STRUCTURE

How Do I Choose?

- For unique or difficult removals, consult with the contracting community to assess costs and the feasibility of a particular removal technique.
- Consult with the department's regional environmental coordinator to determine if the affected waterway or wetland is highly environmentally sensitive and which special provision is appropriate.
- Don't make the decision w/o good information!



Timeliness of Consultant Plan Submittals

Najoua Ksontini, P.E.

Consultant Review and Hydraulics Supervisor

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI <u>May 22, 2018</u>

BOS Plan Submittal Timeline Expectations

• Preliminary Structure Plans:


- Project schedule should allow for a minimum of 60 days for BOS review. Adequate time for comment resolution, design, and final plan preparation prior to final plan submittal will determine the date that preliminary plans need to be submitted.
- For the purpose of tracking, BOS considers preliminary plan submittals to be late if received less than 3 months prior to the PS&E date.

STRUCTURE

BOS Plan Submittal Timeline Expectations


• Final Structure Plans:


 BOS requires that final structure plans, structural computations, and other pertinent documents are submitted 2 months prior to project PS&E date



<text><text><figure>







Why are past-deadline final plan submittals concerning to BOS


- We have a limited number of reviewers
- We have limited review time
- When plans are late, we have less time to work through issues with the designer
- We would like to provide input and QA reviews to as many submittals as possible
- Number of final structure plan submittals average about 120 per PS&E

SIRUCTURES

On-Time Plan Submittal Improvement Form

- In March 2016, BOS implemented a new policy requiring designers to submit a form documenting the reasons for past-deadline final structure plan submittals.
- BOS categorized the reasons for past-deadline final structure plan submittals.

STRUCTURE



Next Steps

- Designers- Please continue to communicate with BOS when project schedules are accelerated or advanced
- BOS- Will discuss with Regional offices impact of accelerated schedules on structure review timelines

SIRUCIURES



Automation, Policy & Standards

David Kiekbusch Structures Development Supervisor

James Luebke Structures Development Engineer

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI

BUREAU OF SIRUCIURES

New standards in past two years

- 9.01 Structure Backfill Limits and Notes 9.02 – Structure Backfill Limits and Notes 2
 9.03 – Wing Fill Sections at Wing Tips • 13.08 – Pier Cap Reinforcement Details 14.11 – MSE Wall – Panel and Block Facing
 14.12 – MSE Wall – Wire Faced 1
 14.13 – MSE Wall – Wire Faced 2 • 17.03 – Edge of Deck Flashing • 27.10 - Steel Expansion Bearing Details • 30.22 – Conduit Details and Notes
- 40.40 & 40.41 Moved A4 abutments to Bridge Rehabilitation

Notable Bridge Manual text changes

• Extensive rewrite of Chapter 45 – Bridge Rating (January 2017)

- Entire chapter rewritten
- Four new rating examples for LFR
 Reinforced Concrete Slab

Bridge Manual text changes (continued)

AASHTO 3.8 – Wind Load: WL and WS

- Extensive update to Chapter 13 Piers, including examples (July 2017)
 - Wind speeds for various limit states
 - Wind pressure is a function of the wind speed, exposure condition and bridge elevation above the ground or water surface
 - WisDOT policy items to simplify wind loading for most bridges

BUTEAU OF





MASH 2016

Required for all lets after December 31, 2019

• 42SS parapet required for:

- All Interstate structures
- All STH and USH with a posted speed ≥ 45 mph
- Railings Type 'M' and Types 'NY 3' and 'NY 4' are TL-2
- Good for most local and collector roads with design speeds ≤ 45 mph
 Trying to get Type 'M' and Types 'NY 3' and 'NY 4' to TL-3
- If TL-3 can't be achieved, then a new railing (could be TL-4



Bridge Maintenance and Bureau of Project Development Coordination

Maintenance Items

Erosion Issues

Design Considerations



Bridge Maintenance Coordination

Discuss Issues

- Wing Wall Grading
 Slope Paving Repairs
 Approach Details

Design Considerations











Wisconsin Department of Transportation




_






Wisconsin Department of Transportation



		_





Wisconsin Department of Transportation


Structural Approach Slabs


• Guidance:

 The geotechnical engineer should evaluate approaches for settlement susceptibility and provide recommendations for mitigating settlements prior to approach placement.

I: 01/18

 Structural approach slabs are not intended to mitigate excessive approach settlements.







Structural Backfill

- Pay Limits
 Not Necessarily Representative of Actual Limits
 Payment Purposes Only Backfill placed beyond pay limits or exceeding plan quantities shall be incident

Precast Piers

SIRUCTURES


Past Usages

Rawson Avenue - Required
Rawson Avenue - Required
IH 39/90 - Contractor's Option (noted allowance)
Sign Structure Column - Contractor Requested



STRUCTURES







Local Program bridges

 Railings and parapets to be MASH compliant:
 Chapter 30 of Bridge Manual gives a MASH TL value for all railings and parapets

Local road design speed versus posted speed (or no posted/statutory speed)
 Will be working with Bureau of Project Development to project Development to

while be working with Bureau of Project Development to provide guidance

Bridge drainage

Desirable to maintain 0.50% profile for drainage, with solid parapets (WisDOT preference)

 Investigating exceptions to the 0.50% criteria, especially for shorter bridges.

Future updates

- July Bridge Manual updates
 - Text with regards to AASHTO 8th Edition (Examples in January 2019)
 - Renumbering of Section 5 Concrete Structures (461 references in BM!)
 - New method for prestressed girder shear
 - New steel girder simplified field splice design procedure
 - $\frac{1}{2}$ filler adjacent to $\frac{1}{2}$ bearing pads

• Other

- Insert sheets are being cleaned up available as ready
- Insert sheet(s) with available cells

Automation

• WiSAMS – Wisconsin Structures Asset Management System

- Automated system to assist with determining the most appropriate course of action for structure maintenance, and eventual replacemen during its life cycle
 - Planners like it, bridge maintenance staff is a little more skeptical...
- Data Warehouse/Business Intelligence
 - Centralized location for all data related to WisDOT structures
 - Used to support important business activities
- BIM for Bridges and Structures



MSE Wall Specifications


Updates

Pay Limits (Plan Values)


Shop Drawing Submittal





EUREAU OF
















My Favorite Complex Structures

Andrew Smith

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI May 22, 2018

The "Home Sweet Home" Bridge

Category: Movable Bridge

• First Movable Bridge constructed with ABC techniques.

• Bridge operator lives on site



SIRUCIURES

Bridge over Achievement Gap

Category: Box Girder Bridge

- Built by Red Neck and Sons
- Cost: 4 bottles of whiskey
- No children were hurt during construction



BUREAU OF SIRUCIURES

Load Rating My Favorite Complex Structures

Andrew Smith Load Rating Engineer


2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI May 22, 2018 _____







What is Considered Complex?

WisDOT Bridge Manual 45.3.11






_











What is required if a structure is categorized "complex"?

Generally... That these complexities are considered in a Load Rating Analysis

Specifically (45.3.11)...

- 1. Refined analysis is required
- 2. Must consider certain load effects (e.g. from curvature and skew)
- Submit Refined Analysis Rating Form (on website)
 Flexible format provide key information

STRUCTURES

What is required if a structure is categorized "complex"?

Generally... That these complexities are considered in a Load Rating Analysis

Specifically (45.3.11)...

- 1. Refined analysis is required
- Design of new "complex" structures will be "refined" by default
- 2. Must consider certain load effects (e.g. from curvature and ske

What constitutes "refined" analysis?

- National resources: AASHTO, FHWA "Manual of Refined Analysis" (inprogress), NSBA G13.1
- Generally considered to be FEA (2D vertical/horizontal, PEB, 3D)
- Chp 45 not dictating how to perform refined analysis
 May depend on project requirements
- Refined ≠ Complex
- e stuctors

BUREAU OF

What is required if a structure is categorized "complex"?

Generally... That these complexities are considered in a Load Rating Analysis


Specifically (45.3.11)...

- 1. Refined analysis is required
- 2. Must consider certain load effects (e.g. from curvature and skew) Already in national guidance
- 3. Submit Refined Analysis Rating Form (on website)

STRUCTURES

Torsion

- Caused by eccentric loading (i.e. structure on a horizontal curve)
- Torque is imparted to girders
- Results in additional normal and shear stresses (on top of those imparted from primary bending)
- Box girders and plate girders handle this differently



Load Shifting

- Global overturning resisted by force couples
- Additive effect to some girders, relieving effect to others
- Analogous to overturning (moment, eccentric load) in pile groups
- If curve is slight enough, the effects of curvature on the <u>gravity loads (i.e.</u> "load shifting") can be neglected see LRFD 4.6.1.2.4

SIRUCTURES

		Ove	nent on System to Curvature tary Verfical Load lystem	Ţ		
1		l	_[_][-		—][
***	Constitution to Vierfoor(const	Û	Û	Û	Û	Û
22	Loads due to et an Eustern	Û	Û		0	Û
11	nder Lauste Stanffast Hindta plan Mornert I	0	Û	Û	Û	ļ

Flange Lateral Bending


- Flange Lateral Bending due to curvature effects must always be accounted for per LRFD
- Effects of Skew on *ft* are more variable and difficult to predict
- Investigate effects with discontinuous cross-frames with skews greater than 20°
- *fe* due to skew determined by:
 - Directly (3D FEM)
 Approximate eqns. and recommended values
 see C6.10.1


SIRUCIURES

What is required if a structure is categorized "complex"?

Specifically (45.3.11)...

- 3. Submit Refined Analysis Rating Form (on website)











What are the benefits?

Consistency

- Repeatability/Documentation (Refreed Analysis Rating Form)
 For timely responses in permitting requests



SIRUCIURES

Performing a load rating on a complex structure?


Please contact rating unit:

Andrew Smith Andrew.Smith@dot.wi.gov 608-266-0989

Josh Dietsche Joshua.Dietsche@dot.wi.gov 608-266-8353

Self-Consolidating Concrete for Prestressed Girders Steven Doocy, P.E.


2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI <u>May 22, 2018</u>



Research Team

- Researchers
- South Dakota State Universit
- Industry
- County Materials
- Spancre
- WHRP Team
 - WisDOTUW-Madison

















Specification

• SPV for SCC

- Specified testing, material and construction information for SCC

BUREAU OF BIRUCIURES




Impleme	entation
B-17-2	223/224
 Looked for longer structure with deeper girders 10 – 54W girders @ 127' long (twin structures) 223 – mandatory SCC 224 – optional SCC 	



li	mplementation	
Camber • Actual = 4.00"	Current Data	
 Plan = 4.28" Compressive Strength f'_{cl} (actual) = 7,900 psi f'_{cl} (plan) = 6,800 psi 	i f' _c (actual) = 12,500 psi f' _c (plan) = 8,000 psi	
	SCC for Prestressed Girders	16


Success!!

- Implemented on twin structures
- Use for all girders
 Complex concrete pours/tight rebar cages
 Substructures
 Other?



Miscellaneous Geotechnical/Structural Topics Jeff Horsfall BTS – Geotechnical Engineer 2018 WisDOT Structural Engineers Symposium

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI May 22, 2018




Geotechnical/Structural Topics

- Geotechnical Manual
- Consultant Submittals
- Pre-boring in Consolidated Material (Intermediate GeoMaterial-IGM)

Geotechnical Manual

• Developed in April 2017 and published on the DOTNET

http://wisconsindot.gov/Pages/doing-bus/eng-consultants/cnsltrsrces/default.aspx



Section 7-1 General
Section 7-2 Foundation Types
Section 7-3 Foundation Analyses and Design
Section 7-4 Subsurface Investigations – All Structures
Section 7-5 Bridges
Section 7-6 Retaining Walls
Section 7-7 Box Culvert, Rigid Frame and Plate Arches
Section 7-8 Ancillary Structures
Miscellaneous Geotechnical/Structural Topics 6

Consultant Submittals

Special Provisions template gives:

I. SOILS AND SUBSURFACE INVESTIGATIONS

Add gINT soil boring logs and soils laboratory data to the following email addresses.

DOTDTSDGeotechnicalgINT@dot.wi.gov DOTDTSDGeotechnicalSirLab@dot.wi.gov

BUREAU OF

Pre-boring in Consolidated Material (Intermediate <u>G</u>eo<u>M</u>aterial-IGM)

550.3.9 Pre-Boring

550.3.9.1 General

(1) Pre-bore holes to the depth the plans or special provisions require. Submit written requests for pre- boring not required under the contract to the engineer for review and approval. Do not impair the capacity of in-place piles or damage adjacent structures by pre-boring operations.

SIRUCIURES

550.3.9.3 Pre-Boring in Rock or Consolidated Materials

(1) For round piles, pre-bore holes at least one inch larger than the pile outside diameter. For other shapes, pre-bore holes at least one inch larger than the greatest diagonal pile section dimension.

(2) Case holes as necessary to prevent introduction of unconsolidated material. Seat the casing firmly into the rock or consolidated material surface. Clear debris from the pre-bore hole before installing the pile.

(3) Firmly seat piles after preboring and backfill within the rock or consolidated material with a cement grout. Remove the casing, backfill the piles with sand or other engineer-approved material, and dispose of excess material.

(4) Do not blast without the engineer's approval.

Pre-boring in Consolidated Material (Intermediate <u>G</u>eo<u>M</u>aterial-IGM)

Intermediate GeoMaterial-IGM


- Cohesive IGMs exhibited unconfined compression strengths between 10 ksf to 100 ksf
- Cohesionless IGMs exhibited blow counts greater than 50 blows per foot (bpf) using a Standard Penetration Test

BUREAU OF

Project Illustration

B-13-831/832 USH18/USH 151 over CTH PD Structure Consultant AECOM Geotechnical Consultant SOILS & ENGINEERING SERVICES, INC.






				- and - a company	
			PODELT-CRADED SAND (SP) PINE		
- 19-1		421-	WIDLN DENSE TO DENSE PELATINE RENSITY.	4.0 10.00	930
0			STRATETICS, WTH SET OF LAND LEAN	10 00 00	
BTI Sel HTI BUT, SH THE TO-			CLAY ICLI LUMIES AND SCANS	-0 00 [3]	
Charter research, sets disattle TO Life					920
RADIETY MEL BRINS FLL DRIVED	THE WELL SEE MEANING IN LT	1	POPUT-STADIO SAND WITH SUT (SP-SW)	-0.03	
	8.9% I		THE CRANED, NON-PLASTIC TO LON	-17 cm	
HOLE CLAP CO. MEXA PLATEOTIC BONK	1	400 -	PLASTICITY PLAST, MORE WORT TO MET.	37 126	
wer project, that the land-of test	-in 🗹	1	DENSE FELATIVE DENSITY, WITH OCCASEINAL	14 (28)	
111 87 7 6496 7 1-7-6	-d xh		THE SETS SAND ISH, FINE POSTLY-GRADED	2	
THE LET'S LOAD WITH WANTE CONTRACT TO CONTRACT TO CONTRACT TO LOAD TO CONTRACT TO LOAD TO CONTRACT TO LOAD TO CONTRACT TO CONTRACT.	Con I	- 191 -	SAND ISPL AND SANEY SET IND SEAMS AND LAYERS	5-43 HSI	
and More, wild? To will, wildle block To willy			CLATET SAND GO THE GRAVEL HEALN PLASTERT!	101	900
INT DRAFT PEAR TO ATT, SACK THE THE T	1.0		THES. REDOWN TO DATE BOOK WAST TO HET	5 W	
THE STATE CORRESPONDENCE AND	1 m 1	- 180 -	MERIN DONE FELATIVE GENERAL LITTLE GRAVEL	-27 3 T	
THE GROP POIDS SOME ME LITTE				2016. 0216-1	
FIRET-IFADD THE RTH TET OF-THE DIMEDLE.	4 00			-100/6* (64/6*)	
TO NET, NEEKN LEVIE RELATER LEVIES, NEW			SANDSTONE SUIDITLY TO MODERATELY NEATHERIES		
SCLARENA, FRE SLTT SAID DAL THE REALT-INDES.	- # 69 🔛		RECORPTION AND GRATER-WRITE, WORT TO HET,	10/0" 04/0"1 10/0" 4/00"1	
SHELPLINE SHELSELSELSHOLDELS	- a a 🖬 🕴		VER DOLE PEAKING DOLETY SANCITORS SUCHALLY TO MARKATELY		880
RUND + UNC 11 21-7 419 17-7 UNC-	4.00 1	- 90 -	KEATERED, URF BROWS, WEST TO WELL	-24 (5)	
111	*** E		WANIN SCALE BELOTHE SEASEY		
181	5.0				
		- 10			810
	40 2				
101	- • 🗑				
	- 00 I	- 10 -			860
	-7 (A) 1	12 C C C C C C C C C C C C C C C C C C C			
III MERCI-GHED LAG (PL THE	10 000				
III (NAME), LENT BROWN, MORT TO HET.	10 12.20	12			
WEEN ODER TO DEVIC RELATED BERITS.	THE ROAD & CONTRACT IN SHEET IN				850
STRATED, WENGEL AND	ne mort o constiti to bitt P				
					840
SIRUCIURES					
		Miscellaneous Ge	otechnical/Structural Topics		




Project Team Foundation Discussion

Options

H-piles driven using modified Gates (resistance factor = 0.50) H-piles driven using Pile Driving Analyzer (resistance factor = 0.65) Pre-bored H-piles with a Static Load Test (resistance factor = 0.80)

















STRUCTU














Miscellaneous GeotechnicalStructural Topics 29	










BOS Overlay Policy

James Luebke

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI May 22, 2018







• Further Developments


- Polyester PolymerAsphaltic with Membrane
- Further Guidance
 - WiSAMS (Wisconsin Structures Asset Management System)
 Bridge Manual
 Standard Details
 Specifications


SIRUCTURES






















Polyester Polymer Overlay Usage

• Decks in Good Condition

- Less than 15 years* old deck
 General Criteria

 - Traffic Restrictions
 High Traffic (AADT > 20,000)
 Remaining life > 20 years

BUREAU OF SIRUCIURES

<u>New System</u> <u>Restrictive Usage</u>

- Polyester Polymer Overlay Usage
- Decks in Good Condition
- General Criteria
 - Traffic Restrictions
 - High Traffic (AADT > 20,000)

Remaining life > 20 years STRUCTURES




- Distressed areas < 2%</p>
- Deck age < 10 years*No General Restrictions

Overlay Policy NPUT: Structure Type Structure Response AADT Design Speed Chloride Content Concrete Permeability Concrete Cover Lane Restrictions Ratings Funding Content Efficiencies Overlay Selection Resources Bridge ManualBOS Funding Contract Efficiencies Existing Overlay OUTPUT: • Low Slump Polymer Overlay Coordination BUREAU OF





































































3D Design & Modeling, BIM for Bridges and Structures Danielle De Tennis & Adam Swierczek

2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI



What is our goal with BIM?

• Create an open data exchange between all involved parties for the lifecycle of the structure

- Software-independent solutions
 Streamline data exchanges
 Eliminate data entry errors

BIM in BOS Design

• Preliminary Design

- Create initial approximate structure geometry
 Improve geometry coordination with roadway



BIM in BOS Design

Hydrology & Hydraulics

- ctors/flowpaths in X and Y more accurate information itter bridge sizing, re placement and skew
- ed accuracy of scour on parameters


- el complex floodplains sumptions inherent to

SIRUCIU

BIM in BOS Design

• Final Design

- Single source of truth throughout design
- Improve process for design iterations and late design changes





BIM in BOS Fabrication

- Move towards 3D model-based shop drawing submittal and review


 - Many fabricators already create 3D models to generate 2D shop drawings Generating and fixing up these plans take up a lot of time.
 They are looking into ways to eliminate the need for 2D plans, or move them closer to the end of the process so the plans don't need to be regenerated so many times.
- BOS is planning a 3D Fabrication pilot project with a steel structure


BUREAU OF STRUCTURES

BIM in BOS Bridge Management


- Looking to add 3D models to
 - Nodels are generated from data already entered in HSI
 Inspectors can document defects directly on the model
 Possibility to store design models & as-built models in the factors.














IH 94 North South Project Overview

Frank Pritzlaff, P.E.


2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI

IH 94 North South **Program Overview**

Current Scope of Work

- Accelerated Schedule
- Quantity Highlights
- Staging Concept
 Unique Roadway Elements

STRUCTURES







Scope of Work – Loo	cal Rehab
TH 20 • February 2018 Let, June 2018 Completio TH H • March 2018 Let, June 2018 Completion TH A • March 2018 Let, June 2018 Completion	

IH 94 North South Scope of Work – Development

• CTH KR • CTH H

Braun Road

International Drive


Wisconn Valley Way
 All Construction Slated Between
 2018 and 2021



IH 94 North South Quantity Highlights – South/Central Segments Only Common Excavation 844 000 CY

Roadway Embankment	— ~ 1,414,000 CY
Base Aggregate Dense	— ~ 302,000 CY
Select Črushed Material	— ~ 521,000 CY
Concrete Pavement 12-Inch Special	
Bridge Deck	
Retaining Walls	— ~ 130,000 SF
BUREAU OF H94 North South	100

IH 94 North So Staging Concept (Acc				
Two lanes in each direction (2/2 traffic) 6 months	06/18 to 11/18			
• Three lanes in each direction (3/3 traffic)				
6 months split bi-directional	12/18 to 05/19			
 6 months bi-directional 	06/19 to 11/19			
Reduces construction from 30 months to 18 months				




IH 94 North South **Unique Roadway Elements**

- Compressed/Accelerated Construction Schedule
 Stage 3 Construction Through Winter
 Approximately 13' Profile Grade Change at CTH KR/Braun Road
 Multiple Adjacent Public and Private Projects
- CTH K Crossroads, IH 94 Frontage Roads, Wis 45 Rehab, Wis 20/CTH C Roundabout, Foxconn Development, etc.
- Items Left in Place from Previous Prep Contract
 On Site Batch Plant/Crushing/Staging Locations


IH 94 North South Structures

Aaron Bonk, P.E.

Bureau of Structures Design Supervisor IH 94 NS Structures Lead 2018 WisDOT Structural Engineers Symposium University of Wisconsin-Madison Union South, Madison, WI









IH 94 NS Structures Unique Aspects of Design


- Typical prestress girder and slab span bridges...
 - Except for the condensed delivery schedule and "standards" updates required
- Typical vertical underclearance requirements...
- Typical pier design...
- Except for requirement not to preclude contractor precast option
 Partial depth precast prestressed deck panels required


BUREAU OF SIRUCIURES

IH 94 NS Structures Foxconn Area Impacts to Structures

 \bullet Full Redesign for 2 Interchanges and 2 Overpasses (14 State Structures and 10± Local Structures Impacted)

Bridge Configurations In Flux Until Early 2018





IH 94 NS Structures Pier Design

- Construction Schedule Dictated ABC (Precast Pier) Option
- Multi-column Piers Designed as CIP, but not to Preclude **Contractor Precast Option**

BUREAU OF BIRUCIURES




1017424 aar 105-54
THE CONTRACTOR MAY FURNISH PRECAST CONCRETE PER IN LEU OF THE CAST-N-PLACE PER WITH THE ACCEPTANCE OF THE SAMP DRAWNOS BY THE STRUCTURES DESIGN SECTION. THE PRECAST CONCRETE PER SHALL CONFORM TO PRECAST DETAILS IN CHAPTER 1 STANDARDS OF THE CURRENT MISCONSING WITH THE EXCEPTION OF METHOD OF PAYWENT, PAYWENT FOR THE, PRECAST PRE SHAL BE BASED ON THE QUINTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE "TOTAL ESTIMATED QUANTITES AND PRICES BUD FOR THE (TEMS) LISTED IN THE CONTRACTOR TO DETEORNE CAST HERE AND RUCTURE LEVELONG TO REAL REQUIRE SMALL BE 4***********************************

IH 94 NS Structures Partial Depth Precast Prestressed Deck Panels


- Construction Schedule Dictated ABC (Partial Depth Precast Prestressed Deck Panels for Girder Bridges) Requirement
- Bridges Designed to Require Panel
 Use



Refined/Updated Chapter 17.10
Bridge Manual Details
 Structures









Wisconsin Department of Transportation

Strengthening Program for Local Load Posted Bridges

Josh Dietsche Supervisor – Bridge Rating/Management Unit

WisDOT Structural Engineers Symposium Madison, WI

Presentation Overview

- Load Postings on the Local System
 - Load PostingsSHV Load Posting Evaluation
- Strengthening Program
 - Program ConceptOverview of the Local Inventory
- BOS Efforts for Repair and Rehab
 Assessing Candidate Bridges
 Repair Methods

STRUCTURES








Bridges are load posted when analysis shows they can no longer safely carry legal-weight traffic.

• What is "legal weight?"



Load Postings: Federal Bridge Formula

• Federal Bridge Formula (FBF) provides a standard to control spacing of truck axles/weights...to make sure the bridge was designed to support what can legally cross it.



Load Postings: Posting Vehicles • Based on the FBF, AASHTO has an established suite of posting

> OO }easte

Ĩº ŀ

Ϋ́́

• Wisconsin has two state-specific posting vehicles.

16 16 16

vehicles

BUREAU OF SIRUCIURES € I



<text><list-item><list-item><list-item><list-item><list-item><list-item> Other States and thed that states incorporate SHVs into their posting analysis by December 31, 2017 • Why are SHVs an issue? • Legal-weight... • What are SHVs?



SHV Load Posting Evaluation: Results

So what was the outcome?
 Some new poslings
 Some lower load poslings

BUREAU OF

Local-Owned		Owned
Posting Level	Current	w/ SHV
40 ton or greater	372	281
35 ton	52	34
30 ton	11	44
25 ton	17	139
20 ton	100	146
15 ton	110	131
10 ton	71	73
5 ton	34	39
Less than 5 ton	6	6
TOTAL:	773	893



Strengthening Program: Overall Concepts

- The SHV evaluation effort highlighted load posting on the local system
- Load postings are implemented for safety purposes...
 ...but they restrict the flow of freight
- With support of WisDOT upper management, BOS looks for methods to eliminate postings, when possible
- Strengthening Program For Local Load Posting Structures

Strengthening Program: Overall Concepts

- Work with local owners to implement cost-effective, stream-lined process to repair bridges and remove postings
- BOS to provide engineering and oversight for repairs
- Use local crews (with assistance from WisDOT) to perform repairs

BUREAU OF

Overview of the Local Bridge Inventory

- The local system is...different...than the state system.

 - TimberConcrete T-girder

STRUCTURES






































BOS Efforts for Repair and Rehab

Make girder composite with slab

- Several installation options available; would be site dependent
 Girders assumed to be non-composite if plans are not available
 First step. field verify if studs already exist





BOS Efforts for Repair and Rehab




C. Locate Strips/Check Surface D. Clean and Prepare FRP Strips G. Roll Out to Ensure Total Contact

BUREAU OF SIRUCIURES










BOS Efforts for Repair and Rehab

- Refined analysis goes above and beyond the routine or traditional methods of analysis
- Often involves a 3D model of structure
- Takes advantage of a more true live load distribution (less simplifications)



BOS Efforts for Repair and Rehab

- Enormous amounts of data
- Processing data takes most of the time
- Processing required to obtain useful information for design or load rating purposes
- Requires more judgment,
 assumptions; less conservative

SIRUCIURES

BOS Efforts for Repair and Rehab

• Other options (more case-specific):

- Removing overburden
- Install external post-tensioning
- Add additional substructure u
- New deck
- Load testing
- Enhanced inspection for better information (NDE methods)
- Other...

