

# Signals, Lighting & ITS Installation and Inspection

## Part 6: ITS

Dean Beekman, P.E. Statewide ITS Engineer <u>Dean.Beekman@dot.wi.gov</u> 414-227-2154



### ITS (Intelligent Transportation System)


- CCTV- Closed Circuit Television Cameras
- RM Ramp Meters
- DMS Dynamic Message Sign
- FOC Fiber Optic Cable
- SDS System Detector Stations
- RG Ramp Gates



- Perform ITS work with onsite assistance and under the supervision of a qualified **Field System Integrator.**
- Responsible for overall system functionality, setting up progress meetings, documentation, as-builts, manuals, and testing procedures.
- Perform all work for fiber optic terminations, splicing, and testing with Certified **Fiber Optic Technician**.



#### **ITS General Requirements**





#### **ITS General Requirements**

Installati	on and Testing Docum	entation		
Instanati	on and resting Docum			
This Test Procee	ture will test the DeepBlue Sensor Assem	blies installed in the field.		
DO HOT DET LU C		TAPCO	Bluetooth	Sensor Installation Forr
PROJECT DETAILS	2	TRAFFIC & PARKING CONTROL CO., INC.	Didecooli	Sensor Instantion For
Cabinet #:	WDS-0139			
Project #:	<u>5569-00-72</u>	WDS Location	n ID	WDS-0139
Contractor:	Westphal	Installation Location ID		WDS-0139
Drawing Page #:	340	Rough Location		USH 14 @ Morse St
Tested By:	Dave Bentfield	GPS Latitude		42.717931
Date:	2/9/2016	GPS Longitude		-88.98816
		Bluetooth Sensor IP		192.168.121.3
SENSOR DETAILS		Modem or Sw	vitch IP	166.165.80.230
Rough Location:	USH 14 @ Morse St	Remote Acce	ss IP	166.165.80.230:8318
Decimal Latitude:	42.717931			
Decimal Longitude: -88.98816		Detector Serial Number		20121191
Remote Access IP:	166.165.80.230:8318	Modem or Sw	vitch Serial Number	MB19D4B1HB
Serial Number:	20121191			
	(b)	Project ID		5569-00-72
Bluetooth Documentation		Contractor		Westphal



- Pre-Construction Work Provide equipment list, catalog cut-sheets, and drawings within 28 days after notice of award to the engineer. The engineer will review the equipment list and drawings within 30 days of submittal.
- **Post-Construction Work** Submit 5 copies of ITS documentation including
  - Operator's and Maintenance procedures manuals
  - Cabinet fiber optic wiring diagram
  - As-built drawings and Equipment inventory list



- List of State-furnished equipment is listed in the Control of Materials section of the specials.
- WISDOT typically provides cameras, camera poles, cabinets, microwave detectors, Bluetooth detectors, solar assemblies, dynamic message signs, fiber optic cable, termination panels, ramp meter controllers, wireless radios, various antennas, cellular modems, Ethernet switches, and optics.
- Proven equipment, good pricing, ease of maintenance and troubleshooting, control of ordering, and simplifies contract documents.
- Typically WISDOT or TAPCO will have the equipment.



#### **CCTV Installations**

- WISDOT provides camera, pole, lowering system, anchor bolts for base, and cabinet.
- Things to watch for:
  - Complete form DT2321
  - Anchor rod and conduit placement in concrete footing.
  - Lowering system and wireless radio placement.
     Don't block important camera views.







#### **CCTV Installations**





#### **CCTV** Installations

# Make sure your electrical contractor puts rat screen on the camera poles!







- WISDOT provides ramp meter controller, loop cards, and cabinet.
- Things to watch for:
  - Proper placement of loops, signal heads, advance flashers, signing, and pavement markings.
  - Cable type and routing.





#### **Ramp Meter Installations**

#### Advance Flasher Assembly




#### **Ramp Meter Cabinet**





#### **Ramp Meter Installations**





- WISDOT provides DMS and cabinet.
- Things to watch for:
  - Proper placement of sign over lanes and proper clearance.
  - Connection of walk-in DMS to sign bridge. Structure plans typically account for vertical I-beams between DMS and sign bridge, however, there can be confusion.
  - Conduit placement in footings for power and communication.
  - Conduit location and type for use on structure.
  - Slight angle/offset for side-mount versions.



#### Walk-in DMS Installations





#### **Cantilever Arterial DMS Installations**





#### Side-Mount DMS Installations





#### **Hybrid DMS Installations**






- WISDOT provides microwave detector, Bluetooth detector, cabinet, and solar assemblies, if required.
- Things to watch for:
  - Proper placement of pole and height of detector. Avoid ditches. Be aware of snow plowing operations.
  - Median barrier wall and other obstructions can cause detection problems.





#### **SDS Installations**








#### **SDS Installations**



Bluetooth detection Providing real time travel times or freeways and arterials





- WISDOT will provide solar panels, batteries, charge regulator, and cabinet.
- Things to watch for:
  - Make sure solar panel array faces south.
  - Check for proper mounting and fastening of equipment.
  - Wiring should be neat and have drip loops.



#### **Solar Powered System Installations**





#### **Solar Power System Installations**





#### **Cabinet Installations**

- WISDOT will provide the cabinet and most of the equipment inside of it.
- Things to watch for:
  - Install pole-mount cabinets 3' above finished grade.
  - Fasten securely with stainless steel straps.
  - Plug conduits with duct seal.





- Observe proper construction techniques to keep water from entering cabinet.
- Mount cabinet (door) away from traffic flow.
- Make sure ID plaque is installed.
- Wiring and equipment should be neat and orderly.





- Be aware of final grade in relation to concrete cabinet base.
- Install required conduits in concrete bases.
- Plug conduits with duct seal.







- WISDOT will provide.....nothing.
- Things to watch for:
  - Proper placement of bases.
  - Check gate arm length and final position when closed.
  - Be aware of sidewalks, traffic lights, drainage features, and other conflicts.





#### **Ramp Gates**

- Adjust gate arm guides so they rest against gate arm when fully open.
- Verify solar powered units are wired properly.
- ID plaques should be installed for each gate arm.
- Backfill around bases to prevent snagging if hit.





#### **ITS** Questions

- 1. The Field System Integrator is responsible for:
  a.) Setting up progress meetings b.) Turning in as-builts
  c.) Performing test procedures d.) All of the above
- 2. The list of state-furnished materials is included in the Wisconsin Standard Specifications.

True False

• 3. The two most important things you can do to protect against rodent damage is to install:

and

#### **Questions?**



## **ITS Contacts**

- Dean Beekman BTO/Statewide
- Randy Asman NE Region
- Jeff Madson BTO/SE Region
- Kyle Hemp SW Region
- Ron Johnson NC Region
- Chad Hines NW Region