



# Wisconsin Department of Transportation

December 16, 2015

## Division of Transportation Systems Development

Bureau of Project Development  
4802 Sheboygan Avenue, Rm 601  
P O Box 7916  
Madison, WI 53707-7916

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #15: 8745-00-71, WISC 2016 012**  
**STH 35 – CTH A**  
**Nemadji River Bridge B160022**  
**CTH C**  
**Douglas County**

### Letting of January 12, 2016

This is Addendum No. 01, which provides for the following:

#### Schedule of Items

Revised Bid Item Quantities						
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total	
643.0420	Traffic Control Barricades Type III	DAY	600	150	750	
643.0705	Traffic Control Warning Lights Type A	DAY	1,200	300	1,500	
643.0900	Traffic Control Signs	DAY	240	60	300	
643.3000	Traffic Control Detour Signs	DAY	7,440	1,860	9,300	

#### Plan Sheets

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
11	Miscellaneous Quantities: Updated Traffic Control Quantities
12	Miscellaneous Quantities: Updated Traffic Control Quantities

#### Other

Revise the contract time for completion from 30 working days to 40 working days (an increase in 10 working days).

**Schedule of Items**

Attached, dated December 16, 2015, are the revised Schedule of Items Pages 5 and 6.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 11 and 12

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

Addendum No. 01  
ID 8745-00-71  
Revised Sheet 11  
December 16, 2015

**SIGN REMOVAL CATEGORIES**

STATION	TYPE II	EACH	638.2602	638.3000
REMOVING SIGNS REMOVING SMALL SIGN SUPPORTS				
Sta. 23+89	LT (Object Marker)	W5-52L	1	1
Sta. 23+89	RT (Object Marker)	W5-52R	1	1
Sta. 26+50	LT (Object Marker)	W5-52R	1	1
Sta. 26+50	RT (Object Marker)	W5-52L	1	1
<b>TOTAL</b>			<b>4</b>	<b>4</b>

**642.5001 FIELD OFFICE TYPE B (CATEGORY 0010)**

LOCATION	EACH
PROJECT 8745-00-71	1

**643.0100 TRAFFIC CONTROL (CATEGORY 0010)**

LOCATION	EACH
PROJECT 8745-00-71	1

**TRAFFIC CONTROL BARRICADES, LIGHTS, AND SIGNS (CATEGORY 0010)**

LOCATION	EACH	DAYS	EACH	DAYS	EACH	DAYS
PROJECT 8745-00-71	10	75	20	75	4	75
<b>TOTAL</b>	<b>750</b>	<b>1,500</b>	<b>1,500</b>	<b>300</b>		

**643.2000 TRAFFIC CONTROL DETOUR (CATEGORY 0010)**

LOCATION	EACH
PROJECT 8745-00-71	1

**628.6005 TURBIDITY BARRIERS (CATEGORY 0010)**

LOCATION	SY
Sta. 25+28	65
Sta. 26+01	85
Undistributed	40
<b>TOTAL</b>	<b>190</b>

**628.7504 TEMPORARY DITCH CHECKS (CATEGORY 0010)**

LOCATION	LF
UNDISTRIBUTED	50

**634.0612 WOOD POSTS 4X6 INCH X 1.2 FT (CATEGORY 0010)**

STATION	LOCATION	EACH
Sta. 23+89	LT (Object Marker)	1
Sta. 23+89	RT (Object Marker)	1
Sta. 26+50	LT (Object Marker)	1
Sta. 26+50	RT (Object Marker)	1
<b>TOTAL</b>		<b>4</b>

**637.2230 SIGNS TYPE II REFLECTIVE F (CATEGORY 0010)**

STATION	LOCATION	SF
Sta. 23+89	LT (Object Marker)	3
Sta. 23+89	RT (Object Marker)	3
Sta. 26+50	LT (Object Marker)	3
Sta. 26+50	RT (Object Marker)	3
<b>TOTAL</b>		<b>12</b>

643.3000 TRAFFIC CONTROL DETOUR SIGNS (CATEGORY 0010)

LOCATION	BACH	DAYS
PROJECT 8745-00-71	124	75
<b>TOTAL</b>		<b>9,300</b>

645.0130 GEOTEXTILE FABRIC TYPE R (CATEGORY 0010)

STATION TO STATION	LOCATION	SY
Sta. 23+76 to Sta. 23+82	RT	8
Sta. 23+76 to Sta. 23+82	LT	8
<b>TOTAL</b>		<b>16</b>

650.0150 SAWING ASPHALT (CATEGORY 0010)

STATION	LOCATION	LF
Sta. 23+00	Mainline	31
Sta. 27+50	Mainline	31
<b>TOTAL</b>		<b>62</b>

CONSTRUCTION STAKING

CATEGORY	LOCATION	650.4500 SUBGRADE		650.5000 STRUCTURE LAYOUT		650.9910 SUPPLEMENTARY CONTROL STAKES		650.9920 SLOPE STAKES	
		LF	LS	LF	LS	LF	LS	LF	LS
0010	Sta. 23+00 TO Sta. 27+50	178	---	---	---	1	---	---	---
0020	B-16-0022	---	---	1	---	---	---	---	---
<b>TOTALS</b>		<b>178</b>	<b>178</b>	<b>1</b>	<b>1</b>	<b>1</b>	<b>1</b>	<b>178</b>	<b>178</b>

646.0106 PAVEMENT MARKING EPOXY 4-INCH

STATION	DESCRIPTION	LF
Sta. 23+00 TO Sta. 27+50	YELLOW DASHED CENTERLINE WHITE EDGE LINE	115 900
<b>TOTAL</b>		<b>1,015</b>

SPV.0090 REMOVE AND REINSTALL GUARDRAIL(CATEGORY 0010)

STATION TO STATION	LOCATION	LF
Sta. 22+71 TO Sta. 23+92	LT	120
Sta. 22+71 TO Sta. 23+92	RT	120
Sta. 26+48 TO Sta. 27+69	LT	120
Sta. 26+48 TO Sta. 27+69	RT	120
<b>TOTAL</b>		<b>480</b>

NOTE: PROVIDE POSTS WITH 4'-6" MIN. EMBEDMENT AT 3'-1 1/2" POST SPACING FROM STATION 23+21 TO STATION 23+71 RIGHT.

Addendum No. 01  
ID 8745-00-71  
Revised Sheet 12  
December 16, 2015

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20160112015PROJECT(S):  
8745-00-71FEDERAL ID(S):  
WISC 2016012

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0430	630.0200 Seeding Temporary	20.000 LB	.		.	
0440	634.0612 Posts Wood 4x6-Inch X 12-FT	4.000 EACH	.		.	
0450	637.2230 Signs Type II Reflective F	12.000 SF	.		.	
0460	638.2602 Removing Signs Type II	4.000 EACH	.		.	
0470	638.3000 Removing Small Sign Supports	4.000 EACH	.		.	
0480	642.5001 Field Office Type B	1.000 EACH	.		.	
0490	643.0100 Traffic Control (project) 01. 8745-00-71	1.000 EACH	.		.	
0500	643.0420 Traffic Control Barricades Type III	750.000 DAY	.		.	
0510	643.0705 Traffic Control Warning Lights Type A	1,500.000 DAY	.		.	
0520	643.0900 Traffic Control Signs	300.000 DAY	.		.	
0530	643.2000 Traffic Control Detour (project) 01. 8745-00-71	1.000 EACH	.		.	

## SCHEDULE OF ITEMS

REVISED:

CONTRACT:  
20160112015PROJECT(S):  
8745-00-71FEDERAL ID(S):  
WISC 2016012

CONTRACTOR : \_\_\_\_\_

LINE NO	ITEM DESCRIPTION	APPROX. QUANTITY AND UNITS	UNIT PRICE		BID AMOUNT	
			DOLLARS	CTS	DOLLARS	CTS
0540	643.3000 Traffic Control Detour Signs	9,300.000 DAY	.		.	
0550	645.0120 Geotextile Fabric Type HR	970.000 SY	.		.	
0560	645.0130 Geotextile Fabric Type R	16.000 SY	.		.	
0570	646.0106 Pavement Marking Epoxy 4-Inch	1,015.000 LF	.		.	
0580	650.4500 Construction Staking Subgrade	178.000 LF	.		.	
0590	650.5000 Construction Staking Base	178.000 LF	.		.	
0600	650.6500 Construction Staking Structure Layout (structure) 01. B-16-0022	LUMP	LUMP		.	
0610	650.9910 Construction Staking Supplemental Control (project) 01. 8745-00-71	LUMP	LUMP		.	
0620	650.9920 Construction Staking Slope Stakes	178.000 LF	.		.	
0630	690.0150 Sawing Asphalt	62.000 LF	.		.	