



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4802 Sheboygan Avenue, Rm 601  
P O Box 7916  
Madison, WI 53707-7916

March 6, 2017

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #16: 2980-00-70, WISC 2017 105**  
**W. Edgerton Avenue**  
**W. Loomis Road To S. 27<sup>th</sup> Street**  
**Local Street**  
**Milwaukee County**

### Letting of March 14, 2017

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
24	Reconnect Storm Sewer Laterals, Item SPV.0060.03
39	Construction Staking Curb Ramp & Sidewalk, Item SPV.0105.02

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
621.0100	Landmark Reference Monument	Each	2	2	4
643.0300	Traffic Control Drums	Days	6,303	20,000	26,303
643.0420	Traffic Control Barricades Type III	Days	9,741	1,528	11,269
643.0705	Traffic Control Lights Type A	Days	16,808	3,056	19,864
643.0900	Traffic Control Signs	Days	13,370	1,528	14,898
643.3000	Traffic Control Detour Signs	Days	7,640	382	8,022
SPV.0060.03	Reconnect Storm Sewer Laterals	Each	19	31	50

**Plan Sheets:**

<b>Revised Plan Sheets</b>	
<b>Plan Sheet</b>	<b>Plan Sheet Title (brief description of changes to sheet)</b>
187	Miscellaneous Quantities (revised 'reconnect storm sewer laterals' table)
189	Miscellaneous Quantities (revised 'landmark reference monument' table)
194	Miscellaneous Quantities (revised 'traffic control items' table)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**2980-00-70**

**March 6, 2017**

**Special Provisions**

**24. Reconnect Storm Laterals, Item SPV.0060.03.**

*Replace entire section titled **A Description** with the following:*

**A Description**

This special provision describes reconnecting existing storm sewer laterals and existing sump pump laterals to new structures or new pipe; or installing new storm sewer laterals to be stubbed at the right of way.

**39. Construction Staking Curb Ramp & Sidewalk, Item SPV.0105.02.**

*Replace paragraph two under section titled **C Construction** with the following:*

Set construction stakes or marks at 25-foot intervals for sidewalk and at 5-foot intervals for curb ramps, maximum or as directed by the engineer. Set and maintain stakes as necessary to achieve the required accuracy and to support the method of operations. Set additional construction stakes as necessary to establish location and grade of curb ramps as detailed in the plan. Locate stakes such that sidewalk and ramps meet all ADA requirements, Standard Detail Drawings requirements and curb ramp construction details as presented in the plan.

**Schedule of Items**

Attached, dated March 6, 2017, are the revised Schedule of Items Pages 1 – 13.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 187, 189 and 194.

END OF ADDENDUM

CURB CUT SECTIONS

ROADWAY	LOCATION	CY	CY	LF
W. EDGERTON AVE	118+00 LT & RT	278	93	550
	133+50 LT	111	37	400
	150+50 LT & RT	500	167	1,000
	<b>TOTAL</b>	<b>889</b>	<b>296</b>	<b>1,950</b>

\* QUANTITIES LISTED ELSEWHERE

CONTROL STRUCTURES

ROADWAY	STR. NO.	SPV.0060.01 CONTROL STRUCTURE 4-FT DIAMETER EACH	SPV.0060.02 LOT 20 OUTLET CONTROL STRUCTURE 5-FT DIAMETER EACH
W. EDGERTON AVE	295	1	1
	296	1	1
	365	1	1
	380	1	1
	674	1	1
	<b>LOT 20 OUTLET CONTROL STRUCTURE</b>	<b>5</b>	<b>1</b>
<b>TOTAL</b>		<b>5</b>	<b>1</b>

RECONNECT STORM SEWER LATERALS

ROADWAY	STATION	OFFSET	EACH
W. EDGERTON AVENUE	105+26.67	32' LT	1
	105+63.84	32' LT	1
	105+81.11	32' LT	1
	106+35.00	32' LT	1
	106+42.22	32' LT	1
	108+93.79	32' LT	1
	109+60.20	32' LT	1
	122+33.69	33' LT	1
	122+73.87	33' LT	1
	<b>TOTAL</b>		
			<b>50</b>

\* UNDISTRIBUTED

\* UNDISTRIBUTED ITEMS ARE ANTICIPATED FOR HOME OWNER REQUESTED LATERALS

PIPE CONNECTION TO EXISTING STRUCTURE

ROADWAY	STATION	OFFSET	EACH
W. EDGERTON AVENUE	94+00.40	31' LT	1
	95+75.84	25' LT	1
	95+79.82	24' LT	1
	97+67.04	33' LT	1
	99+98.30	34' LT	1
	115+15.00	28' RT	1
	115+42.86	52' RT	1
	119+42.84	16' RT	1
	119+45.13	18' RT	1
	123+76.08	35' LT	1
	146+45.19	20' LT	1
	146+52.16	21' LT	1
	154+74.37	38' RT	1
	154+76.37	40' RT	1
	160+16.27	53' LT	1
160+19.12	49' LT	1	
160+22.11	52' LT	1	
<b>TOTAL</b>			<b>17</b>

Addendum No. 01  
ID 2980-00-70  
Revised Sheet 187  
March 6, 2017

SIDEWALK

CATEGORY	ROADWAY	STATION -	STATION	SF
0010	W. EDGERTON AVENUE	96+00	- 107+25	8,153
		107+25	- 118+00	9,495
		118+00	- 127+25	7,860
		127+25	- 133+00	5,173
		133+00	- 138+25	4,359
		138+25	- 144+00	4,946
		144+00	- 155+00	10,670
		155+00	- 163+25	7,520
		163+25	- 168+01	4,276
	S. 43RD STREET	10+85	- 1,094	--
<b>TOTALS</b>				<b>62,452</b>

PIPE UNDERDRAIN 6-INCH

CATEGORY	ROADWAY	NUMBER	LF
0010	W. EDGERTON AVENUE	132	50
		134	50
		126	50
		130	50
		208	100
		210	100
		244	50
		246	50
		248	50
		250	50
		287	100
		295	110
		378	102
		379	160
		938	87
		940	88
<b>TOTALS</b>			<b>1,247</b>

RIPRAP AND GEOTEXTILE

CATEGORY	ROADWAY	STATION	OFFSET	Q25	WIDTH	LENGTH	RIPRAP	GEOTEXTILE	FABRIC TYPE
0010	W. EDGERTON AVENUE			FRS	FT	FT	CY	CY	SY
		109+99	260' LT	22	18	29	--	19	69
		142+50	45' LT	6	14	20	10	--	39
		142+57	365.2' LT	4	11	16	7	--	26
<b>TOTALS</b>							<b>17</b>	<b>19</b>	<b>134</b>

Addendum No. 01  
ID 2980-00-70  
Revised Sheet 189  
March 6, 2017

LANDMARK REFERENCE MONUMENT

CATEGORY	STATION	LOCATION	DESCRIPTION	REFERENCE MONUMENT
0010	115+72.55	EDGERTON AVENUE @ 43RD STREET	NOTCHES IN MANHOLE RIM - WEST 1/4 CORNER OF SECTION 25, TOWNSHIP 6 NORTH, RANGE 21 EAST	EACH 2
	142+23.85	EDGERTON AVENUE @ 35TH STREET	NOTCHES IN MANHOLE RIM, CENTER OF SECTION 25, TOWNSHIP 6 NORTH, RANGE 21 EAST	2
<b>TOTALS</b>				<b>4</b>

Addendum No. 01  
 ID 2980-00-70  
 Revised Sheet 194  
 March 6, 2017

TRAFFIC CONTROL ITEMS														
CATEGORY	ROADWAY	PROJECT DURATION DAYS	643.0300 TRAFFIC CONTROL DRUMS EACH	643.0420 TRAFFIC CONTROL BARRICADES TYPE III EACH	643.0705 TRAFFIC CONTROL WARNING LIGHTS TYPE A EACH	643.0900 TRAFFIC CONTROL SIGNS EACH	643.1000 TRAFFIC CONTROL SIGNS FIXED MESSAGE SF	643.3000 TRAFFIC CONTROL SIGNS DETOUR EACH	FIELD OFFICE TYPE C EACH					
0010	W. LOOMS ROAD	191	22	4,202	4	764	--	6	1,146	--	--	--	--	1
	S. 27TH STREET	191	11	2,101	3	573	--	3	573	--	--	--	--	
	W. EDGERTON AVENUE - WEST	191	--	--	4	764	8	1,528	2	382	9	6	1,146	
	S. 48TH STREET	191	--	--	2	382	4	764	3	573	--	--	--	
	S. 43RD STREET	191	--	--	4	764	8	1,528	6	1,146	--	--	--	
	S. HONEY CREEK DRIVE	191	--	--	2	382	4	764	3	573	--	--	--	
	S. 41ST STREET	191	--	--	2	382	4	764	3	573	--	--	--	
	S. 40TH STREET	191	--	--	2	382	4	764	3	573	--	--	--	
	S. MALLARD CIRCLE	191	--	--	2	382	4	764	3	573	--	--	--	
	S. 37TH STREET - NORTH	191	--	--	2	382	4	764	3	573	--	--	--	
	S. 37TH STREET - SOUTH	191	--	--	2	382	4	764	3	573	--	--	--	
	S. 36TH STREET	191	--	--	2	382	4	764	3	573	--	--	--	
	S. 35TH STREET	191	--	--	2	382	4	764	3	573	--	--	--	
	S. HIDDEN DRIVE	191	--	--	2	382	4	764	3	573	--	--	--	
	S. TUCKAWAY BOULEVARD	191	--	--	2	382	4	764	3	573	--	--	--	
	S. 34th STREET	191	--	--	2	382	4	764	3	573	--	--	--	
	S. 31ST STREET	191	--	--	4	764	8	1,528	6	1,146	--	--	--	
	S. 30TH STREET	191	--	--	4	764	8	1,528	6	1,146	--	--	--	
	S. TUCKAWAY DRIVE	191	--	--	2	382	4	764	3	573	--	--	--	
	W. EDGERTON AVENUE - EAST	191	--	--	2	382	4	764	2	382	9	6	1,146	
	DETOUR	191	--	--	--	--	--	--	--	--	48	28	5,348	
	* UNDISTRIBUTED	191	--	20,000	8	1,528	16	3,056	8	1,528	--	2	382	
	<b>TOTALS</b>			<b>26,303</b>		<b>11,269</b>		<b>19,864</b>		<b>14,898</b>		<b>86</b>		<b>8,022</b>

\* UNDISTRIBUTED ITEMS TO BE USED WITHIN "ROAD CLOSED" SECTION TO PROTECT STRUCTURES, TRENCHES AND WORKZONES

FIELD OFFICE

CATEGORY	PROJECT ID	DESCRIPTION	642.5201 FIELD OFFICE TYPE C
0010	2980-00-70	W. EDGERTON AVE	1
<b>TOTALS</b>			<b>1</b>

TRAFFIC CONTROL

CATEGORY	ROADWAY	643.0100 TRAFFIC CONTROL (2980-00-70) EACH	643.2000 TRAFFIC CONTROL DETOUR (2980-00-70) EACH
0010	W. EDGERTON AVENUE	1	1
<b>TOTALS</b>		<b>1</b>	<b>1</b>

GEOTEXTILE FABRIC TYPE SAS

CATEGORY	PROJECT D	ROADWAY	645.0140 GEOTEXTILE FABRIC TYPE SAS SY
0010	2980-00-70	UNDISTRIBUTED	204
<b>TOTALS</b>			<b>204</b>



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0010	201.0105 Clearing	64.000 STA	_____.	_____.
0020	201.0205 Grubbing	64.000 STA	_____.	_____.
0030	203.0100 Removing Small Pipe Culverts	3.000 EACH	_____.	_____.
0040	204.0100 Removing Pavement	1,897.000 SY	_____.	_____.
0050	204.0150 Removing Curb & Gutter	1,749.000 LF	_____.	_____.
0060	204.0155 Removing Concrete Sidewalk	107.000 SY	_____.	_____.
0070	204.0170 Removing Fence	1,047.000 LF	_____.	_____.
0080	204.0210 Removing Manholes	7.000 EACH	_____.	_____.
0090	204.0220 Removing Inlets	79.000 EACH	_____.	_____.
0100	204.0245 Removing Storm Sewer (size) 01. 12-Inch	3,330.000 LF	_____.	_____.
0110	204.0245 Removing Storm Sewer (size) 02. 15-Inch	626.000 LF	_____.	_____.
0120	204.0245 Removing Storm Sewer (size) 03. 18-Inch	385.000 LF	_____.	_____.
0130	204.0245 Removing Storm Sewer (size) 04. 21-Inch	59.000 LF	_____.	_____.
0140	204.0245 Removing Storm Sewer (size) 05. 24-Inch	125.000 LF	_____.	_____.
0150	204.0245 Removing Storm Sewer (size) 06. 27-Inch	155.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0160	204.0245 Removing Storm Sewer (size) 07. 30-Inch	639.000 LF	_____.	_____.
0170	204.0245 Removing Storm Sewer (size) 08. 36-Inch	203.000 LF	_____.	_____.
0180	204.0280 Sealing Pipes	7.000 EACH	_____.	_____.
0190	205.0100 Excavation Common	39,226.000 CY	_____.	_____.
0200	305.0110 Base Aggregate Dense 3/4-Inch	35.000 TON	_____.	_____.
0210	305.0120 Base Aggregate Dense 1 1/4-Inch	33,097.000 TON	_____.	_____.
0220	310.0110 Base Aggregate Open-Graded	94.000 TON	_____.	_____.
0230	311.0110 Breaker Run	42,416.000 TON	_____.	_____.
0240	415.6000.S Rout and Seal	15,966.000 LF	_____.	_____.
0250	416.0170 Concrete Driveway 7-Inch	858.000 SY	_____.	_____.
0260	416.0610 Drilled Tie Bars	66.000 EACH	_____.	_____.
0270	450.4000 HMA Cold Weather Paving	925.000 TON	_____.	_____.
0280	455.0605 Tack Coat	1,099.000 GAL	_____.	_____.
0290	460.2000 Incentive Density HMA Pavement	6,750.000 DOL	_____.	_____.
0300	460.5223 HMA Pavement 3 LT 58-28 S	6,852.000 TON	_____.	_____.
0310	460.5224 HMA Pavement 4 LT 58-28 S	3,691.000 TON	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0320	465.0120 Asphaltic Surface Driveways and Field Entrances	359.000 TON	_____.	_____.
0330	465.0125 Asphaltic Surface Temporary	34.000 TON	_____.	_____.
0340	520.8000 Concrete Collars for Pipe	47.000 EACH	_____.	_____.
0350	522.0112 Culvert Pipe Reinforced Concrete Class III 12-Inch	247.000 LF	_____.	_____.
0360	522.1012 Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	48.000 EACH	_____.	_____.
0370	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	1.000 EACH	_____.	_____.
0380	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	1.000 EACH	_____.	_____.
0390	601.0331 Concrete Curb & Gutter 31-Inch	15,966.000 LF	_____.	_____.
0400	602.0405 Concrete Sidewalk 4-Inch	1,087.000 SF	_____.	_____.
0410	602.0410 Concrete Sidewalk 5-Inch	62,452.000 SF	_____.	_____.
0420	602.0515 Curb Ramp Detectable Warning Field Natural Patina	740.000 SF	_____.	_____.
0430	606.0100 Riprap Light	17.000 CY	_____.	_____.
0440	606.0200 Riprap Medium	29.000 CY	_____.	_____.
0450	608.0312 Storm Sewer Pipe Reinforced Concrete Class III 12-Inch	4,143.000 LF	_____.	_____.
0460	608.0315 Storm Sewer Pipe Reinforced Concrete Class III 15-Inch	172.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0470	608.0318 Storm Sewer Pipe Reinforced Concrete Class III 18-Inch	853.000 LF	_____.	_____.
0480	608.0321 Storm Sewer Pipe Reinforced Concrete Class III 21-Inch	369.000 LF	_____.	_____.
0490	608.0324 Storm Sewer Pipe Reinforced Concrete Class III 24-Inch	558.000 LF	_____.	_____.
0500	608.0327 Storm Sewer Pipe Reinforced Concrete Class III 27-Inch	29.000 LF	_____.	_____.
0510	608.0330 Storm Sewer Pipe Reinforced Concrete Class III 30-Inch	151.000 LF	_____.	_____.
0520	608.0336 Storm Sewer Pipe Reinforced Concrete Class III 36-Inch	403.000 LF	_____.	_____.
0530	608.0342 Storm Sewer Pipe Reinforced Concrete Class III 42-Inch	109.000 LF	_____.	_____.
0540	608.0412 Storm Sewer Pipe Reinforced Concrete Class IV 12-Inch	2,260.000 LF	_____.	_____.
0550	608.0415 Storm Sewer Pipe Reinforced Concrete Class IV 15-Inch	413.000 LF	_____.	_____.
0560	608.0418 Storm Sewer Pipe Reinforced Concrete Class IV 18-Inch	242.000 LF	_____.	_____.
0570	608.0424 Storm Sewer Pipe Reinforced Concrete Class IV 24-Inch	118.000 LF	_____.	_____.
0580	608.0442 Storm Sewer Pipe Reinforced Concrete Class IV 42-Inch	435.000 LF	_____.	_____.
0590	610.0434 Storm Sewer Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 34x53-Inch	170.000 LF	_____.	_____.



## Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0600	611.0420 Reconstructing Manholes	7.000 EACH	_____.	_____.
0610	611.0555 Manhole Covers Type Q	61.000 EACH	_____.	_____.
0620	611.0642 Inlet Covers Type MS	26.000 EACH	_____.	_____.
0630	611.0651 Inlet Covers Type S	60.000 EACH	_____.	_____.
0640	611.0657 Inlet Covers Type W	69.000 EACH	_____.	_____.
0650	611.1004 Catch Basins 4-FT Diameter	11.000 EACH	_____.	_____.
0660	611.1006 Catch Basins 6-FT Diameter	1.000 EACH	_____.	_____.
0670	611.2004 Manholes 4-FT Diameter	29.000 EACH	_____.	_____.
0680	611.2005 Manholes 5-FT Diameter	17.000 EACH	_____.	_____.
0690	611.2006 Manholes 6-FT Diameter	9.000 EACH	_____.	_____.
0700	611.2008 Manholes 8-FT Diameter	5.000 EACH	_____.	_____.
0710	611.3225 Inlets 2x2.5-FT	70.000 EACH	_____.	_____.
0720	611.3901 Inlets Median 1 Grate	22.000 EACH	_____.	_____.
0730	611.3902 Inlets Median 2 Grate	2.000 EACH	_____.	_____.
0740	611.8110 Adjusting Manhole Covers	47.000 EACH	_____.	_____.
0750	611.8115 Adjusting Inlet Covers	4.000 EACH	_____.	_____.
0760	611.9800.S Pipe Grates	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0770	612.0106 Pipe Underdrain 6-Inch	1,247.000 LF	_____.	_____.
0780	612.0406 Pipe Underdrain Wrapped 6-Inch	1,950.000 LF	_____.	_____.
0790	612.0700 Drain Tile Exploration	200.000 LF	_____.	_____.
0800	616.0700.S Fence Safety	500.000 LF	_____.	_____.
0810	619.1000 Mobilization	1.000 EACH	_____.	_____.
0820	621.0100 Landmark Reference Monuments	4.000 EACH	_____.	_____.
0830	623.0200 Dust Control Surface Treatment	96,173.000 SY	_____.	_____.
0840	624.0100 Water	165.000 MGAL	_____.	_____.
0850	625.0100 Topsoil	11,426.000 SY	_____.	_____.
0860	625.0500 Salvaged Topsoil	22,856.000 SY	_____.	_____.
0870	628.1504 Silt Fence	1,160.000 LF	_____.	_____.
0880	628.1520 Silt Fence Maintenance	1,160.000 LF	_____.	_____.
0890	628.1905 Mobilizations Erosion Control	4.000 EACH	_____.	_____.
0900	628.1910 Mobilizations Emergency Erosion Control	6.000 EACH	_____.	_____.
0910	628.2006 Erosion Mat Urban Class I Type A	37,745.000 SY	_____.	_____.
0920	628.7005 Inlet Protection Type A	199.000 EACH	_____.	_____.
0930	628.7010 Inlet Protection Type B	5.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0940	628.7015 Inlet Protection Type C	85.000 EACH	_____.	_____.
0950	628.7020 Inlet Protection Type D	4.000 EACH	_____.	_____.
0960	628.7504 Temporary Ditch Checks	638.000 LF	_____.	_____.
0970	628.7555 Culvert Pipe Checks	35.000 EACH	_____.	_____.
0980	628.7570 Rock Bags	50.000 EACH	_____.	_____.
0990	629.0210 Fertilizer Type B	23.200 CWT	_____.	_____.
1000	630.0140 Seeding Mixture No. 40	629.000 LB	_____.	_____.
1010	630.0200 Seeding Temporary	475.000 LB	_____.	_____.
1020	631.0300 Sod Water	1.900 MGAL	_____.	_____.
1030	631.1100 Sod Erosion Control	84.000 SY	_____.	_____.
1040	633.5200 Markers Culvert End	1.000 EACH	_____.	_____.
1050	634.0814 Posts Tubular Steel 2x2-Inch X 14-FT	61.000 EACH	_____.	_____.
1060	634.0816 Posts Tubular Steel 2x2-Inch X 16-FT	5.000 EACH	_____.	_____.
1070	637.2210 Signs Type II Reflective H	354.790 SF	_____.	_____.
1080	637.2230 Signs Type II Reflective F	10.250 SF	_____.	_____.
1090	638.2102 Moving Signs Type II	39.000 EACH	_____.	_____.
1100	638.2602 Removing Signs Type II	55.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1110	638.3000 Removing Small Sign Supports	40.000 EACH	_____.	_____.
1120	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
1130	643.0100 Traffic Control (project) 01. 2980-00-70	1.000 EACH	_____.	_____.
1140	643.0300 Traffic Control Drums	26,303.000 DAY	_____.	_____.
1150	643.0420 Traffic Control Barricades Type III	11,269.000 DAY	_____.	_____.
1160	643.0705 Traffic Control Warning Lights Type A	19,864.000 DAY	_____.	_____.
1170	643.0900 Traffic Control Signs	14,898.000 DAY	_____.	_____.
1180	643.1000 Traffic Control Signs Fixed Message	66.000 SF	_____.	_____.
1190	643.2000 Traffic Control Detour (project) 01. 2980-00-70	1.000 EACH	_____.	_____.
1200	643.3000 Traffic Control Detour Signs	8,022.000 DAY	_____.	_____.
1210	645.0111 Geotextile Type DF Schedule A	696.000 SY	_____.	_____.
1220	645.0120 Geotextile Type HR	75.000 SY	_____.	_____.
1230	645.0130 Geotextile Type R	65.000 SY	_____.	_____.
1240	645.0140 Geotextile Type SAS	204.000 SY	_____.	_____.
1250	646.0106 Pavement Marking Epoxy 4-Inch	19,973.000 LF	_____.	_____.
1260	646.0126 Pavement Marking Epoxy 8-Inch	75.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1270	647.0166 Pavement Marking Arrows Epoxy Type 2	1.000 EACH	_____.	_____.
1280	647.0176 Pavement Marking Arrows Epoxy Type 3	1.000 EACH	_____.	_____.
1290	647.0206 Pavement Marking Arrows Bike Lane Epoxy	22.000 EACH	_____.	_____.
1300	647.0406 Pavement Marking Words Bike Lane Epoxy	50.000 EACH	_____.	_____.
1310	647.0566 Pavement Marking Stop Line Epoxy 18-Inch	387.000 LF	_____.	_____.
1320	647.0766 Pavement Marking Crosswalk Epoxy 6-Inch	1,763.000 LF	_____.	_____.
1330	650.4000 Construction Staking Storm Sewer	216.000 EACH	_____.	_____.
1340	650.4500 Construction Staking Subgrade	9,567.000 LF	_____.	_____.
1350	650.5000 Construction Staking Base	9,567.000 LF	_____.	_____.
1360	650.5500 Construction Staking Curb Gutter and Curb & Gutter	16,529.000 LF	_____.	_____.
1370	650.6000 Construction Staking Pipe Culverts	15.000 EACH	_____.	_____.
1380	650.8500 Construction Staking Electrical Installations (project) 01. 2980-00-70	LS	LUMP SUM	_____.
1390	650.9910 Construction Staking Supplemental Control (project) 01. 2980-00-70	LS	LUMP SUM	_____.
1400	650.9920 Construction Staking Slope Stakes	9,567.000 LF	_____.	_____.
1410	652.0225 Conduit Rigid Nonmetallic Schedule 40 2-Inch	8,607.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1420	652.0235 Conduit Rigid Nonmetallic Schedule 40 3-Inch	285.000 LF	_____.	_____.
1430	652.0800 Conduit Loop Detector	404.000 LF	_____.	_____.
1440	653.0105 Pull Boxes Steel 12x24-Inch	2.000 EACH	_____.	_____.
1450	653.0905 Removing Pull Boxes	2.000 EACH	_____.	_____.
1460	654.0105 Concrete Bases Type 5	42.000 EACH	_____.	_____.
1470	654.0230 Concrete Control Cabinet Bases Type L30	1.000 EACH	_____.	_____.
1480	655.0610 Electrical Wire Lighting 12 AWG	5,040.000 LF	_____.	_____.
1490	655.0625 Electrical Wire Lighting 6 AWG	32,780.000 LF	_____.	_____.
1500	655.0700 Loop Detector Lead In Cable	359.000 LF	_____.	_____.
1510	655.0800 Loop Detector Wire	1,282.000 LF	_____.	_____.
1520	656.0200 Electrical Service Meter Breaker Pedestal (location) 01. Sta 155+61.18, 42.2' Rt	LS	LUMP SUM	_____.
1530	657.0255 Transformer Bases Breakaway 11 1/2- Inch Bolt Circle	42.000 EACH	_____.	_____.
1540	659.2230 Lighting Control Cabinets 240/480 30- Inch	1.000 EACH	_____.	_____.
1550	690.0150 Sawing Asphalt	1,486.000 LF	_____.	_____.
1560	690.0250 Sawing Concrete	622.000 LF	_____.	_____.





Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1570	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,800.000 HRS	5.00000	9,000.00
1580	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	3,000.000 HRS	5.00000	15,000.00
1590	SPV.0035 Special 01. Engineered Soil	889.000 CY	_____.	_____.
1600	SPV.0035 Special 02. Curb Cut Stone	296.000 CY	_____.	_____.
1610	SPV.0060 Special 01. Control Structure 4-Ft Diameter	5.000 EACH	_____.	_____.
1620	SPV.0060 Special 02. Lot 20 Outlet Control Structure 5-Ft Diameter	1.000 EACH	_____.	_____.
1630	SPV.0060 Special 03. Reconnect Storm Sewer Laterals	50.000 EACH	_____.	_____.
1640	SPV.0060 Special 04. Manholes 9-Ft Special	1.000 EACH	_____.	_____.
1650	SPV.0060 Special 05. Manholes 10-Ft Special	1.000 EACH	_____.	_____.
1660	SPV.0060 Special 06. Pipe Connection to Existing Structure	17.000 EACH	_____.	_____.
1670	SPV.0060 Special 07. Catch Basins 2x2.5-Ft	41.000 EACH	_____.	_____.
1680	SPV.0060 Special 21. Luminaires Type A	42.000 EACH	_____.	_____.
1690	SPV.0060 Special 22. Poles Type 5 - Aluminum Black	42.000 EACH	_____.	_____.
1700	SPV.0060 Special 23. Polymer Concrete Pull Boxes	11.000 EACH	_____.	_____.
1710	SPV.0060 Special 52. Sanitary Manhole Seal - External Special	28.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1720	SPV.0060 Special 53. Adjust Water Service Boxes	106.000 EACH	_____.	_____.
1730	SPV.0060 Special 54. Adjust Water Valve Boxes	66.000 EACH	_____.	_____.
1740	SPV.0060 Special 55. Water Service Pothole	106.000 EACH	_____.	_____.
1750	SPV.0060 Special 56. Water Service Insulation	10.000 EACH	_____.	_____.
1760	SPV.0060 Special 57. Water Service Alteration Replacement 1-Inch Through 2-Inch	10.000 EACH	_____.	_____.
1770	SPV.0060 Special 58. Water Service Alteration Lowering 1-Inch Through 2-Inch	10.000 EACH	_____.	_____.
1780	SPV.0060 Special 59. Adjusting Water Manholes	6.000 EACH	_____.	_____.
1790	SPV.0060 Special 60. Water Main Protection	5.000 EACH	_____.	_____.
1800	SPV.0090 Special 01. Storm Sewer Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 38x60	45.000 LF	_____.	_____.
1810	SPV.0090 Special 02. PVC Storm Sewer 6-Inch	78.000 LF	_____.	_____.
1820	SPV.0090 Special 51. Copper Water Service 1-Inch Special	400.000 LF	_____.	_____.
1830	SPV.0105 Special 01. Remove Loop Detector Wire and Lead-in Cable	LS	LUMP SUM	_____.
1840	SPV.0105 Special 02. Construction Staking Curb Ramp & Sidewalk	LS	LUMP SUM	_____.
1850	SPV.0105 Special 03. Construction Staking Drainage Ponds	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20170314016 Project(s): 2980-00-70

Federal ID(s): WISC 2017105

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
1860	SPV.0170 Special 01. Test Rolling	100.000 STA	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.

