



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

May 4, 2017

NOTICE TO ALL CONTRACTORS:

Proposal #12: 4880-01-71, WISC 2017 269
CTH D (Main Street)
Beech Street – CTH LL
CTH D
Ozaukee County

Letting of May 9, 2017

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
27	Decorative Street Light Unit, Item SPV.0060.202
37	Construction Staking Sidewalk and Curb Ramps, Item SPV.0105.001
38	Temporary Mailbox Accommodations, Item SPV.0105.002.

Note: Parts of Article 37 and all of Article 38 are not shown on the printed proposals. The proposals located on the HCCI site and the May CD are correct. They are being shown in their entirety as part of this addendum.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

4880-01-71

May 4, 2017

Special Provisions

27. Decorative Street Light Unit, Item SPV.0060.202.

Replace the second bullet item of section titled B.5 Luminaire with the following:

- Luminaire shall be traditional tear drop deep globe style; globe shall be approximately 17" diameter and 17" tall; acceptable globe types include glass and impact resistant acrylic.

37. Construction Staking Sidewalk and Curb Ramps, Item SPV.0105.001.

Replace entire article language with the following:

A Description

Perform all survey required to layout and construct all work associated with the sidewalk and curb ramps included in this contract.

The department may choose to perform quality assurance survey during the project. This quality assurance survey does not relieve the contractor of the responsibility for all survey work required under this contract.

B (Vacant)

C Construction

Survey required under this item shall be according to all pertinent requirements of standard spec 650 and shall include all other miscellaneous survey required to layout and construct all work associated with the sidewalk and curb ramps under this contract.

Set construction stakes or marks at 50-foot intervals, maximum. Set and maintain stakes as necessary to achieve the required accuracy and to support the method of operations. Set additional construction stakes as necessary to establish location and grade of sidewalk and curb ramps, including points of change in alignment grade and at the radius points. Locate stakes to within 0.02 feet horizontally and establish elevations to within 0.01 feet vertically.

D Measurement

The department will measure Construction Staking Sidewalk and Curb Ramps as a single lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0105.001	Construction Staking Sidewalk and Curb Ramps	LS

Payment is full compensation for performing all survey work required to layout and construct all work associated with the sidewalk and curb ramps under this contract.

38. Temporary Mailbox Accommodations, Item SPV.0105.002.

Replace entire article language with the following:

A Description

This special provision describes providing temporary mailbox facilities for the project at locations determined by the Village of Belgium and the United States Postal Service (USPS).

B Materials

Furnish temporary mail boxes according to local USPS requirements.

C Construction

Prior to the start of construction, coordinate with the local Postmaster and Village of Belgium for temporary mailbox requirements (size, height, location(s), etc.). Provide temporary mailbox accommodations that contain no less than the number of mailboxes located within the project limits. Install the mailbox accommodations at the proper height and distance from the curb or edge of roadway as required by the USPS. Provide notice to affected property owners and the USPS no less than one week prior to project completion and removal of the temporary mailbox accommodations.

D Measurement

The department will measure Temporary Mailbox Accommodations as a single lump sum unit of work, acceptably completed.

E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER	DESCRIPTION	UNIT
SPV.105.002	Temporary Mailbox Accommodations	LS

Payment is full compensation for coordinating with the Village of Belgium and USPS; furnishing and installing temporary mailbox(es), including any required posts, mailboxes, foundations, and mounting hardware; removal of the temporary mailboxes; and for cleaning out and restoring the site.

The contractor is not responsible for the removal or reinstallation of permanent mailboxes under this item.

END OF ADDENDUM

