



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4802 Sheboygan Avenue, Rm 601
P O Box 7916
Madison, WI 53707-7916

November 29, 2017

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

**Proposal #06: 5070-01-71, WISC 2018 028
STH 58 – Rock Springs
West County Line to STH 23
STH 154
Sauk County**

Letting of December 12, 2017

This is Addendum No. 01, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
33	Pipe Culverts – Section 520

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
521.3136	Culvert Pipe Corrugated Steel 36-Inch	LF	0	4	4
521.3148	Culvert Pipe Corrugated Steel 48-Inch	LF	0	14	14
521.6124	Culvert Pipe Corrugated Steel Aluminum Coated 24-Inch	LF	0	572	572
521.6130	Culvert Pipe Corrugated Steel Aluminum Coated 30-Inch	LF	0	46	46
521.6148	Culvert Pipe Corrugated Steel Aluminum Coated 48-Inch	LF	0	68	68
522.2419	Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 19X30-Inch	LF	0	146	146
522.2619	Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 19X30-Inch	Each	0	4	4
646.1020	Marking Line Epoxy 4-Inch	LF	0	92,434	92,434
646.3020	Marking Line Epoxy 8-Inch	LF	0	600	600
646.4520	Marking Line Same Day Epoxy 4-Inch	LF	0	58,129	58,129
646.6120	Marking Stop Line Epoxy 18-Inch	LF	0	34	34

646.9000	Marking Removal Line 4-Inch	LF	0	1,431	1,431
649.0105	Temporary Marking Line Paint 4-Inch	LF	0	104,086	104,086
649.0150	Temporary Marking Line Removable Tape 4-Inch	LF	0	3,374	3,374
649.0850	Temporary Marking Stop Line Removable Tape 18-Inch	LF	0	84	84
650.9000	Construction Staking Curb Ramps	Each	0	12	12

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
523.0419	Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 19X30-Inch	LF	146	-146	0
523.0519	Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 19X30-Inch	Each	4	-4	0
529.0124	Culvert Pipe Corrugated Steel Aluminum Coated 24-Inch	LF	572	-572	0
529.0130	Culvert Pipe Corrugated Steel Aluminum Coated 30-Inch	LF	46	-46	0
529.0136	Culvert Pipe Corrugated Steel Aluminum Coated 36-Inch	LF	4	-4	0
529.0148	Culvert Pipe Corrugated Steel Aluminum Coated 48-Inch	LF	82	-82	0
646.0106	Pavement Marking Epoxy 4-Inch	LF	92,434	-92,434	0
646.0126	Pavement Marking Epoxy 8-Inch	LF	600	-600	0
646.0406	Pavement Marking Same Day Epoxy 4-Inch	LF	58,129	-58,129	0
646.0600	Removing Pavement Marking	LF	1,431	-1,431	0
647.0566	Pavement Marking Stop Line Epoxy 18-Inch	LF	34	-34	0
649.0400	Temporary Pavement Marking Removable Tape 4-Inch	LF	3,374	-3,374	0
649.0402	Temporary Pavement Marking Paint 4-Inch	LF	116,259	-116,259	0
649.1400	Temporary Pavement Marking Stop Line Removable Tape 24-Inch	LF	84	-84	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
91, 92, 96, 104	Miscellaneous Quantities (Revised various bit items and quantities)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

5070-01-71

November 29, 2017

Special Provisions

33. Pipe Culverts – Section 520

Add the following to standard spec 520.5.2.

Should the contractor elect to use temporary shoring in the installation of culvert pipes, the cost of providing, installing and removing the shoring material shall be considered incidental to the installation of the culvert pipe.

Schedule of Items

Attached, dated November 29, 2017, are the revised Schedule of Items Pages 1 – 10.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 91, 92, 96 & 104.

END OF ADDENDUM

Addendum No. 01
 ID 5070-01-71
 Revised Sheet 92
 November 29, 2017

TRACKING PADS - CATEGORY 0010

LOCATION	PROJECT WIDE	QUANTITIES	COMMENTS
628.7560 TRACKING PADS EACH	2	UNDISTRIBUTED	

INLET PROTECTION: CATEGORY 0010

STATION	OFFSET	MGAL	EACH	COMMENTS
264+41	34' LT	1	-	GUTTER INLET
264+80	36' LT	-	-	CURB INLET
487+67	20' RT	-	1	COMB. INLET
TOTAL		1	1	2

CONCRETE SIDEWALK: CATEGORY 0010

STATION	SIDE	LF	SF	COMMENTS
264+23 - 264+40	LT	13	64	8W QUADRANT AT W. HILL POINT RD
264+58 - 264+79	RT	16	88	NE QUADRANT AT VILLAGE RD
264+82 - 264+97	LT	11	90	NW QUADRANT AT W. HILL POINT RD
265+80 - 266+05	RT	25	121	STH 154 EB MID BLOCK CROSSWALK
265+80 - 266+05	LT	25	106	STH 154 WB MID BLOCK CROSSWALK
480+19 - 480+46	RT	28	127	STH 154 EB MID BLOCK CROSSWALK
480+27 - 480+39	LT	8	73	STH 154 WB MID BLOCK CROSSWALK
484+69 - 484+74	RT	5	20	SE QUADRANT AT B-56-0468
485+34 - 485+46	LT	-	100	NW QUADRANT AT WEST ST
485+87 - 486+15	LT	25	255	NE QUADRANT AT WEST ST
487+68 - 487+91	LT	17	185	STH 154 WB MID BLOCK CROSSWALK
487+75 - 488+07	RT	38	171	STH 154 EB MID BLOCK CROSSWALK
TOTAL		203	1,400	112

EROSION CONTROL MOBILIZATIONS: CATEGORY 0010

LOCATION	QUANTITIES	COMMENTS
628.1905 MOBILIZATIONS EROSION CONTROL EACH	6	UNDISTRIBUTED
TOTAL	6	3

RIPRAP: CATEGORY 0010

STATION	DIMENSIONS (FT)	RY	COMMENTS
4+40 LT	8.0 4.0 1.5	1.8	9.0
156+48 RT	8.0 4.0 1.5	1.8	9.0
187+82 RT	12.0 6.0 1.5	4.0	15.0
302+97 RT	8.0 4.0 1.5	1.8	9.0
391+86 RT	8.0 4.0 1.5	1.8	9.0
392+07 LT	8.0 4.0 1.5	1.8	9.0
466+42 RT	8.0 4.0 1.5	1.8	9.0
TOTALS		14.7	69.0

WATER: CATEGORY 0010

STATION	MGAL	COMMENTS
624.0100 WATER	17.8	SHOULDERS & SIDEWALK
1+00 - 488+78	17.8	
125+50	134+25	3.9
188+70	194+00	2.0
1+00	488+78	10.0
TOTAL		33.7

TRACKING PADS - CATEGORY 0010

LOCATION	PROJECT WIDE	QUANTITIES	COMMENTS
628.7560 TRACKING PADS EACH	2	UNDISTRIBUTED	
TOTAL	2	3	

Addendum No. 01
 ID 5070-01-71
 Revised Sheet 96
 November 29, 2017

3

CULVERT MARKERS: CATEGORY 0010

633.5200

204.0180
 REMOVING
 DELINEATORS
 AND
 MARKERS
 EACH

STATION	MARKERS EACH	END EACH	COMMENTS
4+41	2	2	RIGHT & LEFT
14+00	2	2	RIGHT & LEFT
22+73	2	2	RIGHT & LEFT
31+00	2	2	RIGHT & LEFT
47+50	2	2	RIGHT & LEFT
65+96	2	2	RIGHT & LEFT
92+69	2	2	RIGHT & LEFT
108+81	2	2	RIGHT & LEFT
129+46	2	2	RIGHT & LEFT
130+39	2	2	RIGHT & LEFT
133+30	2	2	RIGHT & LEFT
145+50	2	2	RIGHT & LEFT
156+48	2	2	RIGHT & LEFT
162+61	2	2	RIGHT & LEFT
187+46	2	2	RIGHT & LEFT
194+47	2	2	RIGHT & LEFT
212+00	2	2	RIGHT & LEFT
224+04	2	2	RIGHT & LEFT
230+60	2	2	RIGHT & LEFT
238+93	2	2	RIGHT & LEFT
244+35	2	2	RIGHT & LEFT
262+48	2	2	RIGHT & LEFT
278+46	2	2	RIGHT & LEFT
285+35	2	2	RIGHT & LEFT
295+40	2	2	RIGHT & LEFT
302+83	2	2	RIGHT & LEFT
324+31	2	2	RIGHT & LEFT
335+48	2	2	RIGHT & LEFT
350+62	2	2	RIGHT & LEFT
367+03	2	2	RIGHT & LEFT
380+10	2	2	RIGHT & LEFT
408+33	2	2	RIGHT & LEFT
419+29	2	2	RIGHT & LEFT
425+01	2	2	RIGHT & LEFT
429+53	2	2	RIGHT & LEFT
440+47	2	2	RIGHT & LEFT
446+00	2	2	RIGHT & LEFT
451+40	2	2	RIGHT & LEFT
455+10	2	2	RIGHT & LEFT
466+42	2	2	RIGHT & LEFT
TOTALS	80	80	

PAVEMENT MARKING: CATEGORY 0010

STATION	MARKING LF	MARKING LF	MARKING LF	MARKING LF	COMMENTS
1+00 - 125+79	24,958	-	16,151	-	29,180
125+79 - 133+97	1,422	400	1,560	16	3,120
133+97 - 188+70	10,946	-	8,018	-	14,855
188+70 - 193+97	968	200	1,042	-	2,061
193+97 - 262+77	13,760	-	9,113	-	16,555
262+77 - 268+10	-	-	133	-	85
268+10 - 470+00	40,380	-	19,673	-	33,804
470+00 - 488+78	-	-	2,439	18	4,426
TOTAL	92,434	600	58,129	34	104,086

SLOPE STABILIZATION: CATEGORY 0010

SPV.0070.01
 SPRAYED
 ASPHALTIC
 SHOULDER
 TREATMENT

STATION	TREATMENT GAL	COMMENTS
202+30 - 203+20	15	B-56-0147 LT
251+60 - 252+40	23	B-56-0148 LT
252+00 - 252+75	15	B-56-0148 RT
268+70 - 269+00	8	B-56-0149 RT
269+35 - 269+75	15	B-56-0149 RT
269+35 - 269+75	15	B-56-0149 LT
468+95 - 469+30	8	B-56-0011 RT
470+75 - 472+00	23	B-56-0011 LT
TOTAL	120	

DESIGN APPLICATION RATE OF 0.3 GAL/SY

LOCATING NO-PASSING ZONES: CATEGORY 0010

STATION	NO-PASSING ZONES MGAL	COMMENTS
1+00 - 488+78	9.24	STH 154
TOTAL	9.24	

PROJECT NO: 5070-01-71

HWY: STH 154

COUNTY: SAUK

MISCELLANEOUS QUANTITIES

SHEET NO: 96

E

FILE NAME:

PLOT DATE:

PLOT BY:

ORIG DATE:

ORIGINATOR: DIST.

PLOT SCALE: 1:1

3



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71

Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	10.000 STA	_____.	_____.
0004	201.0205 Grubbing	10.000 STA	_____.	_____.
0006	203.0100 Removing Small Pipe Culverts	15.000 EACH	_____.	_____.
0008	204.0100 Removing Pavement	106.700 SY	_____.	_____.
0010	204.0110 Removing Asphaltic Surface	904.000 SY	_____.	_____.
0012	204.0120 Removing Asphaltic Surface Milling	136,773.000 SY	_____.	_____.
0014	204.0130 Removing Curb	32.000 LF	_____.	_____.
0016	204.0150 Removing Curb & Gutter	433.000 LF	_____.	_____.
0018	204.0155 Removing Concrete Sidewalk	120.000 SY	_____.	_____.
0020	204.0165 Removing Guardrail	476.000 LF	_____.	_____.
0022	204.0180 Removing Delineators and Markers	80.000 EACH	_____.	_____.
0024	204.0190 Removing Surface Drains	2.000 EACH	_____.	_____.
0026	205.0100 Excavation Common	2,136.000 CY	_____.	_____.
0028	208.0100 Borrow	5,523.000 CY	_____.	_____.
0030	213.0100 Finishing Roadway (project) 01. 5070-01-71	1.000 EACH	_____.	_____.
0032	305.0110 Base Aggregate Dense 3/4-Inch	6,028.000 TON	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71

Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	305.0120 Base Aggregate Dense 1 1/4-Inch	2,480.000 TON	_____.	_____.
0036	305.0130 Base Aggregate Dense 3-Inch	2,441.000 TON	_____.	_____.
0038	305.0500 Shaping Shoulders	923.000 STA	_____.	_____.
0040	415.0120 Concrete Pavement 12-Inch	164.600 SY	_____.	_____.
0042	415.1410 Concrete Pavement Approach Slab HES	106.700 SY	_____.	_____.
0044	416.1010 Concrete Surface Drains	4.400 CY	_____.	_____.
0046	440.4410 Incentive IRI Ride	30,569.000 DOL	1.00000	30,569.00
0048	455.0605 Tack Coat	19,649.000 GAL	_____.	_____.
0050	460.2005 Incentive Density PWL HMA Pavement	32,090.000 DOL	1.00000	32,090.00
0052	460.2010 Incentive Air Voids HMA Pavement	32,090.000 DOL	1.00000	32,090.00
0054	460.4110.S Reheating HMA Pavement Longitudinal Joints	48,173.000 LF	_____.	_____.
0056	460.5224 HMA Pavement 4 LT 58-28 S	32,090.000 TON	_____.	_____.
0058	465.0105 Asphaltic Surface	80.000 TON	_____.	_____.
0060	465.0120 Asphaltic Surface Driveways and Field Entrances	86.000 TON	_____.	_____.
0062	465.0310 Asphaltic Curb	12.000 LF	_____.	_____.
0064	465.0315 Asphaltic Flumes	65.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71

Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	502.0717.S Crack Sealing Epoxy	75.000 LF	_____.	_____.
0068	502.3100 Expansion Device (structure) 01. B-56-0011	LS	LUMP SUM	_____.
0070	502.3200 Protective Surface Treatment	597.000 SY	_____.	_____.
0072	502.4205 Adhesive Anchors No. 5 Bar	70.000 EACH	_____.	_____.
0074	505.0600 Bar Steel Reinforcement HS Coated Structures	1,790.000 LB	_____.	_____.
0076	509.0301 Preparation Decks Type 1	15.000 SY	_____.	_____.
0078	509.0302 Preparation Decks Type 2	8.000 SY	_____.	_____.
0080	509.0500 Cleaning Decks	565.000 SY	_____.	_____.
0082	509.1000 Joint Repair	32.000 SY	_____.	_____.
0084	509.1500 Concrete Surface Repair	8.000 SF	_____.	_____.
0086	509.2000 Full-Depth Deck Repair	3.800 SY	_____.	_____.
0088	509.2500 Concrete Masonry Overlay Decks	44.000 CY	_____.	_____.
0090	509.5100.S Polymer Overlay	134.000 SY	_____.	_____.
0092	520.8700 Cleaning Culvert Pipes	2.000 EACH	_____.	_____.
0094	520.9700.S Culvert Pipe Liners (size) 01. 24-INCH	174.000 LF	_____.	_____.
0096	520.9750.S Cleaning Culvert Pipes for Liner Verification	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71
Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Table with 5 columns: Proposal Line Number, Item ID Description, Approximate Quantity and Units, Unit Price, Bid Amount. Rows include items like Apron Endwalls for Culvert Pipe Steel, Concrete Curb & Gutter, Concrete Sidewalk, etc.



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71

Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0140	614.0390 Steel Plate Beam Guard Short Radius Terminal	2.000 EACH	_____.	_____.
0142	614.0515 Guardrail Stifened LHW	88.000 LF	_____.	_____.
0144	614.0920 Salvaged Rail	929.000 LF	_____.	_____.
0146	614.0925 Salvaged Guardrail End Treatments	24.000 EACH	_____.	_____.
0148	614.2300 MGS Guardrail 3	413.000 LF	_____.	_____.
0150	614.2330 MGS Guardrail 3 K	201.000 LF	_____.	_____.
0152	614.2500 MGS Thrie Beam Transition	680.000 LF	_____.	_____.
0154	614.2610 MGS Guardrail Terminal EAT	25.000 EACH	_____.	_____.
0156	614.8010 Anchor Post Assembly Top Mount	20.000 EACH	_____.	_____.
0158	618.0100 Maintenance And Repair of Haul Roads (project) 01. 5070-01-71	1.000 EACH	_____.	_____.
0160	619.1000 Mobilization	1.000 EACH	_____.	_____.
0162	624.0100 Water	33.700 MGAL	_____.	_____.
0164	625.0500 Salvaged Topsoil	29,028.000 SY	_____.	_____.
0166	627.0200 Mulching	21,040.000 SY	_____.	_____.
0168	628.1104 Erosion Bales	19.000 EACH	_____.	_____.
0170	628.1504 Silt Fence	12,055.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71

Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0172	628.1520 Silt Fence Maintenance	12,055.000 LF	_____.	_____.
0174	628.1905 Mobilizations Erosion Control	6.000 EACH	_____.	_____.
0176	628.1910 Mobilizations Emergency Erosion Control	3.000 EACH	_____.	_____.
0178	628.2002 Erosion Mat Class I Type A	12,999.000 SY	_____.	_____.
0180	628.2027 Erosion Mat Class II Type C	3,985.000 SY	_____.	_____.
0182	628.7010 Inlet Protection Type B	1.000 EACH	_____.	_____.
0184	628.7015 Inlet Protection Type C	1.000 EACH	_____.	_____.
0186	628.7504 Temporary Ditch Checks	394.000 LF	_____.	_____.
0188	628.7555 Culvert Pipe Checks	70.000 EACH	_____.	_____.
0190	628.7560 Tracking Pads	2.000 EACH	_____.	_____.
0192	628.7570 Rock Bags	66.000 EACH	_____.	_____.
0194	629.0210 Fertilizer Type B	22.780 CWT	_____.	_____.
0196	630.0110 Seeding Mixture No. 10	488.000 LB	_____.	_____.
0198	630.0200 Seeding Temporary	976.000 LB	_____.	_____.
0200	633.5200 Markers Culvert End	80.000 EACH	_____.	_____.
0202	634.0612 Posts Wood 4x6-Inch X 12-FT	8.000 EACH	_____.	_____.
0204	634.0614 Posts Wood 4x6-Inch X 14-FT	84.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71

Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0206	634.0616 Posts Wood 4x6-Inch X 16-FT	39.000 EACH	_____.	_____.
0208	634.0618 Posts Wood 4x6-Inch X 18-FT	11.000 EACH	_____.	_____.
0210	634.0622 Posts Wood 4x6-Inch X 22-FT	1.000 EACH	_____.	_____.
0212	637.2210 Signs Type II Reflective H	590.490 SF	_____.	_____.
0214	637.2230 Signs Type II Reflective F	415.000 SF	_____.	_____.
0216	638.2602 Removing Signs Type II	123.000 EACH	_____.	_____.
0218	638.3000 Removing Small Sign Supports	134.000 EACH	_____.	_____.
0220	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0222	643.0100 Traffic Control (project) 01. 5070-01-71	1.000 EACH	_____.	_____.
0224	643.0300 Traffic Control Drums	5,921.000 DAY	_____.	_____.
0226	643.0310.S Temporary Portable Rumble Strips	1.000 LS	_____.	_____.
0228	643.0410 Traffic Control Barricades Type II	84.000 DAY	_____.	_____.
0230	643.0420 Traffic Control Barricades Type III	319.000 DAY	_____.	_____.
0232	643.0705 Traffic Control Warning Lights Type A	638.000 DAY	_____.	_____.
0234	643.0715 Traffic Control Warning Lights Type C	456.000 DAY	_____.	_____.
0236	643.0900 Traffic Control Signs	4,573.000 DAY	_____.	_____.
0238	643.1050 Traffic Control Signs PCMS	28.000 DAY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71

Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0240	643.1070 Traffic Control Cones 42-Inch	252.000 DAY	_____.	_____.
0242	644.1420.S Temporary Pedestrian Surface Plywood	542.000 SF	_____.	_____.
0244	644.1601.S Temporary Curb Ramp	10.000 EACH	_____.	_____.
0246	644.1616.S Temporary Pedestrian Safety Fence	150.000 LF	_____.	_____.
0248	645.0120 Geotextile Type HR	69.000 SY	_____.	_____.
0260	648.0100 Locating No-Passing Zones	9.240 MI	_____.	_____.
0268	650.4500 Construction Staking Subgrade	2,400.000 LF	_____.	_____.
0270	650.5000 Construction Staking Base	2,400.000 LF	_____.	_____.
0272	650.5500 Construction Staking Curb Gutter and Curb & Gutter	1,054.000 LF	_____.	_____.
0274	650.6000 Construction Staking Pipe Culverts	15.000 EACH	_____.	_____.
0276	650.8000 Construction Staking Resurfacing Reference	49,379.000 LF	_____.	_____.
0278	650.9910 Construction Staking Supplemental Control (project) 01. 5070-01-71	LS	LUMP SUM	_____.
0280	650.9920 Construction Staking Slope Stakes	6,900.000 LF	_____.	_____.
0282	661.0100 Temporary Traffic Signals for Bridges (structure) 01. B-56-0011	LS	LUMP SUM	_____.
0284	661.0100 Temporary Traffic Signals for Bridges (structure) 02. B-56-0149	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71

Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0286	661.0100 Temporary Traffic Signals for Bridges (structure) 03. B-56-0468	LS	LUMP SUM	_____.
0288	690.0150 Sawing Asphalt	2,053.000 LF	_____.	_____.
0290	690.0250 Sawing Concrete	72.000 LF	_____.	_____.
0292	SPV.0035 Special 01. Deck Patching - Polymer Overlay	2.000 CY	_____.	_____.
0294	SPV.0060 Special 01. Adjust Water Valve Box	4.000 EACH	_____.	_____.
0296	SPV.0060 Special 02. HMA Percent Within Limits (PWL) Test Strip Volumetrics	2.000 EACH	_____.	_____.
0298	SPV.0060 Special 03. HMA Percent Within Limits (PWL) Test Strip Density	2.000 EACH	_____.	_____.
0300	SPV.0070 Special 01. Sprayed Asphaltic Shoulder Treatment	120.000 GAL	_____.	_____.
0302	SPV.0090 Special 02. Removing HMA Pavement Notched Wedge Longitudinal Milling	48,713.000 LF	_____.	_____.
0304	521.3136 Culvert Pipe Corrugated Steel 36-Inch	4.000 LF	_____.	_____.
0306	521.3148 Culvert Pipe Corrugated Steel 48-Inch	14.000 LF	_____.	_____.
0308	521.6124 Culvert Pipe Corrugated Steel Aluminum Coated 24-Inch	572.000 LF	_____.	_____.
0310	521.6130 Culvert Pipe Corrugated Steel Aluminum Coated 30-Inch	46.000 LF	_____.	_____.
0312	521.6148 Culvert Pipe Corrugated Steel Aluminum Coated 48-Inch	68.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20171212006 Project(s): 5070-01-71

Federal ID(s): WISC 2018028

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0314	522.2419 Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 19x30-Inch	146.000 LF	_____.	_____.
0316	522.2619 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 19x30-Inch	4.000 EACH	_____.	_____.
0318	646.1020 Marking Line Epoxy 4-Inch	92,434.000 LF	_____.	_____.
0320	646.3020 Marking Line Epoxy 8-Inch	600.000 LF	_____.	_____.
0322	646.4520 Marking Line Same Day Epoxy 4-Inch	58,129.000 LF	_____.	_____.
0324	646.6120 Marking Stop Line Epoxy 18-Inch	34.000 LF	_____.	_____.
0326	646.9000 Marking Removal Line 4-Inch	1,431.000 LF	_____.	_____.
0328	649.0105 Temporary Marking Line Paint 4-Inch	104,086.000 LF	_____.	_____.
0330	649.0150 Temporary Marking Line Removable Tape 4-Inch	3,374.000 LF	_____.	_____.
0332	649.0850 Temporary Marking Stop Line Removable Tape 18-Inch	84.000 LF	_____.	_____.
0334	650.9000 Construction Staking Curb Ramps	12.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

