

Wisconsin Department of Transportation

February 3, 2020

NOTICE TO ALL CONTRACTORS:

Proposal #14: 1228-22-72, WISC 2020 042

IH 43 North South Freeway Hampton Rd to Bender Rd

IH 43

Milwaukee County

Letting of February 11, 2020

This is Addendum No. 01, which provides for the following:

Special Provisions:

Division of T	ransportation	Systems
Developmen	t	

Bureau of Project Development 4822 Madison Yards Way, 4th Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

	Revised Special Provisions					
Article No.	L)escription					
3	Prosecution and Progress					
8	Other Contracts					
22	Labeling and Disposal of Waste Material					

Added Special Provisions					
Article No. De		Description			
ĺ	81	Notice to Contractor – Interstate Work Restriction			

Plan Sheets:

Revised Plan Sheets					
Plan Sheet	Plan Sheet Litle (brief description of changes to sheet)				
673	Structure B-40-581 revised the color for girder painting in the general notes to use the correct Blue color instead of Brown.				
678	Structure B-40-582 revised the color for girder painting in the general notes to use the correct Blue color instead of Brown.				
683	Structure B-40-583 revised the color for girder painting in the general notes to use the correct Blue color instead of Brown.				
688	Structure B-40-584 revised the color for girder painting in the general notes to use the correct Blue color instead of Brown.				
693	Structure B-40-585 revised the color for girder painting in the general notes to use the correct Blue color instead of Brown.				
698	Structure B-40-586 revised the color for girder painting in the general notes to use the correct Blue color instead of Brown.				
703	Structure B-40-587 revised the color for girder painting in the general notes to use the correct Blue color instead of Brown.				
704	Structure B-40-602 revised the color for girder painting in the general notes to use the correct Blue color instead of Brown.				

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

ADDENDUM NO. 01

1228-22-72

February 3, 2020

Special Provisions

3. Prosecution and Progress

Replace entire section titled Interim Liquidated Damages with the following:

Northbound IH 43 off-ramp over Lexington Avenue

At the beginning of Stage 1A operations, close the IH 43 northbound off ramp to Silver Spring Dr/Port Washington to through traffic for a maximum of 14 calendar days. Do not reopen until completing the following work: All work on Structure B-40-602 (except girder painting) and approach slabs.

If the contractor fails to complete the work necessary to reopen the ramp to Port Washington Rd (Intersection south of Silver Spring Rd.) to traffic within 14 calendar days, the department will assess the contractor \$6,000 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 14 calendar days. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

If the 14 days cannot be completed prior to the Article 81 Notice to Contractor – Interstate Work Restriction dates, the work should be started post Article 81 Notice to Contractor – Interstate Work Restriction Dates.

Northbound IH 43 off-ramp to Silver Spring Rd. and Port Washington Road

At the beginning of Stage 1A operations, close the IH 43 northbound off ramp to Silver Spring Dr/Port Washington to through traffic for a maximum of 30 calendar days. Do not reopen until completing the following work: All work on Structure B-40-602(except girder painting), all work on Structure B-40-586(except girder painting), all work on Structure B-40-587(except girder painting), new concrete pavement, and all approach slabs.

If the contractor fails to complete the work necessary to reopen the northbound off ramp to Silver Spring Dr/Port Washington Rd in its entirety to traffic within 30 calendar days, the department will assess the contractor \$4,500 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 30 calendar days. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

If the 14 days cannot be completed prior to the Article 81 Notice to Contractor – Interstate Work Restriction dates, the work should be started post Article 81 Notice to Contractor – Interstate Work Restriction Dates.

Northbound IH 43 on-ramp from Silver Spring Rd. and Port Washington Road

At the beginning of Stage 1B operations, close the IH 43 northbound on ramp from Silver Spring Dr/Port Washington to through traffic for a maximum of 21 calendar days. Do not reopen until completing the following work: All work on Structure B-40-585(except girder painting) and approach slabs.

If the contractor fails to complete the work necessary to reopen the northbound on ramp from Silver Spring Dr/Port Washington Rd in its entirety to traffic within 21 calendar days, the department will assess the contractor \$2,500 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 21 calendar days. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

IH 43 Northbound Mainline

Once all work on the IH 43 Northbound off-ramp is entirely complete (except for girder painting), work may commence on IH 43 northbound. Reduce the number of IH 43 northbound lanes to 2 lanes of through traffic

for a maximum of 60 calendar days. Do not reopen until completing the following work: PMA overlay and joint repair on Structure B-40-581, PMA overlay and joint repair on Structure B-40-583, and approach slabs.

If the contractor fails to complete the work necessary to reopen all lanes of northbound IH 43 to traffic within 60 calendar days, the department will assess the contractor \$15,000 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 60 calendar days. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

IH 43 Southbound Mainline

At the beginning of Stage 1B operations, reduce the IH 43 southbound to 2 lanes of through traffic for a maximum of 60 calendar days. Do not reopen until completing the following work: PMA overlay and joint repair on Structure B-40-582, PMA overlay and joint repair on Structure B-40-584, and approach slabs.

If the contractor fails to complete the work necessary to reopen all lanes of southbound IH 43 to traffic within 60 calendar days, the department will assess the contractor \$5,000 in interim liquidated damages for each calendar day the contract work remains incomplete beyond 60 calendar days. An entire calendar day will be charged for any period of time within a calendar day that the road remains closed beyond 12:01 AM.

If contract time expires prior to completing all work specified in the contract, additional liquidated damages will be affixed according to standard spec 108.11.

Add the follow sentence to the end of the Port Washington Road section of the Local Road restrcitions section:

Do not start Stage 2A work until all Stage 1 A&B work is complete.

8. Other Contracts

Add the following projects to the end of the article:

City of Glendale Project G0580230

Silver Spring Rd., Silver Spring Rd Pavement Replacement Glendale Contact: Andy Ashley, 414-831-2869, Andrew.Ashley@clarkdietz.com

City of Glendale Project G0580290

Silver Spring Rd., Port Washington Rd., Port Washington Rd Intersection Pavement Replacement Glendale Contact: Andy Ashley, 414-831-2869, Andrew.Ashley@clarkdietz.com

22. Labeling and Disposal of Waste Material

Replace the first 8 rows of text with the following:

The EPA ID number for Structure B-40-581 is WIR000172106.

The EPA ID number for Structure B-40-582 is WIR000172106.

The EPA ID number for Structure B-40-583 is WIR000172114.

The EPA ID number for Structure B-40-584 is WIR000172114.

The EPA ID number for Structure B-40-585 is WIR000172122.

The EPA ID number for Structure B-40-586 is WIR000172130.

The EPA ID number for Structure B-40-587 is WIR000172148.

The EPA ID number for Structure B-40-602 is WIR000172155.

81. Notice to Contractor – Interstate Work Restriction

From 5:30AM Thursday July 9th to 11:59 PM Friday July 17th, 2020:

Do not perform work; haul equipment; or haul materials, on, along, or across any portion of IH 43, Silver Spring Drive, Hampton Avenue, and Port Washington Road, including ramps. Any exceptions to this work restriction must be approved by the engineer in writing.

Roadway and traffic control maintenance required by the contractor shall be performed as needed during this work restriction. Coordinate with the project engineer for approval in advance of performing necessary roadway or traffic control maintenance work.

Plan Sheets

The following $8\frac{1}{2}$ x 11-inch sheets are attached and made part of the plans for this proposal: Revised: 673, 678, 683, 688, 693, 698, 703, and 704.

END OF ADDENDUM















