



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

March 3, 2020

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #20: 1053-02-82, WISC 2020 077**  
**Wausau - Wittenberg**  
**Hilltop Road to CTH D, EB**  
**STH 29**  
**Marathon County**

### Letting of March 10, 2020

This is Addendum No. 01, which provides for the following:

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0120	Removing Asphaltic Surface Milling	SY	---	28,547	28,547

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0125	Removing Asphaltic Surface Milling	Ton	4,292	-4,292	0

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
30	Miscellaneous Quantities – 1 (Removed bid item 204.0125, replaced with bid item 204.0120)

**Schedule of Items**

Attached, dated March 3, 2020, are the revised Schedule of Items Pages 1 – 3.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 30

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

Addendum No. 01  
 ID 1053-02-82  
 Revised Sheet 30  
 March 3, 2020

**EXCAVATION COMMON**

DIVISION	STATION - STATION	LOCATION	205.0100 CUT (2) CY	UNEXPANDED FILL CY	EXPANDED FILL (13) CY	MASS ORDINATE +/- (14) CY	WASTE CY
DIVISION 1	2852+50EB - 2856+50EB	STH 29 (EB)	1,153	7	9	1,144	1,144
DIVISION 1 SUBTOTAL			1,153	7	9	1,144	1,144
GRAND TOTAL			1,153	7	9	1,144	1,144
<b>TOTAL</b>			<b>1,153</b>				

NOTES:  
 (2) Salvaged/Unusable Pavement Material is included in Cut.  
 (13) Expanded Fill Factor = 1.25  
 (14) The Mass Ordinate + or - Qty calculated for the Division. Plus quantity indicates an excess of material within the Division. Minus indicates a shortage of material within the Division.

**REMOVING ASPHALTIC SURFACE BUTT JOINTS**

STATION - STATION	LOCATION	204.0115 SY	REMARKS
2784+95EB - 2785+05EB	STH 29 (EB)	27	
2833+90EB - 2834+00EB	STH 29 (EB)	27	
2858+77EB - 2859+38EB	STH 29 (EB) - MEDIAN	68	
2859+85EB - 2859+95EB	STH 29 (EB)	27	
2858+90EB - 2859+34EB	CHERRY ST	49	
<b>TOTAL</b>			<b>198</b>

**REMOVING ASPHALTIC SURFACE BUTT JOINTS**

STATION - STATION	LOCATION	204.0115 SY	REMARKS
2779+75EB - 2784+95EB	STH 29 (EB) LT SHLD	17	
2784+95EB - 2792+05EB	STH 29 (EB)	271	
2792+05EB - 2826+40EB	STH 29 (EB)	1154	
2826+40EB - 2833+99EB	STH 29 (EB)	287	
2833+99EB - 2852+50EB	STH 29 (EB) LT & RT SHLD	181	
2844+85EB - 2852+50EB	STH 29 (EB) LT SHLD	100	
2852+50EB - 2856+50EB	STH 29 (EB)	559	
2856+50EB - 2859+95EB	STH 29 (EB)	169	
CTHD	STH 29 MEDIAN	27	
CTHD	SIDEROAD	36	
<b>TOTALS</b>			<b>2465</b>
<b>TOTALS</b>			<b>2719</b>
<b>TOTALS</b>			<b>245</b>

**REMOVING ASPHALTIC SURFACE MILING**

STATION - STATION	LOCATION	204.0120 SY	REMARKS
2779+75EB - 2784+95EB	STH 29 (EB) LT SHLD	173	
2784+95EB - 2792+05EB	STH 29 (EB)	2130	
2792+05EB - 2826+40EB	STH 29 (EB) RT SHLD	631	
2826+40EB - 2833+99EB	STH 29 (EB)	12977	
2833+99EB - 2852+50EB	STH 29 (EB) RT SHLD	3053	
2852+50EB - 2856+50EB	STH 29 (EB) LT & RT SHLD	2807	
2856+50EB - 2859+95EB	STH 29 (EB) LT & RT SHLD	675	
2859+95EB - 2859+95EB	STH 29 (EB) LT & RT SHLD	1596	
CTHD	STH 29 MEDIAN	1342	
CTHD	SIDEROAD	364	
<b>TOTAL</b>			<b>28547</b>

**BASE AGGREGATE DENSE**

STATION - STATION	LOCATION	305.0110 TON	305.0120 TON	REMARKS
2779+75EB - 2784+95EB	STH 29 (EB) - LT SHLD	11		
2784+95EB - 2792+05EB	STH 29 (EB) - LT SHLD	15		
2792+05EB - 2852+50EB	STH 29 (EB) - RT SHLD	94		
2826+40EB - 2844+85EB	STH 29 (EB) - LT SHLD	38		
2844+85EB - 2852+50EB	STH 29 (EB) - LT SHLD	37		
2852+50EB - 2856+50EB	STH 29 (EB) - DRIVING LANES	383		
2856+50EB - 2859+95EB	STH 29 (EB) - LT & RT SHLD	25		
CTHD	STH 29 (EB) - LT & RT SHLD	12		
<b>TOTAL</b>		<b>232</b>	<b>763</b>	

**HMA PAVEMENT**

STATION - STATION	LOCATION	460.6223 TON	460.6424 TON	465.0110 TON	REMARKS
2779+75EB - 2784+95EB	STH 29 (EB) LT SHLD	---	17	---	
2784+95EB - 2792+05EB	STH 29 (EB)	269	271	---	
2792+05EB - 2826+40EB	STH 29 (EB)	1154	1472	---	
2826+40EB - 2833+99EB	STH 29 (EB)	287	289	---	
2833+99EB - 2852+50EB	STH 29 (EB) LT & RT SHLD	---	181	---	
2844+85EB - 2852+50EB	STH 29 (EB) LT SHLD	---	100	---	
2852+50EB - 2856+50EB	STH 29 (EB)	559	170	---	
2856+50EB - 2859+95EB	STH 29 (EB)	169	162	---	
CTHD	STH 29 MEDIAN	27	21	---	
CTHD	SIDEROAD	---	36	---	
<b>TOTALS</b>		<b>2465</b>	<b>2719</b>	<b>245</b>	

**PREPARE FOUNDATION FOR ASPHALTIC SHOULDERS**

STATION - STATION	LOCATION	211.0400 STA	REMARKS
2844+85EB - 2852+50EB	STH 29 (EB) LT SHLD	8	
<b>TOTAL</b>			<b>8</b>

**MISCELLANEOUS QUANTITIES - 1**

STATION - STATION	LOCATION	305.0110 TON	305.0120 TON	REMARKS
		305.0110 TON	305.0120 TON	
		3/4-INCH	1 1/4-INCH	

**PROJECT NO: 1053-02-82**

HWY: STH 29

COUNTY: MARATHON

FILE NAME: \\N31103\public\project\1053-02-82-STH-29-Marathon\Quantities\1053028\_misp.klt

PLOT DATE: 3/22/20 9:38 AM

PLOT BY: \_\_\_\_\_

PLOT NAME: 62600070.misp.klt

PLOT SCALE: 1:1

**PROJECT NO: 1053-02-82**

HWY: STH 29

COUNTY: MARATHON

FILE NAME: \\N31103\public\project\1053-02-82-STH-29-Marathon\Quantities\1053028\_misp.klt

PLOT DATE: 3/22/20 9:38 AM

PLOT BY: \_\_\_\_\_

PLOT NAME: 62600070.misp.klt

PLOT SCALE: 1:1

**SHEET: 30**



## Proposal Schedule of Items

Proposal ID: 20200310020 Project(s): 1053-02-82

Federal ID(s): WISC 2020077

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0110 Removing Asphaltic Surface	510.000 SY	_____.	_____.
0004	204.0115 Removing Asphaltic Surface Butt Joints	198.000 SY	_____.	_____.
0008	205.0100 Excavation Common	1,153.000 CY	_____.	_____.
0010	211.0400 Prepare Foundation for Asphaltic Shoulders	8.000 STA	_____.	_____.
0012	213.0100 Finishing Roadway (project) 01. 1053-02-82	1.000 EACH	_____.	_____.
0014	305.0110 Base Aggregate Dense 3/4-Inch	232.000 TON	_____.	_____.
0016	305.0120 Base Aggregate Dense 1 1/4-Inch	753.000 TON	_____.	_____.
0018	455.0605 Tack Coat	3,191.000 GAL	_____.	_____.
0020	460.2000 Incentive Density HMA Pavement	3,320.000 DOL	1.00000	3,320.00
0022	460.6223 HMA Pavement 3 MT 58-28 S	2,465.000 TON	_____.	_____.
0024	460.6424 HMA Pavement 4 MT 58-28 H	2,719.000 TON	_____.	_____.
0026	465.0110 Asphaltic Surface Patching	245.000 TON	_____.	_____.
0028	465.0400 Asphaltic Shoulder Rumble Strips	13,379.000 LF	_____.	_____.
0030	618.0100 Maintenance And Repair of Haul Roads (project) 01. 1053-02-82	1.000 EACH	_____.	_____.
0032	619.1000 Mobilization	1.000 EACH	_____.	_____.
0034	624.0100 Water	10.000 MGAL	_____.	_____.



## Proposal Schedule of Items

Proposal ID: 20200310020 Project(s): 1053-02-82

Federal ID(s): WISC 2020077

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0036	625.0100 Topsoil	535.000 SY	_____.	_____.
0038	628.1905 Mobilizations Erosion Control	2.000 EACH	_____.	_____.
0040	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____.	_____.
0042	628.7010 Inlet Protection Type B	9.000 EACH	_____.	_____.
0044	628.7555 Culvert Pipe Checks	10.000 EACH	_____.	_____.
0046	629.0210 Fertilizer Type B	0.340 CWT	_____.	_____.
0048	630.0130 Seeding Mixture No. 30	9.600 LB	_____.	_____.
0050	630.0500 Seed Water	3.000 MGAL	_____.	_____.
0052	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0054	643.0300 Traffic Control Drums	2,358.000 DAY	_____.	_____.
0056	643.0420 Traffic Control Barricades Type III	132.000 DAY	_____.	_____.
0058	643.0705 Traffic Control Warning Lights Type A	264.000 DAY	_____.	_____.
0060	643.0715 Traffic Control Warning Lights Type C	648.000 DAY	_____.	_____.
0062	643.0800 Traffic Control Arrow Boards	85.000 DAY	_____.	_____.
0064	643.0900 Traffic Control Signs	825.000 DAY	_____.	_____.
0066	643.1050 Traffic Control Signs PCMS	7.000 DAY	_____.	_____.
0068	643.5000 Traffic Control	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200310020 Project(s): 1053-02-82

Federal ID(s): WISC 2020077

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0070	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	14,814.000 LF	_____.	_____.
0072	646.1555 Marking Line Grooved Contrast Permanent Tape 4-Inch	2,212.500 LF	_____.	_____.
0074	646.3040 Marking Line Grooved Wet Ref Epoxy 8-Inch	360.000 LF	_____.	_____.
0076	646.9000 Marking Removal Line 4-Inch	1,320.000 LF	_____.	_____.
0078	649.0150 Temporary Marking Line Removable Tape 4-Inch	2,640.000 LF	_____.	_____.
0080	650.5000 Construction Staking Base	400.000 LF	_____.	_____.
0082	650.8000 Construction Staking Resurfacing Reference	7,500.000 LF	_____.	_____.
0084	650.9910 Construction Staking Supplemental Control (project) 01. 1053-02-82	LS	LUMP SUM	_____.
0086	690.0150 Sawing Asphalt	478.000 LF	_____.	_____.
0088	740.0440 Incentive IRI Ride	4,000.000 DOL	1.00000	4,000.00
0090	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	300.000 HRS	5.00000	1,500.00
0092	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	600.000 HRS	5.00000	3,000.00
0094	204.0120 Removing Asphaltic Surface Milling	28,547.000 SY	_____.	_____.

Section: 0001

Total: \_\_\_\_\_.

Total Bid: \_\_\_\_\_.