



Wisconsin Department of Transportation

February 26, 2020

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

- Proposal #36:**
- | | |
|---|--|
| <p>8357-01-72, WISC 2017405
T Russell, Little Sand Bay Road
Old Cth K To Termini
TWN RD
Bayfield County</p> | <p>8357-01-73, WISC FLAP030
T Russell, Old Cth K Road
Little Sand Bay Rd To Peterson Hill
LOC STR
Bayfield County</p> |
| <p>8357-01-74, WISC FLAP49C
T Russell, Old Cth K Road
Peterson Hill Road – Leask Drive
LOC STR
Bayfield County</p> | |

Letting of March 10, 2020

This is Addendum No. 02, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
201.0105	Clearing	STA	0	72	72
201.0205	Grubbing	STA	0	72	72

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
37	Added quantities for clearing and grubbing.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 02

8357-01-72/73/74

February 26, 2020

Special Provisions

3. Prosecution and Progress.

*Replace the paragraph two under section titled **Northern Long-eared Bat (*Myotis septentrionalis*)** with the following:*

In accordance to the final 4(d) rule issued for the NLEB, the department has determined that the proposed activity may affect, but will not result in prohibited take of the NLEB. The activity involves tree removal, but will not occur within 0.25 miles of a known hibernacula, nor will the activity remove a known maternity roost tree or any other tree within 150 feet of a known maternity roost tree.

Schedule of Items

Attached, dated February 26, 2020 are the revised Schedule of Items Page 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Revised: 37

END OF ADDENDUM

Addendum No. 02
ID 8357-01-72/73/74
Revised Sheet 37
February 26, 2020

REMOVING TREES

LOCATION	201.0105 CLEARING	201.0205 GRUBBING	STA	STA
PROJECT 8357-01-72 LITTLE SAND BAY RD 188+50	11	11	11	11
PROJECT 8357-01-72 SUBTOTAL	11	11		
PROJECT 8357-01-73 OLD COUNTY K 638+00 - 646+00	8	8	8	8
651+00 - 660+00	9	9	9	9
666+00 - 686+00	20	20	20	20
PROJECT 8357-01-73 SUBTOTAL	37	37		
PROJECT 8357-01-74 OLD COUNTY K 691+00 - 707+00	16	16	16	16
728+00 - 736+00	8	8	8	8
PROJECT 8357-01-74 SUBTOTAL	24	24		
ITEM TOTALS	72	72		

REMOVING SMALL PIPE CULVERTS

STATION	203.0100 LOCATION	EACH	COMMENT
PROJECT 8357-01-72 LITTLE SAND BAY RD 188+50	LT & RT	1	15X56 CMP
190+61	LT & RT	1	48X50 CMP
	LT & RT	1	18X69 CMP
PROJECT 8357-01-72 SUBTOTAL		3	
ITEM TOTAL		3	

REMOVING DELINEATORS AND MARKERS

STATION	LOCATION	204.0180 EACH
PROJECT 8357-01-73 OLD COUNTY K 636+00 - 646+00	LT & RT	26
PROJECT 8357-01-73 SUBTOTAL		26
ITEM TOTAL		26

PREPARE FOUNDATION FOR

211.0100 ASPHALTIC PAVING	211.0100 ASPHALTIC PAVING	211.0100 BASE	211.0500 AGGREGATE	STA
PROJECT 8357-01-72 LITTLE SAND BAY RD 100+16.09 - 239+06.45	1			120
PROJECT 8357-01-72 SUBTOTAL	1			120
PROJECT 8357-01-73 OLD COUNTY K 601+00.00 - 690+10.00	1			90
PROJECT 8357-01-73 SUBTOTAL	1			90
PROJECT 8357-01-74 OLD COUNTY K 690+10.00 - 765+00.00		1		75
PROJECT 8357-01-74 SUBTOTAL		1		75
ITEM TOTALS	1	1		285

EARTHWORK SUMMARY

DIVISION	STATION	EXCAVATION COMMON CY	BORROW CY	UNEXPANDED FILL CY	EXPANDED FILL CY	WASTE CY
DIVISION 1		205.0100	208.1100			
PROJECT 8357-01-72 LITTLE SAND BAY ROAD 100+16 - 239+39	906	1581	1920	2487	0	0
PROJECT 8357-01-72 SUBTOTAL	906	1581	1920	2487	0	0
DIVISION 1 TOTAL	906	1581	1920	2487	0	0
DIVISION 2						
PROJECT 8357-01-73 OLD COUNTY K 601+00 - 690+10	832	7309	6267	8141	0	0
PROJECT 8357-01-73 SUBTOTAL	832	7309	6267	8141	0	0
DIVISION 2 TOTAL	832	7309	6267	8141	0	0
DIVISION 3						
PROJECT 8357-01-74 OLD COUNTY K 690+10 - 765+00	610	981	1220	1591	0	0
PROJECT 8357-01-74 SUBTOTAL	610	981	1220	1591	0	0
DIVISION 3 TOTAL	610	981	1220	1591	0	0
GRAND TOTALS	2348	9871				

FINISHING ROADWAY (PROJECT)

STATION	LOCATION	213.0100 EACH
PROJECT 8357-01-72 LITTLE SAND BAY RD 100+16.09 - 239+06.45		1
PROJECT 8357-01-72 SUBTOTAL		1
PROJECT 8357-01-73 OLD COUNTY K 601+00.00 - 690+10.00		1
PROJECT 8357-01-73 SUBTOTAL		1
PROJECT 8357-01-74 OLD COUNTY K 690+10.00 - 765+00.00		1
PROJECT 8357-01-74 SUBTOTAL		1
ITEM TOTAL		3

NOTE: ALL ITEMS AND QUANTITIES ON THIS SHEET
ARE FOR ENGINEER ESTIMATE CATEGORY 0010,
UNLESS OTHERWISE NOTED.

PROJECT NO: 8357-01-72

HWY: LITTLE SAND BAY RD

COUNTY: BAYFIELD

MISCELLANEOUS QUANTITIES

SHEET 37

E



Proposal Schedule of Items

Proposal ID: 20200310036 Project(s): 8357-01-72, 8357-01-73, 8357-01-74

Federal ID(s): WISC 2017405, WISC FLAP030, WISC FLAP49C

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0128	650.9910 Construction Staking Supplemental Control (project) 03. 8357-01-74	LS	LUMP SUM	_____.
0130	650.9920 Construction Staking Slope Stakes	30,290.000 LF	_____.	_____.
0132	690.0150 Sawing Asphalt	476.000 LF	_____.	_____.
0134	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	2,000.000 HRS	5.00000	10,000.00
0136	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,260.000 HRS	5.00000	6,300.00
0138	SPV.0090 Special 01. Culvert Pipe Corrugated Polyethylene 48-Inch	60.000 LF	_____.	_____.
0140	201.0105 Clearing	72.000 STA	_____.	_____.
0142	201.0205 Grubbing	72.000 STA	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

