



Wisconsin Department of Transportation

April 29, 2020

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #25 6220-00-72
Waupaca - Clintonville
STH 110S – STH 54E/S Br Little Wolf
STH 22
Waupaca County

Letting of May 12, 2020

This is Addendum No. 1, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
14	Field Office

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0120	Removing Asphaltic Surface Milling	SY	54,079	-97	53,982

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
642.5001	Field Office Type B	Each	0	1	1

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
12	Miscellaneous Quantities – Revised Removing Asphaltic Surface Milling

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

6220-00-72

April 30, 2020

Special Provisions

14. Field Office.

Add the following to standard spec 642:

For field offices without handwashing facilities, the contractor will be required to provide and maintain a portable handwashing station at the project field office. The station shall include a hands-free sink with foot pump-operated faucet, soap dispenser, paper towel dispenser, fresh water supply, and collection tank for gray water. Regularly service and maintain the handwashing station and all supplies as needed, and properly dispose of all materials. Costs associated with the handwashing station are incidental to the field office bid item.

Schedule of Items

Attached, dated April 30, 2020, are the revised Schedule of Items Pages 1 – 3.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 12

END OF ADDENDUM

**204.0115
REMOVING ASPHALTIC SURFACE BUTT JOINTS**

STATION	LOCATION	SY
331+00	STH 22, BEGIN PROJECT	33
337+13	STH 110 SOUTH	44
364+77	KUENZI ROAD	27
394+88	BIGALKE ROAD	27
462+07	STH 54 EAST, END PROJECT	33
19W+19	STH 110 NORTH, END PROJECT	44
TOTAL:		208

**211.0100
PREPARATION OF FOUNDATION FOR ASPHALTIC SURFACE**

LOCATION	LS
STH 22 / PROJECT 01, 6220-00-72	1
TOTAL:	1

**305.0110
BASE AGGREGATE DENSE 3/4-INCH**

LOCATION	STATION	TO	STATION	TON	WATER MGAL
STH 22 NORTHBOUND	331+00	-	462+07	1,133	17
STH 22 SOUTHBOUND	331+00	-	462+07	1,133	17
STH 22/110 NORTHBOUND	10W+50	-	19W+19	75	1
STH 22/110 SOUTHBOUND	10W+50	-	19W+19	75	1
UNDISTRIBUTED	-	-	-	84	-
TOTAL:				2,500	36

**204.0120
REMOVING ASPHALTIC SURFACE MILLING**

LOCATION	STATION	TO	STATION	SY
STH 22 NORTHBOUND	331+00	-	462+07	21,845
STH 22 SOUTHBOUND	331+00	-	462+07	21,845
STH 22 NORTHBOUND RIGHT TURN LANE	332+74	-	336+26	302
STH 110 SOUTH	336+26	-	338+43	1,039
STH 22 SOUTHBOUND BYPASS LANE	334+07	-	340+29	561
KUENZI ROAD	363+29	-	366+45	782
BIGALKE ROAD	393+66	-	396+84	536
STH 22 NORTHBOUND BYPASS LANE	453+30	-	459+53	641
STH 22/110/54	455+39	-	457+52	544
STH 54 SOUTHBOUND RIGHT TURN LANE	457+52	-	462+07	402
STH 22/110 NORTHBOUND	10W+72	-	19W+19	1,524
STH 22/110 SOUTHBOUND	10W+72	-	19W+19	1,729
3" SAFETY EDGE, STH 22 RT/LT	331+00	-	462+07	728
CENTERLINE JOINT, STH 22	331+00	-	462+07	1,456
3" SAFETY EDGE RT/LT, STH 22/110	10W+50	-	19W+19	48
TOTAL:				53,982

HMA PAVEMENT ITEMS

LOCATION	STATION	TO	STATION	TACK COAT	4 MT 58-28 \$
STH 22 NORTHBOUND	331+00	-	462+07	1,529	2,450
STH 22 SOUTHBOUND	331+00	-	462+07	1,529	2,450
STH 22 NORTHBOUND RIGHT TURN LANE	332+74	-	336+26	21	30
STH 110 SOUTH	336+26	-	338+43	73	120
STH 22 SOUTHBOUND BYPASS LANE	334+07	-	340+29	39	60
KUENZI ROAD	363+29	-	366+45	55	90
BIGALKE ROAD	393+66	-	396+84	38	60
STH 22 NORTHBOUND BYPASS LANE	453+30	-	459+53	45	70
STH 22/110/54	455+39	-	457+52	38	60
STH 54 SOUTHBOUND RIGHT TURN LANE	457+52	-	462+07	28	40
STH 22/110 NORTHBOUND	10W+72	-	19W+19	107	170
STH 22/110 SOUTHBOUND	10W+72	-	19W+19	121	190
3" SAFETY EDGE, STH 22 RT/LT	331+00	-	462+07	51	40
CENTERLINE JOINT, STH 22	331+00	-	462+07	102	80
3" SAFETY EDGE RT/LT, STH 22/110	10W+50	-	19W+19	3	5
CENTERLINE JOINT, STH 22/110	10W+50	-	19W+19	7	10
TOTAL:				3,786	5,925

Addendum No. 01
ID 6220-00-72
Revised Sheet 12
April 30, 2020



Proposal Schedule of Items

Proposal ID: 20200512025 Project(s): 6220-00-72

Federal ID(s): WISC 2020265

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0115 Removing Asphaltic Surface Butt Joints	208.000 SY	_____.	_____.
0004	204.0120 Removing Asphaltic Surface Milling	53,982.000 SY	_____.	_____.
0006	204.0185 Removing Masonry	4.000 CY	_____.	_____.
0008	211.0100 Prepare Foundation for Asphaltic Paving (project) 01. 6220-00-72	LS	LUMP SUM	_____.
0010	213.0100 Finishing Roadway (project) 01. 6220-00-72	1.000 EACH	_____.	_____.
0012	305.0110 Base Aggregate Dense 3/4-Inch	2,500.000 TON	_____.	_____.
0014	455.0605 Tack Coat	3,786.000 GAL	_____.	_____.
0016	460.2000 Incentive Density HMA Pavement	3,800.000 DOL	1.00000	3,800.00
0018	460.6224 HMA Pavement 4 MT 58-28 S	5,925.000 TON	_____.	_____.
0020	465.0110 Asphaltic Surface Patching	593.000 TON	_____.	_____.
0022	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	11,551.000 LF	_____.	_____.
0024	504.0900 Concrete Masonry Endwalls	4.000 CY	_____.	_____.
0026	618.0100 Maintenance And Repair of Haul Roads (project) 01. 6220-00-72	1.000 EACH	_____.	_____.
0028	619.1000 Mobilization	1.000 EACH	_____.	_____.
0030	624.0100 Water	36.000 MGAL	_____.	_____.
0032	625.0100 Topsoil	114.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200512025 Project(s): 6220-00-72

Federal ID(s): WISC 2020265

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0034	628.1504 Silt Fence	150.000 LF	_____.	_____.
0036	628.1520 Silt Fence Maintenance	150.000 LF	_____.	_____.
0038	628.2002 Erosion Mat Class I Type A	114.000 SY	_____.	_____.
0040	629.0210 Fertilizer Type B	0.100 CWT	_____.	_____.
0042	630.0160 Seeding Mixture No. 60	3.000 LB	_____.	_____.
0044	630.0500 Seed Water	2.600 MGAL	_____.	_____.
0046	643.0900 Traffic Control Signs	538.000 DAY	_____.	_____.
0048	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0050	646.1020 Marking Line Epoxy 4-Inch	24,399.000 LF	_____.	_____.
0052	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	27,363.000 LF	_____.	_____.
0054	646.3020 Marking Line Epoxy 8-Inch	469.000 LF	_____.	_____.
0056	646.4520 Marking Line Same Day Epoxy 4-Inch	24,399.000 LF	_____.	_____.
0058	646.6120 Marking Stop Line Epoxy 18-Inch	72.000 LF	_____.	_____.
0060	648.0100 Locating No-Passing Zones	2.700 MI	_____.	_____.
0062	649.0105 Temporary Marking Line Paint 4-Inch	23,981.000 LF	_____.	_____.
0064	650.8000 Construction Staking Resurfacing Reference	14,026.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200512025 Project(s): 6220-00-72

Federal ID(s): WISC 2020265

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0066	650.9910 Construction Staking Supplemental Control (project) 01. 6220-00-72	LS	LUMP SUM	_____.
0068	740.0440 Incentive IRI Ride	10,625.000 DOL	1.00000	10,625.00
0070	SPV.0180 Special 01. Removing Distressed Pavement Milling	3,740.000 SY	_____.	_____.
0072	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.