

# **Wisconsin Department of Transportation**

July 9, 2020

# **Division of Transportation Systems Development**

Bureau of Project Development 4822 Madison Yards Way, 4<sup>th</sup> Floor South Madison, WI 53705

Telephone: (608) 266-1631 Facsimile (FAX): (608) 266-8459

### **NOTICE TO ALL CONTRACTORS:**

Proposal #06: 3763-00-74

CTH KR, V Mt Pleasant

CTH H to Old Greenbay Road

**CTH KR** 

**Racine County** 

### Letting of July 14, 2020

This is Addendum No. 02, which provides for the following:

### **Special Provisions:**

	Revised Special Provisions				
Article No.	Description				
4	Prosecution and Progress.				
39	Removing Old Structure Over Waterway With Minimal Debris Station 566+00, Item 203.0600.S.200, Removing Old Structure Over Waterway With Minimal Debris Station 566+00, Item 203.0600.S.201.				
80	EBS Backfill, Item SPV.0035.002.				

### **Schedule of Items:**

Revised Bid Item Quantities						
Bid Item	Itam Description	Linit	Old	Revised	Proposal	
Did item	Item Description	Unit	Quantity	Quantity	Total	
205.0100	Excavation Common	CY	351,023	27,840	378,863	
SPV.0035.003	Roadway Embankment	CY	635,684	30,267	665,951	

	Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total	
203.0600.S.202	Removing Old Structure Over Waterway With Minimal Debris STA 565+95	LS	0	1	1	

## Plan Sheets:

	Revised Plan Sheets			
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)			
80	Removal Plan – CTH KR (added/updated removing old structure)			
411	Miscellaneous Quantities (added 'Removing Old Structure' table)			
413	Miscellaneous Quantities (updated 'Earthwork' table)			
801	Structure B-30-143 (updated bill of bars table)			
826	Structure B-30-144 (updated bill of bars table)			
839	Structure B-30-145 (updated girder end detail)			
864	Structure B-30-146 (updated girder end detail)			
886	Structure B-30-147 (updated girder end detail)			
908	Structure B-30-149 (updated girder end detail)			

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist Proposal Management Section

# ADDENDUM NO. 02 3763-00-74 July 9, 2020

#### **Special Provisions**

#### 4. Prosecution and Progress.

Replace bullet 6) under subsection Construction Activities under section titled Stage 2 – March 2021 to June 2021 with the following:

6) Continue grading & fill placement on new CTH KR at CPRR and UPRR approaches

Replace bullet 7) under subsection Construction Activities under section titled Stage 3 – June 2021 to November 2021 under subsection West Construction Activities – CTH H to STH 31 with the following:

7) Finish earthwork on new CTH KR at CPRR and UPRR approaches

Replace paragraph nine under section titled **B Work Restrictions** with the following:

To allow for proper settlement of embankment fills, do not place concrete pavement, breaker run, base course, anchor slabs or structure approaches from Station 465+00 to 476+69; 478+25 to 489+00, 524+00 to 532+53; and 534+08 to 540+00 (bridge approaches to CPRR and UPRR) until May 1, 2022 or as approved by the engineer. Do not place final surface on the Park Access Road until use of Contractor Staging Area 2 is complete.

39. Removing Old Structure Over Waterway With Minimal Debris Station 566+00, Item 203.0600.S.200, Removing Old Structure Over Waterway With Minimal Debris Station 566+00, Item 203.0600.S.201.

Update title to Removing Old Structure Over Waterway With Minimal Debris Station 566+00, Item 203.0600.S.200; Removing Old Structure Over Waterway With Minimal Debris Station 566+00, Item 203.0600.S.201; Removing Old Structure Over Waterway With Minimal Debris Station 565+95, Item 203.0600.S.202.

Replace the entire article with the following:

Conform to standard spec 203 as modified in this special provision.

Add the following to standard spec 203:

#### 203.3.6 Removals Over Waterways and Wetlands

#### 203.3.6.2 Removing Old Structure Over Waterway with Minimal Debris

(1) Remove the existing 3-cell box culvert Structure B-30-75 over the Pike River in large sections and conforming to the contractor's approved structure removal and clean-up plan. As shown in the plans item number 203.0600.S.200 is associated with B-30-143 for removal of the right side of the box culvert, and item number 203.0600.S.201 is associated with B-30-144 for removal of the left side of the box culvert.

As shown in the plans, item number 203.0600.S.202 is associated with the removal of the existing substructure of the pedestrian bridge over the Pike River just south of CTH KR. The salvaging of the superstructure will be paid separately under the bid item Salvage Pedestrian Bridge Superstructure, Item SPV.0105.002.

During removal, prevent all large pieces and minimize the number of small pieces from entering the waterway or wetland. Remove all reinforcing steel, all concrete, and all other debris that falls into the waterway or wetland. The contractor may leave limited amounts of small concrete pieces scattered over the waterway floor or wetland only if the engineer allows.

- (2) Submit a structure removal and clean-up plan as part of the erosion control implementation plan required under standard spec 107.20. Do not start work under the structure removal and clean-up plan without the department's written approval of the plan. Include the following information in the structure removal and clean-up plan:
  - Methods and schedule to remove the structure.
  - Methods to control potentially harmful environmental impacts.
  - Methods for superstructure removal that prevent all large pieces and minimize the number of small pieces from entering the waterway or wetlands.
  - Methods to control dust and contain slurry.
  - Methods for removing piers and abutments. If blasting in water, include restrictions that regulatory agencies and the contract require.
  - Methods for cleaning the waterway or wetlands.
- (3) If stockpiling spoil material, place it on an upland site an adequate distance from the waterway, wetland, or any open water created by excavation. Install silt fence between the spoil pile and the waterway, wetland, or excavation site.

Add the following Removing Old Structure bid item to standard spec 203.5.1:

ITEM NUMBER	DESCRIPTION	UNIT
203.0600.S.200	Removing Old Structure Over Waterway With Minimal Debris Station 566+00	LS
203.0600.S.201	Removing Old Structure Over Waterway With Minimal Debris Station 566+00	LS
203.0600.S.202	Removing Old Structure Over Waterway With Minimal Debris Station 565+95	LS

#### 80. EBS Backfill, Item SPV.0035.002.

Replace the entire article with the following:

#### **A Description**

This special provision describes backfilling EBS Excavation with breaker run or backfill granular grade 1.

#### **B** Materials

Furnish all materials according to standard spec 209.2, and standard spec 311.2 and as hereinafter provided.

#### **C** Construction

Place breaker run or backfill granular grade 1 where EBS Excavation was performed or as the engineer directs. Compact breaker run using standard compaction conforming to standard spec 301.3. Compact backfill granular grade 1 using standard compaction conforming to standard spec 209.3.

#### **D** Measurement

The department will determine weight or volume, adjust for moisture, and convert between weight and volume as specified in standard spec 301.4.

The department will measure EBS Backfill by the cubic yard, acceptably completed.

#### E Payment

The department will pay for measured quantities at the contract unit price under the following bid item:

ITEM NUMBER DESCRIPTION UNIT

SPV.0035.002 EBS Backfill CY

Payment for EBS Backfill is full compensation for providing and compacting breaker run or backfill granular grade 1 in areas of EBS Excavation.

The department will only pay for EBS Backfill at engineer-approved EBS Excavation locations. Work performed under standard spec 105.3 to correct unacceptable work is the contractor's responsibility.

The department will not pay for EBS Backfill to replace materials excavated to remove frost from newly constructed embankments or cut subgrades.


#### Schedule of Items

Attached, dated July 9, 2020, are the revised Schedule of Items Pages 3, 23, and 31.

#### **Plan Sheets**

The following  $8\frac{1}{2}$  x 11-inch sheets are attached and made part of the plans for this proposal: Revised: 80, 411, 413, 801, 826, 839, 864, 886 and 908.

**END OF ADDENDUM** 



<u>က</u>	185 MASONRY	Addendum No. 02 ID 3763-00-74 Revised Sheet 411 July 9, 2020	ALL ITEMS CATEGORY 1000 UNLESS OTHERWISE NOTED
	STATION OFFSET LOCATION		
	STATION		MEDELLANDISCILANTIFIES
0.S.202 URE OVER WATERWAY BRIS STA 565+95 S		204.0170 REMOVING FENCE LF 69 50 119	COLINTY-DACINE
REMOVING OLD STRUCTURE  203.0600.S.202 REMOVING OLD STRUCTURE OVER WATERWAY WITH MINIMAL DEBRIS STA 565+95 LOCATION LS CTH KR 1 1 NL		OFFSET LOCATION 76' RT CTHKR 100' RT STH 31 AL	GX LTZ
STATION OFFSET LG 565+95 RT PROJECT 3763-00-74 TOTAL		STA TO STA 535+03 315+22 - 315+67 PROJECT 3763-00-74 TOTAL	DDO IECT NO. 3783 00.74

ന CONSTRUCTION Stages 1 & 4 Stages 1 & 3 Stages 2 & 3 Stages 1 & 4 Stages 1 & 4 Stage 4 STAGE/S Stage 4 Stage 3 Stage 3 Stage 3 Stage 3 Stage 1 Stage 1 Stage 4 Stage 1 Stage 1 Stage 1 Stage 3 Stage 3 ORDINATE +/- (4) 13,620 158,617 4,232 13,264 446 4,912 466 364 11,069 11,851 -1,365 -1,062 2,464 material within the division. Mass Ordinate = Cut+Excavation to Suitable Subgrade-Embankment. The mass ordinate is for information purposes only as Common Excavation and 6,166 MASS 4) The Mass Ordinate + or - quantity calculated by Division. A positive quantity indicates an excess of material within the division and a negative number indicates a shortage of 267 37 EMBANKMENT (3) (7) SPV.0035.003 ROADWAY 19,949 32,315 36,391 5,100 1,463 873 811 412 75 9 3 235  $\sim$ Roadway Embankment are not balance for quantity purposes and does not guarantee the quality of Common Excavation, and if it can be reused onsite. FILL (CY) 188,860 17,021 312,161 22,406 24,687 13,285 15,629 5,100 967 412 6 75 110 5 3 3 SPV.0035.002 EXCAVATION (2) EBS BACKFILL 4,594 3,289 4,256 3,180 0 0 511 1,473 126 19 88 37 37 1,114  $\stackrel{\smile}{\sim}$  EBS Excavation to be backfilled with EBS Backfill. All EBS Excavation material is assumed to be wasted offsite. SPV.0035.001 4,256 1,473 126 1,114 1,594 3,289 3,180 19 88 37 257 0 0 511  $\stackrel{\smile}{\sim}$ 4 27 3) Roadway Embankment = Unexpanded Fill + Excavation to Suitable Subgrade Replaced EARTHWORK GRANULAR BACKFILL **GRADE 1** 209.1100 0 0 0 3,037 6,173 30,006 2,567 9,097  $\zeta$ 0 0 0 0 0 0 REMOVAL (CY) **EXCAVATION**  Cut Volume Includes Concrete and Asphaltic Surface Material **EXCAVATION COMMON** TOPSOIL OVER-19,006 32,653 14,271 6,669 6,664 3,037 0 205.0100\* CUT (CY) 28,286 25,136 270 7,451 32,307 8,058 11,144 2,574 2,068 188 878 370 237 42 CPRR GEOTECH OVERBUILD (8) FROM / TO STATION 540+00 - 575+00 452+75 - 467+50 524+50 - 540+00 145+00 - 182+50 801+13 - 801+25 900+25 - 901+00 467+50 - 487+00 575+00 - 603+70 201+58 - 202+43 709+25 - 711+25 100+50 - 109+21 307+84 - 322+51 51+82 - 57+18 58+83 - 68+19 10+00 - 14+78 462+00 LT 510+00 RT 550+00 LT UPRR G SOUTH FRONTAGE ROAD (SFR) OLD GREEN BAY ROAD SHARED-USE PATH MCKSBURGDRIVE PARK ACCESS **56TH AVENUE 43RD AVENUE** 90TH STREET 72ND AVENUE ROADWAY SUBTOTAL CTH KR CTHKR POND M CTH KR CTH KR CTH KR CTH KR STH 31 POND L POND N PROJECT 3763-00-74 TOTALS CATEGORY 1000

3

Addendum No. 02 ID 3763-00-74 **Revised Sheet 413** July 9, 2020

actual amount of MSE Backfill to be determined by the wall designer.

7) Roadway Embankment quantity includes volume of material used for MSE Backfill at retaining walls R-30-65, R-30-66, R-30-67 and R-30-68 6) Excavation Common quantites are shown elsewhere in the plan, refer to quantity tables for Regenerative Stormwater Conveyance system

5) Over-Excavation / Topsoil Removal estimated, refer to Over-Excavation and Topsoil Removal Construction Details

8) CPRR Geotech Overbuild is embankment placed to facilitate settlement within 800' of Structures B-30-147 & B-30-148. Excess to be removed after settlement.

9) UPRR Geotech Overbuild is embankment placed to facilitate settlement from 800' west of Structures B-30-145 & B-30-146 to Station 540+00. Excess to be removed after settlement.

'NOTE: ADDITIONAL QUANTITIES SHOWN ELSEWHERE

COUNTY:RACINE PROJECT NO: 3763-00-74 HWY SUDOTION SET80045. Foxonn, Local. Poads/Dasgn/DGN Flee/CTH KR EastPlansheets

HWY: CTH KR


MISCELLANEOUS QUANTITIES


PLOT NAME: 022591\_MQ5


ш


413


SHEET:
















07/09/2020 14:12:41



### Proposal Schedule of Items

Page 3 of 31

Proposal ID: 20200714006 Project(s): 3763-00-74

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0058	204.9105.S Removing (item description) 304. Loop Detector Wire and Lead-in-Cable CTH KR & Old Green Bay Rd	LS	LUMP SUM	·
0060	205.0100 Excavation Common	378,863.000 CY		
0062	205.0501.S Excavation, Hauling, and Disposal of Petroleum Contaminated Soil	128.000 TON		
0064	206.1000 Excavation for Structures Bridges (structure) 200. B-30-143	LS	LUMP SUM	
0066	206.1000 Excavation for Structures Bridges (structure) 201. B-30-144	LS	LUMP SUM	
0068	206.3000 Excavation for Structures Retaining Walls (structure) 200. Structure R-30-65	LS	LUMP SUM	
0070	206.3000 Excavation for Structures Retaining Walls (structure) 201. Structure R-30-66	LS	LUMP SUM	
0072	206.3000 Excavation for Structures Retaining Walls (structure) 202. Structure R-30-67	LS	LUMP SUM	
0074	206.3000 Excavation for Structures Retaining Walls (structure) 203. Structure R-30-68	LS	LUMP SUM	
0076	209.1100 Backfill Granular Grade 1	95,767.000 CY	·	
0078	210.1500 Backfill Structure Type A	2,536.000 TON		
0800	213.0100 Finishing Roadway (project) 001. 3763- 00-74	1.000 EACH		
0082	305.0110 Base Aggregate Dense 3/4-Inch	1,265.000 TON	·	<u> </u>
0084	305.0120 Base Aggregate Dense 1 1/4-Inch	88,143.000 TON		



07/09/2020 14:12:41



### Proposal Schedule of Items

Page 23 of 31

Proposal ID: 20200714006 Project(s): 3763-00-74

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0658	SPV.0035 Special 002. EBS Backfill	25,907.000 CY		
0660	SPV.0035 Special 003. Roadway Embankment	665,951.000 CY	<u> </u>	·
0662	SPV.0035 Special 004. Riffle Cobble	36.000 CY		
0664	SPV.0035 Special 005. No. 1 Aggregate	1,582.000 CY		
0666	SPV.0035 Special 006. Open-Graded Base Aggregate	170.000 CY	·	·
0668	SPV.0035 Special 007. Sand/Woodchip Bed	829.000 CY		·
0670	SPV.0035 Special 008. Compost	170.000 CY	·	
0672	SPV.0035 Special 009. Backfill Slurry	85.000 CY		
0674	SPV.0055 Special 001. Maintain Field Office Left in Place Special Utility Fees Project 3763- 00-74	100,000.000 DOL	1.00000	100,000.00
0676	SPV.0060 Special 002. Temporary Stone Ditch Checks	50.000 EACH		·
0678	SPV.0060 Special 003. Sand Bags	500.000 EACH		
0680	SPV.0060 Special 004. Temporary Sediment Traps	25.000 EACH		·
0682	SPV.0060 Special 005. Erosion Control Filter Bags	400.000 EACH	<u> </u>	
0684	SPV.0060 Special 006. Inlet Frame and Grate for Mountable Curb	26.000 EACH	<del></del>	
0686	SPV.0060 Special 007. Temporary Access Gates at CPRR	2.000 EACH	<u></u>	



### Wisconsin Department of Transportation

07/09/2020 14:12:41

### Proposal Schedule of Items

Page 31 of 31

Proposal ID: 20200714006 Project(s): 3763-00-74

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line	Item ID	Approximate Quantity and	Unit Price	Bid Amount
Number	Description	Units		
0868	SPV.0200	2.000		
	Special 601. Reconstruct Sanitary Manhole Subtraction	VF	·	·
0870	SPV.0055	90,000.000		
	Special 002. Construction Crossing with UPRR	DOL	1.00000	90,000.00
0872	SPV.0060	1.000		
	Special 202. Removing Old Structure Over Waterway with Minimal Debris STA 565+95	EACH	·	·
	Section: 000	01	Total:	

Total Bid: