



Wisconsin Department of Transportation

July 9, 2020

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #13: 6600-00-61, WISC 2020 267
Mosinee - Elderon
Old 51 Road to East View Drive
STH 153
Marathon County

6600-00-62, WISC 2020 268
Mosinee – Elderon
I-39 SB Ramp to NB Ramp
STH 153
Marathon County

Letting of July 14, 2020

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress
6	Holiday Work Restrictions

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
643.0300	Traffic Control Drums	Day	14,593	-787	13,806
643.0410	Traffic Control Barricades Type II	Day	1,752	123	1,875
643.0420	Traffic Control Barricades Type III	Day	1,081	-236	845
643.0705	Traffic Control Warning Lights Type A	Day	3,330	-390	2,940
643.0715	Traffic Control Warning Lights Type C	Day	1,756	-264	1,492
643.0800	Traffic Control Arrow Boards	Day	82	-13	69
643.0900	Traffic Control Signs	Day	6,205	-509	5,696
643.1070	Traffic Control Cones 42-Inch	Day	25,275	-7,825	17,450

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
450.4000	HMA Cold Weather Paving (6600-00-61)	Ton	2,482	-2,482	0

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
83, 86-89	Miscellaneous Quantities – Remove HMA Cold Weather Paving and adjust Traffic control quantities

Other

Revise Contract Time for Completion from a Completion Date of October 30, 2020 to a 35 Working Day Contract.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

6600-00-61, 62

July 9, 2020

Special Provisions

3. Prosecution and Progress.

Replace paragraphs two and three with the following:

Provide the time frame for construction of the project within the 2020-2021 construction seasons to the engineer in writing within a month after executing the contract but at least 14 calendar days before the preconstruction conference. Complete all work prior to June 11, 2021. Upon approval, the engineer will issue the notice to proceed within ten calendar days before the beginning of the approved time frame.

To revise the time frame, submit a written request to the engineer at least two weeks before the beginning of the intended time frame. The engineer will approve or deny that request based on the conditions cited in the request and its effect on the department's scheduled resources.

When, in the fall of 2020, after completion of Stage 1 (curb ramps, concrete sidewalk and curb & gutter), and weather conditions or seasonal restrictions preclude the satisfactory performance of further work under this contract, the engineer will, in writing, suspend operations until the spring of 2021. Construction operations shall be resumed in the spring of 2021 within ten days after the date on which a written order to do so has been issued by the engineer.

Asphaltic paving in Stages 2 and 3 must be done within the same construction year.

6. Holiday Work Restrictions.

Add the following to the end of the list of time periods for work restrictions:

- From noon Friday, May 28, 2021 to 6:00 AM Tuesday, June 1, 2021 for Memorial Day.

Schedule of Items

Attached, dated July 9, 2020, are the revised Schedule of Items Pages 1 – 5.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 83, 86, 87, 88 and 89.

END OF ADDENDUM

TRAFFIC CONTROL DRUMS & WARNING LIGHTS

STATION - STATION	LOCATION	643.0300 DRUMS		643.0715 LIGHTS TYPE C		REMARKS	
		NO	DAYS	NO	DAYS		
STAGE 1 45+00 - 125+25	STH 153 (EB & WB)	316	28	8848	25	700	SEE TRAFFIC CONTROL - STAGE 1
STAGE 1 SUB-TOTALS		8848		700			
STAGE 2 45+00 - 56+75	STH 153 (EB & WB)	66	8	528	12	96	SEE TRAFFIC CONTROL - STAGE 2A
45+00 - 56+75	STH 153 (EB & WB)	57	7	399	8	56	SEE TRAFFIC CONTROL - STAGE 2B
56+75 - 125+25	STH 153 (EB & WB)	91	15	1365	14	210	SEE TRAFFIC CONTROL - STAGE 2
STAGE 2 SUB-TOTALS		2292		362			
STAGE 3 45+00 - 125+25	STH 153 (EB & WB)	100	26	2600	14	364	SEE TRAFFIC CONTROL - STAGE 3
STAGE 3 SUB-TOTALS		2600		364			
DETOURS							
NB OFF RAMP	IH 39/USH 51 OFF RAMP	10	3	30	10	30	SEE DETOURS
NB ON RAMP	IH 39/USH 51 ON RAMP	3	1	3	3	3	SEE DETOURS
SB OFF RAMP	IH 39/USH 51 OFF RAMP	10	3	30	10	30	SEE DETOURS
SB ON RAMP	IH 39/USH 51 ON RAMP	3	1	3	3	3	SEE DETOURS
DETOURS SUB-TOTALS		66		66			
GRAND TOTALS		13806		1492			

Addendum No. 01
 ID 6600-0-61/62
 Revised Sheet 86
 July 9, 2020

TRAFFIC CONTROL FLEXIBLE TUBULAR MARKERS

STATION - STATION	LOCATION	643.0500 643.0600 POSTS BASES		REMARKS
		EACH	EACH	
45+00 - 56+75	STH 153 (EB & WB)	22	22	SEE TRAFFIC CONTROL - STAGE 2A
45+00 - 56+75	STH 153 (EB & WB)	22	22	SEE TRAFFIC CONTROL - STAGE 2B
TOTALS		44	44	

TRAFFIC CONTROL BARRICADE & WARNING LIGHTS TYPE A

STATION	LOCATION	643.0410		643.0420		643.0705		REMARKS			
		NO	DAYS	BARRICADE TYPE II	BARRICADE TYPE III	LIGHTS TYPE A	LIGHTS TYPE A				
		NO	DAYS	NO	DAYS	NO	DAYS				
STAGE 1											
45+00 - 125+25	STH 153 (EB & WB)	51	28	1428	8	28	224	50	28	1400	SEE TRAFFIC CONTROL - STAGE 1
STAGE 1 SUB-TOTALS				1428			224			1400	
STAGE 2											
45+00 - 56+75	STH 153 (EB & WB)	--	--	--	3	8	24	6	8	48	SEE TRAFFIC CONTROL - STAGE 2A
45+00 - 56+75	STH 153 (EB & WB)	--	--	--	1	7	7	2	7	14	SEE TRAFFIC CONTROL - STAGE 2B
56+75 - 125+25	STH 153 (EB & WB)	9	15	135	13	15	195	32	15	480	SEE TRAFFIC CONTROL - STAGE 2
STAGE 2 SUB-TOTALS				135			226			542	
STAGE 3											
45+00 - 125+25	STH 153 (EB & WB)	12	26	312	15	26	390	38	26	988	SEE TRAFFIC CONTROL - STAGE 3
STAGE 3 SUB-TOTALS				312			390			988	
DETOURS											
IH 39/USH 51 NB OFF RAMP		--	--	--	1	3	3	2	3	6	SEE DETOURS
IH 39/USH 51 NB ON RAMP		--	--	--	1	1	1	2	1	2	SEE DETOURS
IH 39/USH 51 SB OFF RAMP		--	--	--	1	3	3	2	3	6	SEE DETOURS
IH 39/USH 51 SB ON RAMP		--	--	--	1	1	1	2	1	2	SEE DETOURS
DETOURS SUB-TOTALS				0			5			10	
GRAND TOTALS				1875			845			2940	

TRAFFIC CONTROL ARROW BOARDS

STATION	LOCATION	NO	DAY	REMARKS
125+00	STH 153 (WB)	1	69	SEE ADVANCED WARNING SIGNING
TOTAL			69	

Addendum No. 01
ID 6600-0-61/62
Revised Sheet 87
July 9, 2020

Addendum No. 01
ID 6600-0-61/62
Revised Sheet 88
July 9, 2020

TRAFFIC CONTROL SIGNS

LOCATION	MESSAGE	SIGN CODE	NO	DAYS	DAY	REMARKS
ADVANCED WARNING						
OLD 51 ROAD & STH 153	ROAD WORK AHEAD	W20-1A	3	69	207	SEE ADVANCED WARNING SIGNING
	ROAD WORK 1000 FT	W20-1C	1	69	69	SEE ADVANCED WARNING SIGNING
	ROAD WORK 500 FT	W20-1D	3	69	207	SEE ADVANCED WARNING SIGNING
	ROAD WORK 250 FT	W20-1(MOD)	2	69	138	SEE ADVANCED WARNING SIGNING
	STH 153	M1-6	2	69	138	SEE ADVANCED WARNING SIGNING
	EAST	M3-2	2	69	138	SEE ADVANCED WARNING SIGNING
	END ROAD WORK	G20-2A	3	69	207	SEE ADVANCED WARNING SIGNING
			ADVANCED WARNING SUB-TOTAL		1104	
STAGE 1						
STH 153 (EB & WB)	SIDEWALK CLOSED	R9-9	17	28	476	SEE TRAFFIC CONTROL - STAGE 1
	LANE CLOSED	R11-2L	8	28	224	SEE TRAFFIC CONTROL - STAGE 1
	RIGHT LANE CLOSED AHEAD	W20-5A	1	28	28	SEE TRAFFIC CONTROL - STAGE 1
	RIGHT LANE ENDS SYMBOL	W4-2R	1	28	28	SEE TRAFFIC CONTROL - STAGE 1
SIDERoads & Ramps	ROAD WORK AHEAD	W20-1A	14	28	392	SEE TRAFFIC CONTROL - STAGE 1
	END ROAD WORK	G20-2A	2	28	56	SEE TRAFFIC CONTROL - STAGE 1
			STAGE 1 SUB-TOTAL		1204	
STAGE 2						
STH 153 (EB & WB)	NIGHT ARROW	W01-6	4	8	32	SEE TRAFFIC CONTROL - STAGE 2A
	LANE CLOSED	R11-2L	13	8	104	SEE TRAFFIC CONTROL - STAGE 2 & 2B
	SIDEWALK CLOSED	R9-9	3	15	45	SEE TRAFFIC CONTROL - STAGE 2
	NIGHT ARROW	W01-6	1	15	15	SEE TRAFFIC CONTROL - STAGE 2
SIDERoads & Ramps	ROAD WORK AHEAD	W20-1A	14	15	210	SEE TRAFFIC CONTROL - STAGE 2,2A,2B
	END ROAD WORK	G20-2A	2	15	30	SEE TRAFFIC CONTROL - STAGE 2,2A,2B
			STAGE 2 SUB-TOTAL		436	
STAGE 3						
STH 153 (EB & WB)	NIGHT ARROW	W01-6	1	26	26	SEE TRAFFIC CONTROL - STAGE 3
	LANE CLOSED	R11-2L	14	26	364	SEE TRAFFIC CONTROL - STAGE 3
	SIDEWALK CLOSED	R9-9	4	26	104	SEE TRAFFIC CONTROL - STAGE 3
SIDERoads & Ramps	ROAD WORK AHEAD	W20-1A	14	26	364	SEE TRAFFIC CONTROL - STAGE 3
	END ROAD WORK	G20-2A	2	26	52	SEE TRAFFIC CONTROL - STAGE 3
			STAGE 3 SUB-TOTAL		910	
WIDTH RESTRICTIONS						
FOR PROJECT	MAX 10' WIDTH	W12-52	14	60	840	SEE TRAFFIC CONTROL - WIDTH RESTRICTIONS
	STH 153	M1-6	10	60	600	SEE TRAFFIC CONTROL - WIDTH RESTRICTIONS
	EAST	M3-2	2	60	120	SEE TRAFFIC CONTROL - WIDTH RESTRICTIONS
	WEST	M3-4	1	60	60	SEE TRAFFIC CONTROL - WIDTH RESTRICTIONS
	XX MILES AHEAD	W57-52	7	60	420	SEE TRAFFIC CONTROL - WIDTH RESTRICTIONS
			WIDTH RESTRICTIONS SUB-TOTAL		2040	
DETOUR						
NB & SB OFF RAMP	RAMP CLOSED	R11-2R	2	3	6	SEE DETOURS
NB & SB ON RAMP	RAMP CLOSED	R11-2R	2	1	2	SEE DETOURS
			DETOURS SUB-TOTAL		2	
			GRAND TOTAL		5696	

TRAFFIC CONTROL SIGNS PCMS

STATION	LOCATION	DESCRIPTION	PHASE 1	PHASE 2	643.1050 DAY	REMARKS
IH 39/ USH 51 NB	1.75 MILES SOUTH OF STH 153 NB EXIT	NIGHTLY RAMP CLOSURE	MONTH DAY TIME		3	SEE DETOURS PLAN SHEETS
		WIS 153 RAMP CLOSED	USE EXIT 181		3	SEE DETOURS PLAN SHEETS
IH 39/ USH 51 NB	0.75 MILES NORTH OF STH 153 SB EXIT	NIGHTLY RAMP CLOSURE	MONTH DAY TIME		3	SEE DETOURS PLAN SHEETS
		WIS 153 RAMP CLOSED	USE EXIT 175		3	SEE DETOURS PLAN SHEETS
STH 153 (EB & WB)	IH 39/USH 51 NB ON RAMP	NIGHTLY RAMP CLOSURE	MONTH DAY TIME		1	SEE DETOURS PLAN SHEETS
		139 NB ON RAMP CLOSED	USE SB RAMP TO EXIT 175		1	SEE DETOURS PLAN SHEETS
STH 153 (EB & WB)	IH 39/USH 51 SB ON RAMP	NIGHTLY RAMP CLOSURE	MONTH DAY TIME		1	SEE DETOURS PLAN SHEETS
		139 SB ON RAMP CLOSED	USE NB RAMP TO EXIT 181		1	SEE DETOURS PLAN SHEETS
TOTAL					16	

Addendum No. 01
ID 6600-0-61/62
Revised Sheet 89
July 9, 2020

TRAFFIC CONTROL CONES 42-INCH

STATION - STATION	LOCATION	NO	DAYS	DAY	REMARKS
643.1070 CONES					
STAGE 2					
45+00 - 56+75	STH 153 (EB & WB)	56	8	448	SEE TRAFFIC CONTROL - STAGE 2A
45+00 - 56+75	STH 153 (EB & WB)	45	7	315	SEE TRAFFIC CONTROL - STAGE 2B
56+75 - 125+25	STH 153 (EB & WB)	355	15	5325	SEE TRAFFIC CONTROL - STAGE 2
STAGE 2 SUB-TOTALS 6088					
STAGE 3					
45+00 - 125+25	STH 153 (EB & WB)	437	26	11362	SEE TRAFFIC CONTROL - STAGE 3
STAGE 3 SUB-TOTALS 11362					
GRAND TOTALS 17450					

TEMPORARY PEDESTRIAN

STATION - STATION	LOCATION	SF	DAY	LF	LF	REMARKS
46+75 - 47+80	STH 153 (LT)	--	20	113	178	646.7420 * MARKING
0+50CW - 1+15CW	CHERRY ST (WEST)	157	--	102	101	CROSSWALK
0+14CE - 1+14CE	CHERRY ST (EAST)	160	--	118	101	EPOXY
60+55 - 60+82	STH 153 (LT)	--	--	83	122	PEDESTRIAN TRANSVERSE
61+60 - 61+82	STH 153 (LT)	--	--	71	122	PEDESTRIAN TRANSVERSE
0+30V	IH 39/USH 51 (SB) OFF RAMP (WEST)	20	20	66	85	ASPHALT RAMP BARRICADE LINE 6-INCH
0+55X	IH 39/USH 51 (SB) ON RAMP (EAST)	115	20	75	85	
0+55Y	IH 39/USH 51 (NB) ON RAMP (WEST)	40	20	75	82	
0+70Z	IH 39/USH 51 (NB) ON RAMP (EAST)	35	20	66	82	
0+50WW	WESTVIEW DR (WEST)	20	20	121	140	
0+65WE	WESTVIEW DR (EAST)	--	--	55	142	
TOTALS 547 120 945 1240						
PROJECT 6600-00-61 TOTALS 337 40 663 906						
PROJECT 6600-00-62 TOTALS 210 80 282 334						

* QUANTITY SHOWN ELSEWHERE IN MISCELLANEOUS QUANTITIES

PROJECT NO: 6600-00-61,62

COUNTY: MARATHON

HWY: STH 153

SHEET: 89

FILE NAME: \\usah\hwy\6600\6600-00-61-62_C01-153_C01-153-EB-WB-CONES\032021.dwg

PLOT DATE: 2/26/2021 12:28:51

PLOT BY: [Redacted]

PROJECT NO: 6600-00-61,62



Proposal Schedule of Items

Proposal ID: 20200714013 Project(s): 6600-00-61, 6600-00-62

Federal ID(s): WISC 2020267, WISC 2020268

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0100 Removing Concrete Pavement	344.000 SY	_____.	_____.
0004	204.0105 Removing Pavement Butt Joints	798.000 SY	_____.	_____.
0006	204.0109.S Removing Concrete Surface Partial Depth	396,593.000 SF	_____.	_____.
0008	204.0110 Removing Asphaltic Surface	62.000 SY	_____.	_____.
0010	204.0115 Removing Asphaltic Surface Butt Joints	78.000 SY	_____.	_____.
0012	204.0120 Removing Asphaltic Surface Milling	6,009.000 SY	_____.	_____.
0014	204.0150 Removing Curb & Gutter	1,200.000 LF	_____.	_____.
0016	204.0155 Removing Concrete Sidewalk	279.000 SY	_____.	_____.
0018	213.0100 Finishing Roadway (project) 01. 6600-00-61	1.000 EACH	_____.	_____.
0020	213.0100 Finishing Roadway (project) 02. 6600-00-62	1.000 EACH	_____.	_____.
0022	305.0110 Base Aggregate Dense 3/4-Inch	26.000 TON	_____.	_____.
0024	310.0110 Base Aggregate Open-Graded	106.000 TON	_____.	_____.
0026	390.0403 Base Patching Concrete Shes	188.000 SY	_____.	_____.
0028	416.0610 Drilled Tie Bars	413.000 EACH	_____.	_____.
0030	416.0620 Drilled Dowel Bars	91.000 EACH	_____.	_____.
0034	455.0605 Tack Coat	3,554.000 GAL	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200714013 Project(s): 6600-00-61, 6600-00-62

Federal ID(s): WISC 2020267, WISC 2020268

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0036	460.2000 Incentive Density HMA Pavement	3,250.000 DOL	1.00000	3,250.00
0038	460.6224 HMA Pavement 4 MT 58-28 S	5,064.000 TON	_____	_____
0040	465.0110 Asphaltic Surface Patching	147.000 TON	_____	_____
0042	465.0305 Asphaltic Surface Safety Islands	6.000 TON	_____	_____
0044	601.0409 Concrete Curb & Gutter 30-Inch Type A	1,200.000 LF	_____	_____
0046	602.0405 Concrete Sidewalk 4-Inch	3,172.000 SF	_____	_____
0048	602.0505 Curb Ramp Detectable Warning Field Yellow	170.000 SF	_____	_____
0050	602.0605 Curb Ramp Detectable Warning Field Radial Yellow	102.000 SF	_____	_____
0052	618.0100 Maintenance And Repair of Haul Roads (project) 01. 6600-00-61	1.000 EACH	_____	_____
0054	619.1000 Mobilization	1.000 EACH	_____	_____
0056	624.0100 Water	20.000 MGAL	_____	_____
0058	628.1905 Mobilizations Erosion Control	3.000 EACH	_____	_____
0060	628.1910 Mobilizations Emergency Erosion Control	2.000 EACH	_____	_____
0062	628.2006 Erosion Mat Urban Class I Type A	750.000 SY	_____	_____
0064	628.7015 Inlet Protection Type C	85.000 EACH	_____	_____
0066	628.7555 Culvert Pipe Checks	12.000 EACH	_____	_____



Proposal Schedule of Items

Proposal ID: 20200714013 Project(s): 6600-00-61, 6600-00-62

Federal ID(s): WISC 2020267, WISC 2020268

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0068	642.5201 Field Office Type C	1.000 EACH	_____.	_____.
0070	643.0300 Traffic Control Drums	13,806.000 DAY	_____.	_____.
0072	643.0410 Traffic Control Barricades Type II	1,875.000 DAY	_____.	_____.
0074	643.0420 Traffic Control Barricades Type III	845.000 DAY	_____.	_____.
0076	643.0500 Traffic Control Flexible Tubular Marker Posts	44.000 EACH	_____.	_____.
0078	643.0600 Traffic Control Flexible Tubular Marker Bases	44.000 EACH	_____.	_____.
0080	643.0705 Traffic Control Warning Lights Type A	2,940.000 DAY	_____.	_____.
0082	643.0715 Traffic Control Warning Lights Type C	1,492.000 DAY	_____.	_____.
0084	643.0800 Traffic Control Arrow Boards	69.000 DAY	_____.	_____.
0086	643.0900 Traffic Control Signs	5,696.000 DAY	_____.	_____.
0088	643.1050 Traffic Control Signs PCMS	16.000 DAY	_____.	_____.
0090	643.1070 Traffic Control Cones 42-Inch	17,450.000 DAY	_____.	_____.
0092	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0094	644.1410 Temporary Pedestrian Surface Asphalt	547.000 SF	_____.	_____.
0096	644.1601 Temporary Pedestrian Curb Ramp	120.000 DAY	_____.	_____.
0098	644.1810 Temporary Pedestrian Barricade	945.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20200714013 Project(s): 6600-00-61, 6600-00-62

Federal ID(s): WISC 2020267, WISC 2020268

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0100	646.1020 Marking Line Epoxy 4-Inch	5,943.000 LF	_____.	_____.
0102	646.3020 Marking Line Epoxy 8-Inch	1,615.000 LF	_____.	_____.
0104	646.5020 Marking Arrow Epoxy	15.000 EACH	_____.	_____.
0106	646.5120 Marking Word Epoxy	3.000 EACH	_____.	_____.
0108	646.6120 Marking Stop Line Epoxy 18-Inch	505.000 LF	_____.	_____.
0110	646.7420 Marking Crosswalk Epoxy Transverse Line 6-Inch	2,062.000 LF	_____.	_____.
0112	646.8020 Marking Corrugated Median Epoxy	315.000 SF	_____.	_____.
0114	646.8120 Marking Curb Epoxy	691.000 LF	_____.	_____.
0116	646.8220 Marking Island Nose Epoxy	25.000 EACH	_____.	_____.
0118	649.0150 Temporary Marking Line Removable Tape 4-Inch	3,058.000 LF	_____.	_____.
0120	650.8000 Construction Staking Resurfacing Reference	7,124.000 LF	_____.	_____.
0122	650.8500 Construction Staking Electrical Installations (project) 02. 6600-00-62	LS	LUMP SUM	_____.
0124	650.9000 Construction Staking Curb Ramps	27.000 EACH	_____.	_____.
0126	650.9910 Construction Staking Supplemental Control (project) 01. 6600-00-61	LS	LUMP SUM	_____.
0128	650.9910 Construction Staking Supplemental Control (project) 02. 6600-00-62	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20200714013 Project(s): 6600-00-61, 6600-00-62

Federal ID(s): WISC 2020267, WISC 2020268

SECTION: 0001

Contract Items

Alt Set ID:

Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0130	652.0800 Conduit Loop Detector	1,350.000 LF	_____	_____
0132	655.0700 Loop Detector Lead In Cable	10,204.000 LF	_____	_____
0134	655.0800 Loop Detector Wire	6,803.000 LF	_____	_____
0136	690.0150 Sawing Asphalt	137.000 LF	_____	_____
0138	690.0250 Sawing Concrete	14,631.000 LF	_____	_____
0140	740.0440 Incentive IRI Ride	9,310.000 DOL	1.00000	9,310.00
0142	SPV.0060 Special 01. Grading Shaping and Finishing Curb Ramps	14.000 EACH	_____	_____
0144	SPV.0060 Special 02. Research and Locate Existing Land Parcel Monuments	2.000 EACH	_____	_____
0146	SPV.0060 Special 03. Verify and Replace Existing Land Parcel Monuments	2.000 EACH	_____	_____
0148	SPV.0170 Special 01. Concrete Joint and Crack Cleaning and Repair	284.000 STA	_____	_____
Section: 0001			Total:	_____
			Total Bid:	_____

