



# Wisconsin Department of Transportation

July 8, 2021

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #01: 1229-04-70, WISC 2021385**  
**I-43 North South Freeway**  
**Silver Spring Dr to STH 60**  
**IH 43**  
**Milwaukee and Ozaukee County**

### Letting of July 13, 2021

This is Addendum No. 02, which provides for the following:

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
305.0120	Base Aggregate Dense 1 ¼ Inch	TON	35,526	5,329	40,855
312.0110	Select Crushed Material	TON	41,448	6,217	47,665
495.1000.S	Cold Patch	TON	1,000	-900	100

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
311	Miscellaneous Quantities (updated 'Aggregate Items' table)
326	Miscellaneous Quantities (updated 'Pavement Repair Items' table)

#### **Schedule of Items**

Attached, dated July 8, 2021, are the revised Schedule of Items Pages 2 and 3.

#### **Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 311, 326.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

END OF ADDENDUM

AGGREGATE ITEMS

211.0400 PREPAIR FOUNDATION FOR ASPHALTIC SHOULDERS  
305.0120 BASE AGGREGATE 1 1/4 INCH DENSE  
312.0110 SELECT CRUSHED MATERIAL  
645.0220 GEOGRID TYPE SR

Table with columns: STATION, TO, STATION, OFFSET, LOCATION, STA, TON, TON, SY. Includes sub-totals for STAGE 1, STAGE 2, and PROJECT 1229-04-70 TOTAL.

NOTE:  
BASE AGGREGATE DENSE = 2 TON/CY  
SELECT CRUSHED = 1.8 TON/CY

Addendum No. 02  
ID 1229-04-70  
Revised Sheet 311  
July 8, 2021

FINISHING ROADWAY

Table with columns: LOCATION, EACH, TOTAL. Includes sub-totals for PROJECT 1229-04-70.

REMOVING OVERHEAD SIGNS

Table with columns: STATION, OFFSET, LOCATION, SIGN STRUCTURE, LS. Includes sub-totals for PROJECT 1229-04-70 TOTAL.

PAVEMENT REPAIR ITEMS			
LOCATION	TONS	EACH	TONS
PROJECT 1229-04-70	100	5	1000
PROJECT 1229-04-70 TOTAL	100	5	1000

495.1000.S SPV.0060.0120 SPV.0195.0020  
 COLD PATCH MOBILIZATIONS EMERGENCY HMA LONGITUDINAL  
 PAVEMENT REPAIR JOINT REPAIR

  

FIELD OFFICE FIXED	
LOCATION	TONS
PROJECT 1229-04-70	6
PROJECT 1229-04-70 TOTAL	6

SPV.0135.0100  
 FIELD OFFICE FIXED  
 MON

  

COVERING TRAFFIC SIGNAL EQUIPMENT	
LOCATION	LS
IH.43 NB OFF RAMP & CTHW	1
PROJECT 1229-04-70 TOTAL	1

SPV.0105.3000  
 COVERING TRAFFIC SIGNAL  
 EQUIPMENT

Addendum No. 02  
 ID 1229-04-70  
 Revised Sheet 326  
 July 8, 2021

SURVEY PROJECT	
LOCATION	LS
PROJECT 1229-04-70	1
PROJECT 1229-04-70 TOTAL	1

SPV.0105.0604  
 SURVEY PROJECT

  

PAVEMENT CLEANUP	
LOCATION	HRS
PROJECT 1229-04-70	250
PROJECT 1229-04-70 TOTAL	250

SPV.0075.0601  
 PAVEMENT CLEANUP

SAWING			
STATION	OFFSET	LOCATION	LF
1271+03	LT	IH.43 SB	11
1275+90	RT	IH.43 NB	9
1271+03	LT	IH.43 SB	3928
1275+90	RT	IH.43 NB	3433
1281+81	RT	IH.43 NB	164
1301+84	LT	IH.43 SB	232
1310+00	LT	IH.43 SB	23
1310+00	RT	IH.43 NB	24
1312+00	LT	IH.43 SB	21
1312+00	RT	IH.43 NB	26
1312+00	LT	IH.43 SB	1755
1312+00	RT	IH.43 NB	1594
1329+25	LT	IH.43 SB	24
1327+75	RT	IH.43 NB	24
1327+75	RT	IH.43 NB	24
1330+75	LT	IH.43 SB	22
1332+25	LT	IH.43 SB	24
1330+75	RT	IH.43 NB	3740
1332+25	LT	IH.43 SB	3472
1367+93	RT	IH.43 NB	11
1366+76	LT	IH.43 SB	11
1578+00	RT	IH.43 NB	20
1624+91	RT	IH.43 NB	79.00
1651+17	RT	IH.43 NB	667
1687+30	RT	IH.43 NB	64
1771+47	RT	IH.43 NB	139
PROJECT 1229-04-70 TOTAL			1,199

690.0150 SAWING ASPHALT LF 11  
 690.0250\* SAWING CONCRETE LF --

\* ADDITIONAL QUANTITIES SHOWN ELSEWHERE

EMERGENCY RESPONSE TO TRAFFIC	
LOCATION	EACH
PROJECT 1229-04-70 TOTAL	4

SPV.0060.0940  
 EMERGENCY RESPONSE TO TRAFFIC INVOLVING CONCRETE BARRIER TEMPORARY

  

EMERGENCY RESPONSE TO TRAFFIC INVOLVING CRASH CUSHION	
LOCATION	EACH
PROJECT 1229-04-70 TOTAL	2

SPV.0060.0945  
 EMERGENCY RESPONSE TO TRAFFIC INVOLVING CRASH CUSHION

CPM PROGRESS SCHEDULE	
LOCATION	EACH
PROJECT 1229-04-70	1
PROJECT 1229-04-70 TOTAL	3

SPV.0060.0601  
 MONTHLY CPM PROGRESS SCHEDULE UPDATES



Proposal Schedule of Items

Proposal ID: 20210713001 Project(s): 1229-04-70

Federal ID(s): WISC 2021385

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0032	204.9060.S Removing (item description) 0001. Removing Apron Endwall	4.000 EACH	_____.	_____.
0034	204.9090.S Removing (item description) 0001. Removing Draintile	100.000 LF	_____.	_____.
0036	204.9090.S Removing (item description) 0002. Removing Underdrain	31,485.000 LF	_____.	_____.
0038	204.9105.S Removing (item description) 0001. Removing Overhead Sign Structure S-40-16	LS	LUMP SUM	_____.
0040	204.9105.S Removing (item description) 0002. Removing Overhead Sign Structure S-45-401	LS	LUMP SUM	_____.
0042	205.0100 Excavation Common	46,119.000 CY	_____.	_____.
0044	211.0400 Prepare Foundation for Asphaltic Shoulders	360.000 STA	_____.	_____.
0046	213.0100 Finishing Roadway (project) 0001. 1229-04-70	1.000 EACH	_____.	_____.
0048	305.0120 Base Aggregate Dense 1 1/4-Inch	40,855.000 TON	_____.	_____.
0050	312.0110 Select Crushed Material	47,665.000 TON	_____.	_____.
0052	416.0610 Drilled Tie Bars	1,047.000 EACH	_____.	_____.
0054	416.0620 Drilled Dowel Bars	2,548.000 EACH	_____.	_____.
0056	416.0750.S Concrete Pavement Partial Depth Repair Joint Repair	500.000 LF	_____.	_____.
0058	416.1715 Concrete Pavement Repair SHES	817.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20210713001 Project(s): 1229-04-70

Federal ID(s): WISC 2021385

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0060	416.1725 Concrete Pavement Replacement SHES	2,147.000 SY	_____.	_____.
0062	455.0605 Tack Coat	9,051.000 GAL	_____.	_____.
0064	460.2000 Incentive Density HMA Pavement	18,320.000 DOL	1.00000	18,320.00
0066	460.6223 HMA Pavement 3 MT 58-28 S	20,982.000 TON	_____.	_____.
0068	460.6224 HMA Pavement 4 MT 58-28 S	7,629.000 TON	_____.	_____.
0070	495.1000.S Cold patch	100.000 TON	_____.	_____.
0072	511.2300 Temp Shoring Left in Place (location) 0001. Sta 1316+60 to Sta 1323+50	2,531.000 SF	_____.	_____.
0074	520.8000 Concrete Collars for Pipe	10.000 EACH	_____.	_____.
0076	522.1012 Apron Endwalls for Culvert Pipe Reinforced Concrete 12-Inch	1.000 EACH	_____.	_____.
0078	522.1015 Apron Endwalls for Culvert Pipe Reinforced Concrete 15-Inch	1.000 EACH	_____.	_____.
0080	522.1018 Apron Endwalls for Culvert Pipe Reinforced Concrete 18-Inch	1.000 EACH	_____.	_____.
0082	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	3.000 EACH	_____.	_____.
0084	522.2619 Apron Endwalls for Culvert Pipe Reinforced Concrete Horizontal Elliptical 19x30-Inch	2.000 EACH	_____.	_____.
0086	603.8000 Concrete Barrier Temporary Precast Delivered	19,293.000 LF	_____.	_____.

