



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

October 28, 2021

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #40: 8130-00-72, WISC 2022031
Spoooner – Stone Lake
Crystal Brook Bridge B-65-0065
STH 70
Washburn County

8130-01-70, WISC 2022032
Spoooner – Stone Lake
USH 53 To South Junction CTH M
STH 70
Washburn County

Letting of November 9, 2021

This is Addendum No. 01, which provides for the following:

Special Provisions:

Added Special Provisions	
Article No.	Description
25	Removing Structure Over Waterway Remove Debris B-65-60, Item 203.0250

Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
203.0250	Removing Structure Over Waterway Remove Debris (structure) 01. B-65-60	EACH	0	1	1

Deleted Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
203.0200	Removing Old Structure (station) 01. 678+12	LS	1	-1	0

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01
8130-00-72, 8130-01-70
October 28, 2021

Special Provisions

25. Removing Structure Over Waterway Remove Debris B-65-60, Item 203.0250.

This work shall be according to the pertinent requirements of standard spec 203 and as provided here.

Excavate around existing culvert, leaving existing soil at each end of culvert, measuring seven feet tall and five feet thick. In excavated area, place riprap on each side of existing culvert at plan elevations. Excavation and riprap placement will be in confined area. Remove soil and culvert at inlet, placing riprap as excavation occurs. Remove soil and culvert at outlet, placing riprap as excavation occurs. After complete culvert removal, additions and/or movement of riprap will be required for final slope protection.

Payment is full compensation for sequenced removal.

Schedule of Items

Attached, dated October 28, 2021, are the revised Schedule of Items Pages 1 - 8.

END OF ADDENDUM



Proposal Schedule of Items

Proposal ID: 20211109040 Project(s): 8130-00-72, 8130-01-70

Federal ID(s): WISC 2022032, WISC 2022031

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	4.000 STA	_____.	_____.
0004	203.0100 Removing Small Pipe Culverts	3.000 EACH	_____.	_____.
0008	204.0115 Removing Asphaltic Surface Butt Joints	625.000 SY	_____.	_____.
0010	204.0120 Removing Asphaltic Surface Milling	2,816.000 SY	_____.	_____.
0012	204.0165 Removing Guardrail	580.000 LF	_____.	_____.
0014	204.0270 Abandoning Culvert Pipes	3.000 EACH	_____.	_____.
0016	205.0100 Excavation Common	8,780.000 CY	_____.	_____.
0018	206.1000 Excavation for Structures Bridges (structure) 01. B-65-0060	LS	LUMP SUM	_____.
0020	209.0200.S Backfill Controlled Low Strength	34.000 CY	_____.	_____.
0022	210.1500 Backfill Structure Type A	772.000 TON	_____.	_____.
0024	211.0100 Prepare Foundation for Asphaltic Paving (project) 01. 8130-01-70	LS	LUMP SUM	_____.
0026	211.0700.S Prepare Foundation for CIR Base Layer (project) 01. 8130-01-70	1.000 EACH	_____.	_____.
0028	211.0800.S Base Repair for CIR Layer	1,000.000 CY	_____.	_____.
0030	213.0100 Finishing Roadway (project) 01. 8130-01-70	1.000 EACH	_____.	_____.
0032	305.0110 Base Aggregate Dense 3/4-Inch	4,100.000 TON	_____.	_____.
0034	305.0120 Base Aggregate Dense 1 1/4-Inch	1,137.000 TON	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20211109040 Project(s): 8130-00-72, 8130-01-70

Federal ID(s): WISC 2022032, WISC 2022031

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0036	305.0500 Shaping Shoulders	336.000 STA	_____.	_____.
0038	327.1000.S CIR Asphaltic Base Layer	118,190.000 SY	_____.	_____.
0040	415.0060 Concrete Pavement 6-Inch	34.000 SY	_____.	_____.
0042	415.0410 Concrete Pavement Approach Slab	134.000 SY	_____.	_____.
0044	416.0610 Drilled Tie Bars	10.000 EACH	_____.	_____.
0046	416.1010 Concrete Surface Drains	4.000 CY	_____.	_____.
0048	455.0605 Tack Coat	13,648.000 GAL	_____.	_____.
0050	455.0770.S Asphalt Stabilizing Agent	497.000 TON	_____.	_____.
0052	460.0105.S HMA Percent Within Limits (PWL) Test Strip Volumetrics	1.000 EACH	_____.	_____.
0054	460.0110.S HMA Percent Within Limits (PWL) Test Strip Density	2.000 EACH	_____.	_____.
0056	460.2000 Incentive Density HMA Pavement	530.000 DOL	1.00000	530.00
0058	460.2005 Incentive Density PWL HMA Pavement	13,150.000 DOL	1.00000	13,150.00
0060	460.2007 Incentive Density HMA Pavement Longitudinal Joints	25,990.000 DOL	1.00000	25,990.00
0062	460.2010 Incentive Air Voids HMA Pavement	17,940.000 DOL	1.00000	17,940.00
0064	460.6645 HMA Pavement 5 MT 58-34 V	17,936.000 TON	_____.	_____.
0066	460.9000.S Material Transfer Vehicle	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20211109040 Project(s): 8130-00-72, 8130-01-70

Federal ID(s): WISC 2022032, WISC 2022031

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0068	465.0105 Asphaltic Surface	300.000 TON	_____.	_____.
0070	465.0110 Asphaltic Surface Patching	100.000 TON	_____.	_____.
0072	465.0115 Asphaltic Surface Detours	100.000 TON	_____.	_____.
0074	465.0120 Asphaltic Surface Driveways and Field Entrances	11.000 TON	_____.	_____.
0076	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	28,870.000 LF	_____.	_____.
0078	502.0100 Concrete Masonry Bridges	516.000 CY	_____.	_____.
0080	502.3200 Protective Surface Treatment	617.000 SY	_____.	_____.
0082	502.3210 Pigmented Surface Sealer	146.000 SY	_____.	_____.
0084	503.0155 Prestressed Girder Type I 54W-Inch	420.000 LF	_____.	_____.
0086	505.0400 Bar Steel Reinforcement HS Structures	8,460.000 LB	_____.	_____.
0088	505.0600 Bar Steel Reinforcement HS Coated Structures	58,050.000 LB	_____.	_____.
0090	505.0800.S Bar Steel Reinforcement HS Stainless Structures	1,330.000 LB	_____.	_____.
0092	506.2605 Bearing Pads Elastomeric Non-Laminated	8.000 EACH	_____.	_____.
0094	506.4000 Steel Diaphragms (structure) 01. B-65-0060	6.000 EACH	_____.	_____.
0096	516.0500 Rubberized Membrane Waterproofing	34.000 SY	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20211109040 Project(s): 8130-00-72, 8130-01-70

Federal ID(s): WISC 2022032, WISC 2022031

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0098	520.8700 Cleaning Culvert Pipes	3.000 EACH	_____.	_____.
0100	520.9700.S Culvert Pipe Liners (size) 01. 24-Inch	366.000 LF	_____.	_____.
0102	520.9750.S Cleaning Culvert Pipes for Liner Verification	3.000 EACH	_____.	_____.
0104	521.1012 Apron Endwalls for Culvert Pipe Steel 12-Inch	2.000 EACH	_____.	_____.
0106	522.0124 Culvert Pipe Reinforced Concrete Class III 24-Inch	182.000 LF	_____.	_____.
0108	522.0130 Culvert Pipe Reinforced Concrete Class III 30-Inch	94.000 LF	_____.	_____.
0110	522.1024 Apron Endwalls for Culvert Pipe Reinforced Concrete 24-Inch	4.000 EACH	_____.	_____.
0112	522.1030 Apron Endwalls for Culvert Pipe Reinforced Concrete 30-Inch	2.000 EACH	_____.	_____.
0114	530.0112 Culvert Pipe Corrugated Polyethylene 12-Inch	75.000 LF	_____.	_____.
0116	550.2106 Piling CIP Concrete 10 3/4 X 0.365-Inch	2,850.000 LF	_____.	_____.
0118	601.0590 Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBTT	56.000 LF	_____.	_____.
0120	606.0200 Riprap Medium	3.000 CY	_____.	_____.
0122	606.0300 Riprap Heavy	1,006.000 CY	_____.	_____.
0124	611.0654 Inlet Covers Type V	2.000 EACH	_____.	_____.
0126	611.3220 Inlets 2x2-FT	2.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20211109040 Project(s): 8130-00-72, 8130-01-70

Federal ID(s): WISC 2022032, WISC 2022031

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0128	612.0406 Pipe Underdrain Wrapped 6-Inch	220.000 LF	_____.	_____.
0130	614.0150 Anchor Assemblies for Steel Plate Beam Guard	4.000 EACH	_____.	_____.
0132	614.2300 MGS Guardrail 3	263.000 LF	_____.	_____.
0134	614.2500 MGS Thrie Beam Transition	158.000 LF	_____.	_____.
0136	614.2610 MGS Guardrail Terminal EAT	4.000 EACH	_____.	_____.
0138	618.0100 Maintenance And Repair of Haul Roads (project) 01. 8130-01-70	1.000 EACH	_____.	_____.
0140	619.1000 Mobilization	1.000 EACH	_____.	_____.
0142	624.0100 Water	55.000 MGAL	_____.	_____.
0144	625.0500 Salvaged Topsoil	4,375.000 SY	_____.	_____.
0146	627.0200 Mulching	840.000 SY	_____.	_____.
0148	628.1504 Silt Fence	530.000 LF	_____.	_____.
0150	628.1520 Silt Fence Maintenance	530.000 LF	_____.	_____.
0152	628.1905 Mobilizations Erosion Control	4.000 EACH	_____.	_____.
0154	628.1910 Mobilizations Emergency Erosion Control	3.000 EACH	_____.	_____.
0156	628.2008 Erosion Mat Urban Class I Type B	4,375.000 SY	_____.	_____.
0158	629.0210 Fertilizer Type B	2.900 CWT	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20211109040 Project(s): 8130-00-72, 8130-01-70

Federal ID(s): WISC 2022032, WISC 2022031

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0160	630.0120 Seeding Mixture No. 20	121.000 LB	_____.	_____.
0162	630.0500 Seed Water	15.000 MGAL	_____.	_____.
0164	633.5200 Markers Culvert End	31.000 EACH	_____.	_____.
0166	634.0616 Posts Wood 4x6-Inch X 16-FT	53.000 EACH	_____.	_____.
0168	634.0618 Posts Wood 4x6-Inch X 18-FT	2.000 EACH	_____.	_____.
0170	637.2210 Signs Type II Reflective H	81.500 SF	_____.	_____.
0172	637.2230 Signs Type II Reflective F	336.020 SF	_____.	_____.
0174	638.2602 Removing Signs Type II	44.000 EACH	_____.	_____.
0176	638.3000 Removing Small Sign Supports	31.000 EACH	_____.	_____.
0178	642.5001 Field Office Type B	1.000 EACH	_____.	_____.
0180	643.0300 Traffic Control Drums	250.000 DAY	_____.	_____.
0182	643.0420 Traffic Control Barricades Type III	1,980.000 DAY	_____.	_____.
0184	643.0705 Traffic Control Warning Lights Type A	3,960.000 DAY	_____.	_____.
0186	643.0900 Traffic Control Signs	28,730.000 DAY	_____.	_____.
0188	643.0920 Traffic Control Covering Signs Type II	4.000 EACH	_____.	_____.
0190	643.1000 Traffic Control Signs Fixed Message	14.000 SF	_____.	_____.
0192	643.5000 Traffic Control	1.000 EACH	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20211109040 Project(s): 8130-00-72, 8130-01-70

Federal ID(s): WISC 2022032, WISC 2022031

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0194	645.0111 Geotextile Type DF Schedule A	115.000 SY	_____.	_____.
0196	645.0120 Geotextile Type HR	1,489.000 SY	_____.	_____.
0198	646.1005 Marking Line Paint 4-Inch	179,300.000 LF	_____.	_____.
0200	646.1020 Marking Line Epoxy 4-Inch	34,270.000 LF	_____.	_____.
0202	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	65,960.000 LF	_____.	_____.
0204	646.3005 Marking Line Paint 8-Inch	100.000 LF	_____.	_____.
0206	649.0105 Temporary Marking Line Paint 4-Inch	66,784.000 LF	_____.	_____.
0208	649.0120 Temporary Marking Line Epoxy 4-Inch	34,270.000 LF	_____.	_____.
0210	650.4500 Construction Staking Subgrade	549.000 LF	_____.	_____.
0212	650.5000 Construction Staking Base	549.000 LF	_____.	_____.
0214	650.5500 Construction Staking Curb Gutter and Curb & Gutter	56.000 LF	_____.	_____.
0216	650.6000 Construction Staking Pipe Culverts	3.000 EACH	_____.	_____.
0218	650.6500 Construction Staking Structure Layout (structure) 01. B-65-0060	LS	LUMP SUM	_____.
0220	650.8000 Construction Staking Resurfacing Reference	34,100.000 LF	_____.	_____.
0222	650.9910 Construction Staking Supplemental Control (project) 01. 8130-00-72	LS	LUMP SUM	_____.



Proposal Schedule of Items

Proposal ID: 20211109040 Project(s): 8130-00-72, 8130-01-70

Federal ID(s): WISC 2022032, WISC 2022031

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0224	650.9910 Construction Staking Supplemental Control (project) 02. 8130-01-70	LS	LUMP SUM	_____.
0226	650.9920 Construction Staking Slope Stakes	1,098.000 LF	_____.	_____.
0228	690.0150 Sawing Asphalt	60.000 LF	_____.	_____.
0230	715.0415 Incentive Strength Concrete Pavement	500.000 DOL	1.00000	500.00
0232	715.0502 Incentive Strength Concrete Structures	3,096.000 DOL	1.00000	3,096.00
0234	740.0440 Incentive IRI Ride	25,290.000 DOL	1.00000	25,290.00
0236	ASP.1T0A On-the-Job Training Apprentice at \$5.00/HR	1,000.000 HRS	5.00000	5,000.00
0238	ASP.1T0G On-the-Job Training Graduate at \$5.00/HR	1,000.000 HRS	5.00000	5,000.00
0240	SPV.0090 Special 01. Ditch Cleaning	200.000 LF	_____.	_____.
0242	203.0250 Removing Structure Over Waterway Remove Debris (structure) 01. B-65-60	1.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.