



# Wisconsin Department of Transportation

December 9, 2021

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #08: 5160-07-71, WISC 2022068**  
**Ferryville - Genoa**  
**Old Hwy 35 To STH 56/B-62-93,-264**  
**STH 35**  
**Vernon & Crawford Counties**

### Letting of December 14, 2021

This is Addendum No. 02, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
3	Prosecution and Progress

#### Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
204.0120	Removing Asphaltic Surface Milling	SY	239,726	11,675	251,401

#### Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
63	Miscellaneous Quantities (Removing Asphaltic Surface items were revised to address removal of SPV item Salvaged Asphaltic Pavement (Addendum No. 01))
194	Cross Sections (Culvert pipe note was updated to match miscellaneous quantities)
205	Cross Sections (Culvert pipe note was updated to match miscellaneous quantities)

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 02**

**5160-07-71**

**December 9, 2021**

**Special Provisions**

**3. Prosecution and Progress.**

*Replace the entire section titled Guardrail, Milling, Cold In-Place Recycling (CIR), and Paving with the following:*

Guardrail, Milling, and Cold In-Place Recycling (CIR):

Remove guardrail at the beginning of the milling operation. Delineate the shoulders with drums where guardrail has been removed. After the milling operation, traffic may operate on the milled surface for no more than 7 continuous calendar days. CIR work shall be completed only between May 1 and October 1 of the year of construction. Stage construction operations to minimize trucking on the CIR surface. These timeframes do not apply in Excavation Below Subgrade (EBS) areas.

The contract time for completion is based on an expedited work schedule and may require extraordinary forces and equipment.

**Schedule of Items**

Attached, dated December 9, 2021, are the revised Schedule of Items Page 1.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 63, 194, and 205.

END OF ADDENDUM

CLEARING AND GRUBBING

CATEGORY	STATION	TO	STATION	LOCATION	201.0105 CLEARING STA	201.0205 GRUBBING STA
0010	917+50	-	918+50	LT	1	1
0010	942+00	-	943+00	LT	1	1
0010	UNDISTRIBUTED				2	2
					TOTAL 0010	4

REMOVING ASPHALTIC SURFACE ITEMS

CATEGORY	STATION	TO	STATION	LOCATION	204.0115 REMOVING ASPHALTIC SURFACE BUTT JOINTS	204.0120 REMOVING ASPHALTIC SURFACE MILLING	REMARKS
0010	450+95	-	451+48	MAINLINE	200		
0010	451+48	-	491+31	MAINLINE	154	13,905	
0010	491+31	-	491+81	MAINLINE	154		
0010	492+56	-	493+06	MAINLINE	156		
0010	493+06	-	877+45	MAINLINE	---	155,548	
0010	493+89	-	496+82	LT	118		BOAT LANDING
0010	503+64	-	506+67	RT	190		CRAWFORD STREET
0010	509+22	-	510+71	RT	286		STH 82
0010	515+40	-	516+71	RT	324		S MILL PARK DRIVE
0010	626+33	-	637+06	RT	160		ZITZNER ROAD
0010	650+46	-	651+88	RT	175		BATTLE HOLLOW ROAD
0010	677+73	-	678+40	LT	105		CHBI
0010	680+63	-	682+13	RT	181		BLUFF ROAD
0010	693+53	-	694+01	LT	107		GANTENBEN ROAD
0010	734+60	-	736+17	RT	171		TERHUNE STREET
0010	740+15	-	740+65	RT	60		STEVENS ROAD
0010	741+95	-	742+56	RT	88		CTH UU
0010	748+54	-	749+14	RT	74		WASHINGTON STREETS
0010	759+56	-	760+44	RT	142		WASHINGTON STREET N
0010	861+12	-	863+03	RT	252		HECKS POINT ROAD
0010	877+45	-	877+95	MAINLINE	245		
0010	880+39	-	880+59	MAINLINE	---	27	
0010	880+59	-	892+59	MAINLINE	---	5,945	
0010	890+05	-	890+98	RT	193		MEADOW LANE
0010	892+39	-	892+89	MAINLINE	---	200	MILLING TRANSITION
0010	892+89	-	1075+25	MAINLINE	---	73,776	
0010	921+39	-	922+70	RT	258		MUNDSACK ROAD
0010	997+47	-	998+53	RT	204		EDGEWOOD LANE
0010	1027+49	-	1028+65	RT	110		GHANOLI ROAD
0010	1074+31	-	1075+75	RT	237		STH 56
0010	1075+25	-	1075+75	MAINLINE	200		
					TOTAL 0010	4,390	
					TOTAL 0010	253,400	

TOTAL 0010 21

REMOVING CONCRETE

CATEGORY	STATION	TO	STATION	LOCATION	SY	
0010	917+50	-	918+50	LT	1	
0010	942+00	-	943+00	LT	1	
0010	UNDISTRIBUTED				2	
					TOTAL 0010	4

PROJECT NO: 5160-07-1

HWY: STH 35

COUNTY: CRAWFORD & VERNON

MISCELLANEOUS QUANTITIES

PLOT NAME: 11

SHEET: 63


E

REMOVING GUARDRAIL

CATEGORY	STATION	TO	STATION	LOCATION	204.0165 REMOVING GUARDRAIL	
0010	489+81	-	491+83	RT	200	
0010	489+81	-	491+83	LT	200	
0010	492+57	-	496+01	LT	352	
0010	492+58	-	494+10	RT	151	
0010	508+10	-	511+13	LT	303	
0010	593+29	-	594+49	RT	135	
0010	644+95	-	652+12	LT	716	
0010	665+91	-	667+90	LT	1,204	
0010	675+20	-	677+86	RT	266	
0010	678+40	-	693+55	LT	1,514	
0010	694+00	-	720+33	LT	2,640	
0010	753+89	-	755+05	RT	116	
0010	793+56	-	813+83	LT	2,028	
0010	820+68	-	840+91	LT	2,015	
0010	876+41	-	877+89	LT	148	
0010	876+40	-	877+88	RT	148	
0010	912+71	-	919+52	LT	690	
0010	919+84	-	922+24	LT	241	
0010	922+63	-	927+23	LT	466	
0010	932+21	-	942+20	LT	1,003	
0010	994+78	-	1005+94	LT	1,116	
0010	1014+00	-	1015+70	LT	178	
0010	1014+05	-	1016+29	RT	229	
0010	1036+26	-	1059+15	RT	2,292	
0010	1059+24	-	1065+15	LT	592	
0010	1069+43	-	1073+23	LT	380	
					TOTAL 0010	19,343

REMOVING STORM SEWER

CATEGORY	STATION	TO	STATION	LOCATION	204.0245.01 REMOVING STORM SEWER (SIZE) (01.24- INCH)	
0010	1058+15	-			59	
					TOTAL 0010	59







## Proposal Schedule of Items

Proposal ID: 20211214008 Project(s): 5160-07-71

Federal ID(s): WISC 2022068

SECTION: 0001 Roadway Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	4.000 STA	_____.	_____.
0004	201.0205 Grubbing	4.000 STA	_____.	_____.
0006	203.0100 Removing Small Pipe Culverts	21.000 EACH	_____.	_____.
0008	203.0220 Removing Structure (structure) 01. B-62-18	1.000 EACH	_____.	_____.
0010	203.0220 Removing Structure (structure) 02.B-62-93	1.000 EACH	_____.	_____.
0012	203.0335 Debris Containment Over Waterway (structure) 01.B-12-20	1.000 EACH	_____.	_____.
0014	204.0100 Removing Concrete Pavement	39.000 SY	_____.	_____.
0016	204.0110 Removing Asphaltic Surface	1,371.000 SY	_____.	_____.
0018	204.0115 Removing Asphaltic Surface Butt Joints	4,390.000 SY	_____.	_____.
0020	204.0120 Removing Asphaltic Surface Milling	251,401.000 SY	_____.	_____.
0022	204.0165 Removing Guardrail	19,343.000 LF	_____.	_____.
0024	204.0220 Removing Inlets	1.000 EACH	_____.	_____.
0026	204.0245 Removing Storm Sewer (size) 01. 24-Inch	59.000 LF	_____.	_____.
0028	205.0100 Excavation Common	7,655.000 CY	_____.	_____.
0030	206.1000 Excavation for Structures Bridges (structure) 01.B-62-93	LS	LUMP SUM	_____.