



Wisconsin Department of Transportation

November 23, 2021

**Division of Transportation Systems
Development**

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #16 5725-00-72, WISC 2022 076
STH 11 – CTH N
Pecatonica River Bridge, B-33-0138
CTH D
Lafayette County

Letting of December 14, 2021

This is Addendum No. 01, which provides for the following:

Special Provisions:

Revised Special Provisions	
Article No.	Description
6	Utilities

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

ADDENDUM NO. 01

5725-00-72

November 23, 2021

Special Provisions

1. Utilities.

Replace entire article language with the following:

This contract does not come under the provision of Administrative Rule Trans 220.

stp-107-066 (20080501)

Within the limits of this project there are underground and aerial facilities. Coordinate construction activities with a call to Diggers Hotline, and/or a direct call to the utilities for the underground facilities in the area as required per statutes. Use caution to ensure the integrity of underground facilities, and maintain OSHA code clearances from overhead facilities at all times.

Alliant Energy (Electric)

Alliant Energy has overhead electric along the west side of CTH D. The overhead line cross over CTH D at the curve north of the bridge and continues along the west side of CTH N.

Alliant Energy plans to bury new facilities beginning at STA 14+50 RT and will cross under CTH D to the east side of the roadway. New buried facilities will continue to the north along the eastern right of way of CTH D crossing under the Pecatonica River, continuing north along CTH N. Approximately 100-feet north of the project limits on CTH N, buried facilities will cross under CTH N to the west side to reconnect with existing facilities. Existing poles at the following locations and associated wires within the project limits will be removed: Sta. 12+56, RT, 10+52, RT, 8+96, LT, and 81+84, LT. New facilities will be installed prior to construction.

TDS Telecom (Communications)

TDS has a copper cable that runs west along CTH D; a copper and fiber facility that runs north along CTH N, a copper and fiber facility that runs south along CTH D; and buried facilities that cross under CTH D to the west of CTH N.

Beginning at STA 11+64, 46' RT, TDS will install new buried fiber facilities located approximately 3-feet to the east of the new proposed western right of way line for CTH D. New facilities will be located at a depth of approximately 48"- 60" including underneath the streambed for the Pecatonica River. At approximately STA 8+20, 50' RT, buried fiber along the proposed right of way will bend to the north to cross under CTH D at approximately STA 7+50, towards the northern proposed right of way for CTH D. The buried fiber will branch to the west along CTH D with a 3-foot offset from the proposed right of way along CTH D and to the northwest along CTH N with a 3-foot offset from the proposed right of way along CTH N.

New buried fiber will connect into existing fiber just outside the western project limits on the north side of CTH D, at the project limits on CTH N on the west side, and at approximately STA 11+64, 75' RT on the southern limits of CTH D.

Existing facilities between Sta. 0+10 and Sta. 11+00 along CTH D will be discontinued. Existing facilities between Sta. 80+00 and Sta. 83+00 along CTH N will be discontinued. New facilities will be installed prior to construction.

END OF ADDENDUM