



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

May 4, 2022

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #02: 1011-01-60, WISC 2022373
Madison - Portage
.55 Mi S Cth V To North County Line
IH 39
Dane County

1011-01-75, WISC 2022375
Madison - Portage
Cth V To 0.4 Mi N of Cth I, Nb Rdwy
IH 39
Dane County

Letting of May 10, 2022

This is Addendum No. 03, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
416.1715	Concrete Pavement Repair SHES	SY	1,527	509	2,036

Plan Sheets:

Revised Plan Sheets (Project ID 1011-01-60)	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
28	Updated Miscellaneous Quantity Sheet

Schedule of Items

Attached, dated May 4, 2022, are the revised Schedule of Items Page 1.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:
Project ID 1011-01-60. Revised: 28.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

CONCRETE PAVEMENT

***ALL ITEMS CATEGORY 0010 UNLESS OTHERWISE NOTED.

PROJECT NO: 1011-01-60

HWY: IH 39

COUNTY: DANE

MISCELLANEOUS QUANTITIES

SHEET 28

E

STATION TO	STATION	ALIGNMENT	305.0110 BASE AGGREGATE DENSE 3/4-INCH (TON)	624.0100 WATER (MGAL)	415.0080 CONCRETE PAVEMENT 8-INCH (SY)	416.0610 DRILLED TIE BARS (EACH)	416.0620 DRILLED DOWEL BARS (EACH)	416.1710 CONCRETE PAVEMENT REPAIR (SY)	* 416.1715 CONCRETE PAVEMENT REPAIR SHES (SY)	416.1720 CONCRETE PAVEMENT REPLACEMENT (SY)	416.1725 CONCRETE PAVEMENT REPLACEMENT SHES (SY)	COMMENT
407+70 -	435+00	'EB'	0	0	0	20	48	0	32	0	21	STAGE 1A
435+00 -	464+00	'EB'	0	0	0	0	16	0	11	0	0	
464+00 -	493+75	'EB'	0	0	0	0	0	0	0	0	21	
493+75 -	522+75	'EB'	0	0	0	12	48	0	28	0	0	
522+75 -	551+75	'EB'	0	0	0	0	0	0	0	0	0	
551+75 -	580+75	'EB'	0	0	0	0	0	0	0	0	0	
580+75 -	609+75	'EB'	0	0	0	8	16	0	0	0	0	
609+75 -	629+24	'EB'	0	0	0	0	128	0	71	0	0	
STAGE 1A TOTAL												
407+70 -	435+00	'EB'	0	0	0	0	160	0	109	0	0	
435+00 -	464+00	'EB'	0	0	0	67	96	0	63	0	112	STAGE 1B
464+00 -	493+75	'EB'	0	0	0	0	48	0	37	0	0	
493+75 -	522+75	'EB'	0	0	0	0	48	0	32	0	0	
522+75 -	551+75	'EB'	0	0	0	0	80	0	57	0	0	
551+75 -	580+75	'EB'	0	0	0	0	208	0	149	0	0	
580+75 -	609+75	'EB'	0	0	0	17	64	0	45	0	0	
609+75 -	629+24	'EB'	0	0	0	84	736	0	25	0	112	
STAGE 1B TOTAL												
STAGE 1 TOTALS												
407+70 -	435+00	'WB'	0	0	0	104	864	0	589	0	133	
435+00 -	464+00	'WB'	0	0	0	0	32	0	29	0	0	STAGE 2A
464+00 -	493+75	'WB'	0	0	0	0	16	0	11	0	0	
493+75 -	522+75	'WB'	0	0	0	0	0	0	0	0	0	
522+75 -	551+75	'WB'	0	0	0	230	64	0	0	383	119	
551+75 -	580+75	'WB'	0	0	0	102	48	0	0	170	0	
580+75 -	609+75	'WB'	0	0	0	22	16	0	0	0	0	
609+75 -	629+24	'WB'	0	0	0	353	176	0	40	553	0	
STAGE 2A TOTAL												
407+70 -	435+00	'WB'	0	0	0	0	128	0	93	0	145	STAGE 2B
435+00 -	464+00	'WB'	0	0	0	0	32	0	27	0	0	
464+00 -	493+75	'WB'	0	0	0	0	128	0	85	0	0	
493+75 -	522+75	'WB'	0	0	0	0	48	0	32	0	0	
522+75 -	551+75	'WB'	0	0	0	71	576	0	352	0	0	
551+75 -	580+75	'WB'	0	0.8	74	53	3	0	175	0	26	
580+75 -	609+75	'WB'	46	0.7	68	50	224	0	0	0	0	
609+75 -	629+24	'WB'	96	1.5	142	37	432	0	303	0	0	
STAGE 2B TOTAL												
STAGE 2 TOTALS												
UNDISTRIBUTED			96	1.5	142	564	1,747	0	1,107	553	145	
PROJECT TOTALS			106	1.7	142	802	3,134	50	340	111	56	
MISCELLANEOUS QUANTITIES												
PROJECT TOTALS												
PROJECT TOTALS												
PROJECT TOTALS												

Addendum No. 03
ID 1011-01-60
Revised Sheet 28
May 4, 2022

*PATCHING TO BE EXTENDED 4-FEET PAST EXISTING TRANSVERSE JOINT. PATCHES SHALL BE 8-FEET MINIMUM.

**UNDISTRIBUTED QUANTITY FOR 'WB' MEDIAN AND OUTSIDE SHOULDER CONCRETE PAVEMENT REPAIR/REPLACEMENT BETWEEN STA 547+00/WB' AND 595+00/WB' REQUIRED FOR PROJECT 1011-01-75 STAGING. LOCATIONS TO BE DETERMINED BY ENGINEER.



Proposal Schedule of Items

Proposal ID: 20220510002 Project(s): 1011-01-60, 1011-01-75

Federal ID(s): WISC 2022375, WISC 2022373

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0100 Removing Concrete Pavement	8,434.000 SY	_____.	_____.
0004	204.0110 Removing Asphaltic Surface	142.000 SY	_____.	_____.
0006	211.0200 Prepare Foundation for Concrete Pavement (project) 01. 1011-01-60	LS	LUMP SUM	_____.
0008	211.0200 Prepare Foundation for Concrete Pavement (project) 01. 1011-01-75	LS	LUMP SUM	_____.
0010	213.0100 Finishing Roadway (project) 01. 1011-01-60	1.000 EACH	_____.	_____.
0012	213.0100 Finishing Roadway (project) 02. 1011-01-75	1.000 EACH	_____.	_____.
0014	305.0110 Base Aggregate Dense 3/4-Inch	106.000 TON	_____.	_____.
0016	305.0120 Base Aggregate Dense 1 1/4-Inch	468.000 TON	_____.	_____.
0018	415.0080 Concrete Pavement 8-Inch	142.000 SY	_____.	_____.
0020	415.1125 Concrete Pavement HES 12 1/2-Inch	8,434.000 SY	_____.	_____.
0022	416.0610 Drilled Tie Bars	4,599.000 EACH	_____.	_____.
0024	416.0620 Drilled Dowel Bars	3,166.000 EACH	_____.	_____.
0026	416.1110 Concrete Shoulder Rumble Strips	8,600.000 LF	_____.	_____.
0028	416.1710 Concrete Pavement Repair	50.000 SY	_____.	_____.
0030	416.1715 Concrete Pavement Repair SHES	2,036.000 SY	_____.	_____.
0032	416.1720 Concrete Pavement Replacement	664.000 SY	_____.	_____.