



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

November 2, 2022

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #36: 4489-02-70, WISC 2023037
T Brothertown - Chilton
E Jefferson Rd to W Chestnut St
CTH G
Calumet County

Letting of November 8, 2022

This is Addendum No. 03, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Old Quantity	Revised Quantity	Proposal Total
205.0100	Common Excavation	CY	8,169	-900	7,269

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
20	MISCELLANEOUS QUANTITIES – Changed quantity of item 205.0100 Common Excavation to 7,269 cy, as the quantity for the pulverization expansion material was changed to be incidental to item 325.0100 pulverize and relay and note (8) was added to explain the common excavation measurement as it relates to the expansion of the pulverized material.

Schedule of Items

Attached, dated November 2, 2022, are the revised Schedule of Items Page 1.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 20.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 03
ID 4489-02-70
Revised Sheet 20
November 2, 2022

EXCAVATION COMMON

DIVISION	FROM/TO STATION	COMMON EXCAVATION (1)(8)		SALVAGED/UNUSABLE PAVEMENT MATERIAL (4)	AVAILABLE MATERIAL (5)	UNEXPANDED FILL	EXPANDED FILL FACTOR (6)	MASS ORDINATE +/- (7)	COMMENTS
		CUT (2)	EBS EXCAVATION						
CTH-G	1+00 TO 35+50	1,530	0	0	1,530	124	155	1,375	PULVERIZED AND REMOVAL OF EXCESS PULVERIZED MATERIAL
CTH-G	35+50 TO 47+00	3,201	0	736	2,465	10	13	3,828	RECONSTRUCT
CTH-G	47+00 TO 109+25	2,038	0	0	2,038	140	175	5,691	PULVERIZED AND REMOVAL OF EXCESS PULVERIZED MATERIAL
CTH-G	UNDIST	0	500	0	500	0	0	6,189	
TOTAL COMMON EXC (8)		7,269							

NOTES:

- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
- (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
- (3) EBS EXCAVATION TO BE BACK FILLED WITH 1 1/4" BASE AGGREGATE DENSE
- (4) SALVAGED/UNUSABLE PAVEMENT MATERIAL
- (5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
- (6) EXPANDED FILL FACTOR = 1.25
- (7) THIS MASS ORDINATE +/- IS CALCULATED FOR THE REGION PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.
- (8) MEASUREMENT OF COMMON EXCAVATION SHALL COMPARE THE EXISTING SURFACE (PRIOR TO PULVERIZING) TO THE PROPOSED SUBGRADE SURFACE. NO ADDITIONAL QUANTITY SHALL BE INCLUDED FOR THE EXPANSION OF PULVERIZED MATERIAL

REMOVING ASPHALTIC SURFACE MILLING

204.0115 204.0120 325.0100 624.0100

STATION	TO	STATION	LOCATION	SY	SY	MGAL	REMARKS
1+00	-	35+50	CTH G	--	--	74	SOUTH RURAL SEGMENT
35+50	-	47+00	CTH G	--	--	--	PAVEMENT REPLACEMENT SEGMENT
47+00	-	109+25	CTH G	--	--	133	SOUTH RURAL SEGMENT
109+25	-	116+81	CTH G	9	3,400	--	NORTH URBAN SEGMENT
UNDISTRIBUTED			CTH G	--	--	800	DRIVEWAYS
TOTAL		9		3,400	35,300	207*	

BASE AGGREGATE ITEMS

STATION	TO	STATION	LOCATION	TON	TON	MGAL
1+00	-	35+50	CTH G	600	400	8
35+50	-	47+00	CTH G	200	5000	100
47+00	-	109+25	CTH G	1,100	600	12
UNDISTRIBUTED			UNDIST	600	1,000	20
TOTAL		2,500		7,000	132*	

*ADDITIONAL QUANTITY LISTED IN PLANS

ALL ITEMS 0010 CATEGORY UNLESS OTHERWISE LISTED



Proposal Schedule of Items

Proposal ID: 20221108036 Project(s): 4489-02-70

Federal ID(s): WISC 2023037

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	204.0115 Removing Asphaltic Surface Butt Joints	9.000 SY	_____.	_____.
0004	204.0120 Removing Asphaltic Surface Milling	3,400.000 SY	_____.	_____.
0006	205.0100 Excavation Common	7,269.000 CY	_____.	_____.
0008	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 4489-02-70	1.000 EACH	_____.	_____.
0010	213.0100 Finishing Roadway (project) 01. 4489-02-70	1.000 EACH	_____.	_____.
0012	305.0110 Base Aggregate Dense 3/4-Inch	2,500.000 TON	_____.	_____.
0014	305.0120 Base Aggregate Dense 1 1/4-Inch	7,000.000 TON	_____.	_____.
0016	325.0100 Pulverize and Relay	35,300.000 SY	_____.	_____.
0018	455.0605 Tack Coat	5,750.000 GAL	_____.	_____.
0020	460.2000 Incentive Density HMA Pavement	5,984.000 DOL	1.00000	5,984.00
0022	460.5223 HMA Pavement 3 LT 58-28 S	5,250.000 TON	_____.	_____.
0024	460.5224 HMA Pavement 4 LT 58-28 S	4,100.000 TON	_____.	_____.
0026	465.0110 Asphaltic Surface Patching	25.000 TON	_____.	_____.
0028	465.0120 Asphaltic Surface Driveways and Field Entrances	50.000 TON	_____.	_____.
0030	465.0475 Asphalt Centerline Rumble Strips 2-Lane Rural	9,400.000 LF	_____.	_____.
0032	611.8110 Adjusting Manhole Covers	1.000 EACH	_____.	_____.