



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

December 9, 2022

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #24: 9160-17-71, WISC 2023107
Pound – Marinette
USH 141 – CTH E
STH 64
Marinette County

9160-19-71, WISC 2023108
Pound – Marinette
CTH E – STH 180
STH 64
Marinette County

Letting of December 13, 2022

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
643.3120	Temporary Marking Line Epoxy 4-Inch	LF	108,430	-54,215	51,205
646.1020	Marking Line Epoxy 4-Inch	LF	80,515	-23,930	56,585
646.3545	Marking Line Grooved Wet Ref Contrast Epoxy 8-Inch	LF	1280	-200	1080

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
646.4520	Marking Line Same Day Epoxy 4-Inch	LF	0	3,010	3,010

Plan Sheets:

Revised Plan Sheets – 9160-17-71	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
37	Miscellaneous Quantities – Updated Marking Quantity

Revised Plan Sheets – 9160-19-71	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
38	Miscellaneous Quantities – Updated and Added Marking Quantity

Schedule of Items

Attached, dated December 9, 2022, are the revised Schedule of Items Pages 9 and 11.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

9160-17-71 Revised: 37

9160-19-71 Revised: 38

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

Addendum No. 02
ID 9160-17-71
Revised Sheet 37
December 9, 2022

TRAFFIC CONTROL

STAGE/LOCATION	APPROXIMATE SERVICE PERIOD		643.0300		643.0420		643.0705		643.0900		643.1050		REMARKS
	DAYS	NO. IN SERVICE	TRAFFIC CONTROL DRUMS	TRAFFIC CONTROL BARRICADES TYPE III	TRAFFIC CONTROL WARNING LIGHTS TYPE A	TRAFFIC CONTROL SIGNS	SIGNS PORTABLE MESSAGE	NO. IN SERVICE	TRAFFIC CONTROL SIGNS	SIGNS PORTABLE MESSAGE	NO. IN SERVICE	TRAFFIC CONTROL SIGNS	
SIDERoadS DURING BOX CULVERT REMOVAL/CULVERT REPLACEMENT	21	-	-	13	273	26	546	39	819	-	-	-	BARRICADES AND SIGNS FOR SIDEROAD CLOSURES DETAIL 4
MAINLINE CLOSURE FOR BOX CULVERT REMOVAL/CULVERT REPLACEMENT	21	-	-	10	210	20	420	10	210	-	-	-	BARRICADES AND SIGNS FOR MAINLINE CLOSURES DETAIL A & C
MAINLINE CLOSURES FOR SMALL CULVERT WORK	14	-	-	10	140	20	280	10	140	-	-	-	BARRICADES AND SIGNS FOR MAINLINE CLOSURES DETAIL A & C
SIDERoadS DURING SMALL CULVERT WORK	14	-	-	2	28	4	56	6	84	-	-	-	BARRICADES AND SIGNS FOR SIDEROAD CLOSURES DETAIL 4
CULVERT WORK AREA	14	6	84	-	-	-	-	2	28	-	-	-	CULVERT AREAS AFTER REPLACEMENT PRIOR TO PAVING
MAINLINE ADVANCED WARNING	65	-	-	-	-	-	-	10	650	2	14	-	MAINLINE ADVANCED SIGNING WHEN STH 64 IS OPEN TO THRU TRAFFIC
MILLING AND PAVING	65	16	1,040	-	-	-	-	8	520	-	-	-	MILLED SURFACE AND UNEVEN LANE SITUATIONS
SIDERoadS DURING MILLING AND PAVING	65	-	-	-	-	-	-	23	1,495	-	-	-	ROAD WORK AHEAD ON ALL SIDEROADS
SHOULDER WORK	10	16	160	-	-	-	-	4	40	-	-	-	SHOULDER DROP-OFFS DURING CONSTRUCTION
UNDISTRIBUTED	-	-	116	-	179	-	358	-	254	-	-	-	
TOTALS			1,400	830	1,660	4,240	2	14					

* ADDITIONAL QUANTITIES SHOWN ELSEWHERE

MARKING

STATION	TO	STATION	LOCATION	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	MARKING LINE	REMARKS	
				PAINT 4-INCH	EPOXY 4-INCH	EPOXY 4-INCH	REF EPOXY 4-INCH	GROOVED WET	GROOVED WET	REF CONTRAST	EPOXY 8-INCH	EPOXY	EPOXY	EPOXY	EPOXY	EPOXY	EPOXY	EPOXY	EPOXY		
				LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF	LF		
643.3105	-	643.3120	646.1020	646.1040	646.3545	646.5220	646.8320														
29407	-	575+65	STH 64	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	TEMPORARY MARKING LINE	YELLOW CENTERLINE MILLED SURFACE	
29407	-	575+65	STH 64	33,295	33,295	33,295	33,295	33,295	33,295	33,295	33,295	33,295	33,295	33,295	33,295	33,295	33,295	33,295	33,295	YELLOW CENTERLINE SURFACE LAYER UNEVEN PAVEMENT - JOINT AREA	
29407	-	575+65	STH 64	750	750	750	750	750	750	750	750	750	750	750	750	750	750	750	750	CULVERT REPLACEMENT	
29407	-	575+65	STH 64	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	WHITE EDGE LINE & CHANNELIZATION	
29407	-	575+65	STH 64	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	YELLOW CENTERLINE	
370+58	-	372+50	STH 64	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	PARK AND RIDE	
TOTALS				67,340	33,295	33,295	109,320	480	480	1	1	375	375								

NOTE: PROVIDE FULL REPLACEMENT OF EXISTING MARKINGS WITH TEMPORARY MARKINGS
EDGELINES WHICH DO NOT NEED TO BE MARKED UNTIL FINAL MARKINGS, EXCEPT IN CULVERT REPLACEMENT AREAS BEFORE BEING MILLED

TRAFFIC CONTROL

STAGE/LOCATION	603.8000	603.8125	643.0300	643.0420	643.0705	643.0900	643.1050	REMARKS
APPROXIMATE SERVICE PERIOD	CONCRETE BARRIER DELIVERED	CONCRETE BARRIER TEMPORARY PRECAST INSTALLED	TRAFFIC CONTROL DRUMS	TRAFFIC CONTROL BARRICADES TYPE III	TRAFFIC CONTROL WARNING LIGHTS TYPE A	TRAFFIC CONTROL SIGNS	TRAFFIC CONTROL SIGNS PCMS	
DAYS	LF	LF	NO. IN SERVICE DAY	NO. IN SERVICE DAY	NO. IN SERVICE DAY	NO. IN SERVICE DAY	NO. IN SERVICE DAY	
MAINLINE CLOSURE FOR BOX CULVERT WORK/CULVERT REPLACEMENTS	-	-	-	20	40	20	-	BARRICADES AND SIGNS FOR MAINLINE CLOSURES DETAIL A & C
BOX CULVERT WINGWALL REPLACEMENT	200	200	10	2	4	16	224	ONE LANE ROAD STOP CONDITION FOR WINGWALL WORK
SIDEROAD SIGNING DURING DETOUR	-	-	16	17	34	51	1,428	BARRICADES USED AT ALL THROUGH SIDEROADS
CULVERT WORK	-	-	-	-	-	8	-	CULVERTS AFTER REPLACEMENT PRIOR TO PAVING
MAINLINE ADVANCED WARNING	-	-	-	-	-	10	700	2 14 MAINLINE ADVANCED SIGNING WHEN STH 64 IS OPEN TO THRU TRAFFIC
MILLING AND PAVING	-	-	16	-	-	8	560	MILLED SURFACE AND UNEVEN LANE SITUATIONS
SIDEROADS DURING MILLING AND PAVING	-	-	-	-	-	17	1,190	ROAD WORK AHEAD ON ALL SIDEROADS
SHOULDER PAVEMENT WIDENING WORK	-	-	50	-	-	4	40	SHOULDER DROP-OFFS DURING CONSTRUCTION
UNDISTRIBUTED	-	-	-	211	-	-	456	
TOTALS	200	200	2,650	1,275	2,550	5,382	14	

PAVEMENT MARKING

STATION	TO	LOCATION	LF	LF	LF	LF	REMARKS	
582+00	-	584+00	150	-	-	200	ONE LANE ROAD STOP CONDITION FOR WINGWALL WORK	
575+65	-	946+36	5TH 64	-	-	-	YELLOW CENTERLINE MILLED SURFACE	
575+65	-	20+920	20+920	-	-	-	YELLOW CENTERLINE SURFACE LAYER UNEVEN PAVEMENT - JOINT AREA	
575+65	-	838+00	5TH 64	17,910	-	-	YELLOW CENTERLINE WITH RUMBLE STRIPS	
838+00	-	946+36	5TH 64	-	-	3,010	YELLOW CENTERLINE	
575+65	-	919+50	5TH 64	-	-	68,770	WHITE EDGELINE & CHANNELIZATION	
919+50	-	946+36	5TH 64	-	-	5,380	WHITE EDGELINE	
575+65	-	946+36	5TH 64	1,980	-	-	CULVERT REPLACEMENTS	
TOTALS			43,970	17,910	23,290	68,770	600	200

NOTE: PROVIDE FULL REPLACEMENT OF EXISTING MARKINGS WITH TEMPORARY MARKINGS EDGELANES WHICH DO NOT NEED TO BE MARKED UNTIL FINAL MARKINGS, EXCEPT IN CULVERT REPLACEMENT AREAS BEFORE BEING MILLED

CONSTRUCTION STAKING

STATION	TO	LOCATION	LF	LF	LF	LF	REMARKS	
650.4000	-	650.5500	CONSTRUCTION STAKING	650.6000	CONSTRUCTION STAKING	650.6501	CONSTRUCTION STAKING	650.9911
575+65	-	946+36	5TH 64	2	435	1	36,707	1
TOTALS			2	435	1	36,707	1	

SAWING PAVEMENT

STATION	TO	LOCATION	LF	LF	LF	LF	REMARKS	
690.0150	-	690.0250	SAWING ASPHALT	690.0250	SAWING CONCRETE	-	-	-
575+65	-	946+36	5TH 64	823	5TH 64	440	440	CULVERT REPLACEMENTS
575+65	-	946+36	5TH 64	450	5TH 64	-	-	CURB AND GUTTER
575+65	-	946+36	5TH 64	17	5TH 64	60	60	PRIVATE ENTRANCES
TOTALS			1,290	500				

Addendum No. 02
ID 9160-119-71
Revised Sheet 38
December 9, 2022



Proposal Schedule of Items

Proposal ID: 20221213024 Project(s): 9160-17-71, 9160-19-71

Federal ID(s): WISC 2023108, WISC 2023107

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0242	643.0900 Traffic Control Signs	15,159.000 DAY	_____.	_____.
0244	643.0920 Traffic Control Covering Signs Type II	13.000 EACH	_____.	_____.
0246	643.1000 Traffic Control Signs Fixed Message	214.500 SF	_____.	_____.
0248	643.1050 Traffic Control Signs PCMS	70.000 DAY	_____.	_____.
0250	643.3105 Temporary Marking Line Paint 4-Inch	111,310.000 LF	_____.	_____.
0252	643.3120 Temporary Marking Line Epoxy 4-Inch	51,205.000 LF	_____.	_____.
0254	643.5000 Traffic Control	1.000 EACH	_____.	_____.
0256	645.0120 Geotextile Type HR	390.000 SY	_____.	_____.
0258	646.1020 Marking Line Epoxy 4-Inch	56,585.000 LF	_____.	_____.
0260	646.1040 Marking Line Grooved Wet Ref Epoxy 4-Inch	178,090.000 LF	_____.	_____.
0262	646.3545 Marking Line Grooved Wet Ref Contrast Epoxy 8-Inch	1,080.000 LF	_____.	_____.
0264	646.5220 Marking Symbol Epoxy	1.000 EACH	_____.	_____.
0266	646.8320 Marking Parking Stall Epoxy	375.000 LF	_____.	_____.
0268	646.9000 Marking Removal Line 4-Inch	200.000 LF	_____.	_____.
0270	650.4000 Construction Staking Storm Sewer	3.000 EACH	_____.	_____.
0272	650.5500 Construction Staking Curb Gutter and Curb & Gutter	2,323.000 LF	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20221213024 Project(s): 9160-17-71, 9160-19-71

Federal ID(s): WISC 2023108, WISC 2023107

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0302	SPV.0090 Special 01. Culvert Pipe Reinforced Concrete Horizontal Elliptical Class HE-IV 48x76-In	42.000 LF	_____.	_____.
0304	SPV.0180 Special 01. Removing Distressed Asphaltic Surface Milling	400.000 SY	_____.	_____.
0306	646.4520 Marking Line Same Day Epoxy 4-Inch	3,010.000 LF	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.