

ORDER OF SHEETS

Section No.	1	Title
Section No.	2	Typical Sections and Details
Section No.	3	Estimate of Quantities
Section No.	3	Miscellaneous Quantities
Section No.	4	Right of Way Plat
Section No.	5	Plan and Profile
Section No.	6	Standard Detail Drawings
Section No.	7	Sign Plates
Section No.	8	Structure Plans
Section No.	9	Computer Earthwork Data
Section No.	9	Cross Sections

TOTAL SHEETS = 92

PROJECT LOCATION



STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION

PLAN OF PROPOSED IMPROVEMENT

HAGER CITY - PRESCOTT

BIG RIVER BRIDGE B-47-0042

STH 35

PIERCE COUNTY

STATE PROJECT NUMBER
7180-02-72

STATE PROJECT	FEDERAL PROJECT	
	PROJECT	CONTRACT
7180-02-72	WISC 2024039	1

PROJECT ID: 7180-02-72

COUNTY: PIERCE


DESIGN DESIGNATION 7180-02-72

A.A.D.T.	2024	=	2,680
A.A.D.T.	2044	=	3,310
D.H.V.		=	350
D.D.		=	60/40
T.		=	9.1 %
DESIGN SPEED		=	55 MPH
ESALS		=	720,000

END PROJECT
STA 11+00

STRUCTURE B-47-0042
STA 10+00

BEGIN PROJECT
STA 8+50
Y = 312137.078
X = 434354.838




CONVENTIONAL SYMBOLS

PLAN	
CORPORATE LIMITS	
PROPERTY LINE	
LOT LINE	
LIMITED HIGHWAY EASEMENT	
EXISTING RIGHT OF WAY	
PROPOSED OR NEW R/W LINE	
SLOPE INTERCEPT	
REFERENCE LINE	
EXISTING CULVERT	
PROPOSED CULVERT (Box or Pipe)	
COMBUSTIBLE FLUIDS	
MARSH AREA	
WOODED OR SHRUB AREA	

PROFILE	
GRADE LINE	
ORIGINAL GROUND	
MARSH OR ROCK PROFILE (To be noted as such)	
SPECIAL DITCH	
GRADE ELEVATION	
CULVERT (Profile View)	
UTILITIES	
ELECTRIC	
FIBER OPTIC	
GAS	
SANITARY SEWER	
STORM SEWER	
TELEPHONE	
WATER	
UTILITY PEDESTAL	
POWER POLE	
TELEPHONE POLE	

ROCK	
LABEL	
E	
FO	
G	
SAN	
SS	
T	
W	



TOTAL NET LENGTH OF CENTERLINE = 0.047 MI

HORIZONTAL POSITIONS SHOWN ON THIS PLAN ARE WISCONSIN COORDINATE REFERENCE SYSTEM (WISCRS), PIERCE COUNTY, NAD83 (2011), IN U.S. SURVEY FEET. POSITIONS SHOWN ARE GRID COORDINATES, GRID BEARINGS, AND GRID DISTANCES. GRID DISTANCES ARE THE SAME AS GROUND DISTANCES. ELEVATIONS ARE REFERENCED TO NAVD 88 (2012). GPS DERIVED ELEVATIONS ARE BASED ON GEOID 12A.

ORIGINAL PLANS PREPARED BY




DATE: 7-11-23 *Justin Shavlik*
(Professional Engineer Signature)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

PREPARED BY	
Surveyor	SEH
Designer	SEH
Project Manager	LANCE WILLISTON, P.E.
Regional Examiner	TOU YANG, P.E.
Regional Supervisor	JIM KOENIG, P.E.

APPROVED FOR THE DEPARTMENT
Digitally signed by James Koenig P.E.
DATE: 2023.07.12 08:24:27
Koenig P.E. *James Koenig*
(Signature)

ALIGNMENT TIES



GENERAL NOTES

WHEN THE QUANTITY OF BASE AGGREGATE OR HMA PAVEMENT IS MEASURED FOR PAYMENT BY THE TON, THE DEPTH OR THICKNESS OF THE LAYER SHOWN ON THE PLANS IS APPROXIMATE AND THE ACTUAL THICKNESS WILL DEPEND ON THE DISTRIBUTION OF THE MATERIAL AS DIRECTED BY THE ENGINEER.

THE LOCATION OF EXISTING UTILITY INSTALLATIONS AS SHOWN ON THE PLANS IS APPROXIMATE. THERE MAY BE OTHER UTILITY INSTALLATIONS WITHIN THE PROJECT AREA THAT ARE NOT SHOWN. NOTIFY DIGGERS HOTLINE AND ANY AFFECTED UTILITIES PRIOR TO THE START OF WORK. ANY UTILITY WHICH IS NOT A MEMBER OF DIGGERS HOTLINE MUST BE CONTACT SEPARATELY.

NO TREES OR SHRUBS ARE TO BE REMOVED WITHOUT THE APPROVAL OF THE ENGINEER.

THE EXACT LOCATION OF THE EROSION CONTROL DEVICES SHALL BE DETERMINED IN THE FIELD.

DISTURBED AREAS WITHIN THE RIGHT-OF-WAY, EXCEPT THE AREAS WITHIN THE FINISHED SHOULDER POINTS, ARE TO BE 4-INCH SALVAGED TOPSOILED, FERTILIZED, TEMPORARY SEEDED, SEEDED AND EMATTED.

ALL PAVEMENT DIMENSIONS AND STATIONS ARE SHOWN TO THE EDGE OF PAVEMENT UNLESS NOTED OTHERWISE.

A VERTICAL SAWCUT SHALL BE MADE THROUGH EXISTING PAVEMENTS AT REMOVAL LIMITS.

UTILITY CONTACTS

CENTURYLINK - COMMUNICATIONS
20 S WILSON AVENUE
RICE LAKE WI 54868
TELEPHONE: 715.475.2029 (OFFICE), 715.292.0082 (MOBILE)
ATTENTION: KYLE SCHLAMPP
EMAIL: KYLE.SCHLAMPP@LUMEN.COM

PIERCE PEPIN COOPERATIVE SERVICES - ELECTRIC
W7725 US HWY 10
PO BOX 420
ELLSWORTH WI 54011-0420
TELEPHONE: 715.273.2473 (OFFICE), 715.307.1904 (MOBILE)
ATTENTION: BRAD RISTOW
EMAIL: BRISTOW@PIERCEPEPIN.COOP

SIGNAL TIMING INFORMATION

STRUCTURE #	STAGE #	YELLOW		ALL RED		GREEN		TOTAL SPLIT	
		Φ1	Φ2	Φ1	Φ2	Φ1	Φ2	Φ1	Φ2
		EB	WB	EB	WB	EB	WB	EB	WB
B-47-0042*	ALL	2.8	2.8	29.1	29.1	23.0	23.0	55.0	55.0

*ALL SIGNALS SHALL REST IN RED UNTIL A CALL IS RECEIVED BY THE STOP LINE DETECTION

RUNOFF COEFFICIENT TABLE



	HYDROLOGIC SOIL GROUP											
	A			B			C			D		
	SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)			SLOPE RANGE (PERCENT)		
LAND USE:	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER	0-2	2-6	6 & OVER
ROW CROPS	.08	.16	.22	.12	.20	.27	.15	.24	.33	.19	.28	.38
	.22	.30	.38	.26	.34	.44	.30	.37	.50	.34	.41	.56
MEDIAN STRIP-TURF	.19	.20	.24	.19	.22	.26	.20	.23	.30	.20	.25	.30
	.24	.26	.30	.25	.28	.33	.26	.30	.37	.27	.32	.40
SIDE SLOPE-TURF			.25			.27			.28			.30
			.32			.34			.36			.38
PAVEMENT:												
ASPHALT	.70 - .95											
CONCRETE	.80 - .95											
BRICK	.70 - .80											
DRIVES, WALKS	.75 - .85											
ROOFS	.75 - .95											
GRAVEL ROADS, SHOULDERS	.40 - .60											

TOTAL PROJECT AREA = 2.8 ACRES
TOTAL AREA EXPECTED TO BE DISTURBED BY CONSTRUCTION ACTIVITIES = 0.9 ACRES

WISDOT CONSULTANT PM CONTACT
5400 KING JAMES WAY #200
FITCHBURG, WI 53719
TELEPHONE: 608.663.1218, EXT. 809
ATTENTION: LANCE WILLISTON
EMAIL: LWILLISTON@KLENGINEERING.COM


DESIGN CONTACT
10 NORTH BRIDGE STREET
CHIPPEWA FALLS, WI 54729
TELEPHONE: 715.720.6279
ATTENTION: JUSTIN SHAVLIK
EMAIL: JSHAVLIK@SEHINC.COM


WDNR CONTACT
DNR WEST CENTRAL REGION HQ
1300 WEST CLAIREMONT AVENUE
EAU CLAIRE, WI 54701
TELEPHONE: 715.836.6571
ATTENTION: AMY LESIK
EMAIL: AMYL.LESIK@WISCONSIN.GOV



SUPERELEVATION TABLE

STATION	DESCRIPTION	RIGHT OUTSIDE LANE	RIGHT OUTSIDE SHOULDER
4+00.00'	BEGIN ALIGNMENT	-2.00%	-4.00%
12+86.40'	END NORMAL CROWN	-2.00%	-4.00%
13+37.40'	LEVEL CROWN	0.00%	-4.00%
13+88.40'	REVERSE CROWN	2.00%	-4.00%
14+39.40'	LOW SHOULDER MATCH, BEGIN SHOULDER ROLLOVER	4.00%	-4.00%
15+41.40'	BEGIN FULL SUPER	8.00%	0.00%
16+50.00'	END ALIGNMENT	8.00%	0.00%





NOTES:

STAGE 1 BRIDGE RE-DECK AND APPROACH WORK APPLIED TO NB STH 35 ON B-47-0042. TWO PHASE SIGNALS WITH TEMPORARY VEHICLE DETECTION REQUIRED TO CONTROL STH 35 TRAFFIC (SHOWN). SEE GENERAL NOTES SHEET FOR TEMPORARY SIGNAL TIMING INFORMATION. SEE STRUCTURE PLANS FOR ADDITIONAL TRAFFIC CONTROL TYPICAL SECTION INFORMATION.

STAGE 2 BRIDGE RE-DECK AND APPROACH WORK APPLIED TO SB STH 35 ON B-47-0042. TWO PHASE SIGNALS WITH TEMPORARY VEHICLE DETECTION REQUIRED TO CONTROL STH 35 TRAFFIC. MIRROR STAGE 1 TRAFFIC CONTROL SHOWN FOR STAGE 2. RE-INSTALL CONCRETE BARRIER, CRASH CUSHIONS, TEMPORARY MARKING LINES, AND DRUMS, USING THE SAME TAPER RATES AND LENGTHS SHOWN.

DETAIL OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD DETAILS, STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND WISCONSIN MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (WMUTCD).



USE SDD "TRAFFIC CONTROL, ONE LANE ROAD WITH TEMPORARY SIGNALS", "TRAFFIC CONTROL, WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY", "BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION", "TRAFFIC CONTROL, ADVANCED WIDTH RESTRICTION SIGNING", "CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS".

11' ADVANCED WIDTH RESTRICTION SIGNING REQUIRED FROM CTH E TO CTH EE DURING STAGES 1 & 2 NOT SHOWN. SEE STRUCTURE PLAN CONSTRUCTION STAGING DETAIL FOR ADDITIONAL LANE WIDTH DIMENSIONS.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 100 FEET, (200 FEET DESIRABLE) DISTANCE TO EXISTING SIGNS.



PROJECT NO: 7180-02-72	HWY: STH 35	COUNTY: PIERCE	TRAFFIC CONTROL	SHEET	E
------------------------	-------------	----------------	-----------------	-------	---

Estimate Of Quantities

7180-02-72

Line	Item	Item Description	Unit	Total	Qty
0002	201.0105	Clearing	STA	1.000	1.000
0004	201.0205	Grubbing	STA	1.000	1.000
0006	203.0270	Removing Structure Over Waterway Debris Capture (structure) 01. B-47-0042	EACH	1.000	1.000
0008	204.0165	Removing Guardrail	LF	930.000	930.000
0010	205.0100	Excavation Common	CY	753.000	753.000
0012	206.1001	Excavation for Structures Bridges (structure) 01. B-47-0042	EACH	1.000	1.000
0014	208.0100	Borrow	CY	652.000	652.000
0016	210.1500	Backfill Structure Type A	TON	35.000	35.000
0018	213.0100	Finishing Roadway (project) 01. 7180-02-72	EACH	1.000	1.000
0020	305.0110	Base Aggregate Dense 3/4-Inch	TON	186.000	186.000
0022	305.0120	Base Aggregate Dense 1 1/4-Inch	TON	872.000	872.000
0024	312.0110	Select Crushed Material	TON	50.000	50.000
0026	455.0605	Tack Coat	GAL	69.000	69.000
0028	460.2000	Incentive Density HMA Pavement	DOL	256.000	256.000
0030	460.6244	HMA Pavement 4 MT 58-34 S	TON	394.000	394.000
0032	502.0100	Concrete Masonry Bridges	CY	120.000	120.000
0034	502.3200	Protective Surface Treatment	SY	380.000	380.000
0036	502.3210	Pigmented Surface Sealer	SY	100.000	100.000
0038	502.4205	Adhesive Anchors No. 5 Bar	EACH	136.000	136.000
0040	505.0600	Bar Steel Reinforcement HS Coated Structures	LB	28,520.000	28,520.000
0042	505.0906	Bar Couplers No. 6	EACH	289.000	289.000
0044	506.4000	Steel Diaphragms (structure) 01. B-47-0042	EACH	10.000	10.000
0046	509.1500	Concrete Surface Repair	SF	35.000	35.000
0048	516.0500	Rubberized Membrane Waterproofing	SY	10.000	10.000
0050	601.0588	Concrete Curb & Gutter 4-Inch Sloped 36-Inch Type TBT	LF	148.000	148.000
0052	602.3010	Concrete Surface Drains	CY	5.000	5.000
0054	603.8000	Concrete Barrier Temporary Precast Delivered	LF	650.000	650.000
0056	603.8125	Concrete Barrier Temporary Precast Installed	LF	1,300.000	1,300.000
0058	606.0200	Riprap Medium	CY	8.000	8.000
0060	606.0300	Riprap Heavy	CY	50.000	50.000
0062	614.0150	Anchor Assemblies for Steel Plate Beam Guard	EACH	4.000	4.000
0064	614.0905	Crash Cushions Temporary	EACH	4.000	4.000
0066	614.2300	MGS Guardrail 3	LF	550.000	550.000
0068	614.2500	MGS Thrie Beam Transition	LF	157.600	157.600
0070	614.2610	MGS Guardrail Terminal EAT	EACH	4.000	4.000
0072	618.0100	Maintenance And Repair of Haul Roads (project) 01. 7180-02-72	EACH	1.000	1.000
0074	619.1000	Mobilization	EACH	1.000	1.000
0076	624.0100	Water	MGAL	14.000	14.000
0078	625.0500	Salvaged Topsoil	SY	2,920.000	2,920.000
0080	628.1504	Silt Fence	LF	1,500.000	1,500.000
0082	628.1520	Silt Fence Maintenance	LF	1,500.000	1,500.000
0084	628.1905	Mobilizations Erosion Control	EACH	3.000	3.000
0086	628.1910	Mobilizations Emergency Erosion Control	EACH	3.000	3.000
0088	628.2008	Erosion Mat Urban Class I Type B	SY	3,390.000	3,390.000
0090	629.0210	Fertilizer Type B	CWT	2.000	2.000
0092	630.0120	Seeding Mixture No. 20	LB	89.000	89.000
0094	630.0200	Seeding Temporary	LB	89.000	89.000
0096	630.0500	Seed Water	MGAL	73.000	73.000
0098	638.2102	Moving Signs Type II	EACH	7.000	7.000

Estimate Of Quantities

7180-02-72

Line	Item	Item Description	Unit	Total	Qty
0100	642.5001	Field Office Type B	EACH	1.000	1.000
0102	643.0300	Traffic Control Drums	DAY	8,643.000	8,643.000
0104	643.0420	Traffic Control Barricades Type III	DAY	129.000	129.000
0106	643.0705	Traffic Control Warning Lights Type A	DAY	258.000	258.000
0108	643.0715	Traffic Control Warning Lights Type C	DAY	3,612.000	3,612.000
0110	643.0900	Traffic Control Signs	DAY	5,418.000	5,418.000
0112	643.3180	Temporary Marking Line Removable Tape 6-Inch	LF	3,400.000	3,400.000
0114	643.3850	Temporary Marking Stop Line Removable Tape 18-Inch	LF	48.000	48.000
0116	643.5000	Traffic Control	EACH	1.000	1.000
0118	645.0111	Geotextile Type DF Schedule A	SY	115.000	115.000
0120	645.0120	Geotextile Type HR	SY	90.000	90.000
0122	646.2020	Marking Line Epoxy 6-Inch	LF	3,910.000	3,910.000
0124	646.9000	Marking Removal Line 4-Inch	LF	2,450.000	2,450.000
0126	650.4500	Construction Staking Subgrade	LF	860.000	860.000
0128	650.5000	Construction Staking Base	LF	860.000	860.000
0130	650.5500	Construction Staking Curb Gutter and Curb & Gutter	LF	118.000	118.000
0132	650.9911	Construction Staking Supplemental Control (project) 01. 7180-02-72	EACH	1.000	1.000
0134	650.9920	Construction Staking Slope Stakes	LF	860.000	860.000
0136	661.0101	Temporary Traffic Signals for Bridges (structure) 01. B-47-0042	EACH	1.000	1.000
0138	690.0150	Sawing Asphalt	LF	1,118.000	1,118.000
0140	715.0502	Incentive Strength Concrete Structures	DOL	720.000	720.000
0142	999.2000.S	Installing and Maintaining Bird Deterrent System (station) 01. 10+00	EACH	1.000	1.000
0144	ASP.1T0A	On-the-Job Training Apprentice at \$5.00/HR	HRS	300.000	300.000
0146	ASP.1T0G	On-the-Job Training Graduate at \$5.00/HR	HRS	600.000	600.000
0148	SPV.0060	Special 01. Temporary Vehicle Detection B-47-0042	EACH	1.000	1.000
0150	SPV.0060	Special 02. Foam Void Filling B-47-0042	EACH	1.000	1.000

3

3

CLEARING & GRUBBING

STATION	LOCATION	201.0105	201.0205
		CLEARING	GRUBBING
STH 35			
10+50 - 11+50	LT	1	1
ITEM TOTALS		1	1

REMOVING GUARDRAIL

STATION	LOCATION	204.0165
		SY
STH 35		
STAGE 1		
8+50 - 9+55	RT	96
10+45 - 15+00	RT	357
STAGE 2		
5+50 - 9+55	LT	357
10+45 - 12+00	LT	120
ITEM TOTAL		930

BASE AGGREGATE DENSE

STATION	LOCATION	305.0110	305.0120	624.0100
		3/4-INCH	1 1/4-INCH	WATER
		TON	TON	MGAL
STH 35				
STAGE 1				
8+50 - 9+55	RT	19	137	2
10+45 - 15+00	RT	74	291	4
STAGE 2				
5+50 - 9+55	LT	66	311	4
10+45 - 12+00	LT	27	133	4
ITEM TOTALS		186	872	14

CONCRETE BARRIER TEMPORARY PRECAST

STATION	LOCATION	603.8000	603.8125
		DELIVERED	INSTALLED
		LF	LF
STH 35			
STAGE 1			
6+50 - 13+00	LT & RT	650	650
STAGE 2			
5+50 - 12+00	LT & RT	-	650
ITEM TOTALS		650	1300

EXCAVATION

STATION	LOCATION	205.0100	AVAILABLE	EXPANDED	208.0100
		COMMON	MATERIAL	FILL	BORROW
		CY	CY	CY	CY
STH 35					
STAGE 1					
8+50 - 9+50	RT	119	92	40	-52
10+50 - 15+00	RT	264	190	293	103
STAGE 2					
5+50 - 9+50	LT	266	208	636	428
10+50 - 12+00	LT	104	87	260	173
ITEM TOTALS		753	577	1229	652

CONCRETE SURFACE DRAINS FLUME TYPE

STATION	LOCATION	601.0588	602.3010
		CONCRETE	CONCRETE
		CY	LF
STH 35			
STAGE 1			
8+91 - 9+50	RT	-	59
9+06	RT	2	-
10+63 - 10+78	RT	-	15
STAGE 2			
8+78 - 9+37	LT	-	59
8+94	LT	3	-
10+50 - 10+65	LT	-	15
ITEM TOTALS		5	148

RIPRAP ITEMS

STATION	LOCATION	606.0200	645.0120
		RIPRAP	GEOTEXTILE
		CY	SY
STH 35			
STAGE 1			
9+06	RT	4	10
STAGE 2			
8+94	LT	4	10
ITEM TOTALS		8	20

NOTES:
 1) UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN COMMON EXCAVATION.
 2) AVAILABLE MATERIAL DOES NOT INCLUDE UNUSABLE PAVEMENT EXCAVATION VOLUME.
 3) EXPANSION FACTOR = 1.3

ASPHALTIC PAVEMENT ITEMS

STATION	LOCATION	455.0605	460.6244
		TACK	HMA
		COAT	4 MT 58-34 S
		GAL	TON
STH 35			
STAGE 1			
8+50 - 9+55	RT	14	78
10+45 - 15+00	RT	20	113
STAGE 2			
5+50 - 9+55	LT	24	140
10+45 - 12+00	LT	11	63
ITEM TOTALS		69	394

GUARDRAIL ITEMS

STATION	LOCATION	614.2300	614.2500	614.2610
		MGS	MGS	MGS
		GUARDRAIL	THRIE	GUARDRAIL
		3	TRANSITION	EAT
		LF	LF	EACH
STH 35				
STAGE 1				
8+50 - 9+55	RT	-	39.40	1
10+45 - 15+00	RT	262.5	39.40	1
STAGE 2				
5+50 - 9+55	LT	262.5	39.40	1
10+45 - 12+00	LT	25	39.40	1
ITEM TOTALS		550	157.6	4

PROJECT NO: 7180-02-72

HWY: STH 35

COUNTY: PIERCE

MISCELLANEOUS QUANTITIES

SHEET

E

MAINTENANCE AND REPAIR OF HAUL ROADS (PROJECT)

STATION	618.0100 EACH
STH 35	1
ITEM TOTAL	1

MOBILIZATIONS EROSION CONTROL

STATION	628.1905 EROSION CONTROL EACH	628.1910 EMERGENCY EROSION CONTROL EACH
STH 35	3	3
ITEM TOTALS	3	3

TEMPORARY MARKING

STATION	LOCATION	643.3180 LINE REMOVABLE TAPE 6-INCH (YELLOW)		643.3850 LINE REMOVABLE TAPE 6-INCH (WHITE)		643.3850 STOP LINE REMOVABLE TAPE 18-INCH (WHITE)		REMARKS
		LF	LF	LF	LF	LF	LF	
STH 35								
STAGE 1								
5+00		-	-	-	12			STOP LINE
6+00 - 15+00		-	900	-				EDGE LINE
6+90 - 13+90		-	700	-				EDGE LINE
15+50		-	-	-	12			STOP LINE
STAGE 2								
4+00		-	-	-	12			STOP LINE
4+50 - 13+50		-	900	-				EDGE LINE
5+60 - 12+60		-	700	-				EDGE LINE
14+50		-	-	-	12			STOP LINE
14+50 - 15+50		200	-	-				DOUBLE YELLOW CENTERLINE
ITEM TOTALS			3400		48			

MOBILIZATION

STATION	619.1000 EACH
STH 35	1
ITEM TOTAL	1

PERMANENT SIGNING

STATION	LOCATION	638.2102 MOVING SIGNS TYPE II EACH	REMARKS
STH 35	LT & RT	7	SALVAGE AND REINSTALL ALL EXISTING SIGNS AND POSTS
ITEM TOTAL		7	

SALVAGED TOPSOIL, MULCHING AND SEEDING

STATION	LOCATION	625.0500 SALVAGED TOPSOIL SY	629.0210 FERTILIZER TYPE B CWT	630.0120 SEEDING MIXTURE NO. 20 LB	630.0200 SEEDING TEMPORARY LB	630.0500 SEED WATER MGAL
STH 35						
STAGE 1						
8+50 - 9+55	RT	160	0.1	5	5	4
10+45 - 15+00	RT	840	0.6	27	27	22
STAGE 2						
5+50 - 9+55	LT	1430	1.0	42	42	35
10+45 - 12+00	LT	490	0.3	15	15	12
ITEM TOTALS		2920	2	89	89	73

FIELD OFFICE TYPE B

STATION	642.5001 EACH
STH 35	1
ITEM TOTAL	1

MARKING LINE

STATION	LOCATION	646.2020 EPOXY 6-INCH (YELLOW) (WHITE)		REMARKS
		LF	LF	
STH 35				
4+00 - 15+50		2300	-	DOUBLE YELLOW CENTERLINE
5+50 - 13+90		-	840	SB EDGELINE
5+60 - 14+30		-	770	NB EDGELINE
ITEM TOTALS			3910	

EROSION CONTROL ITEMS

STATION	LOCATION	628.1504 SILT FENCE LF	628.1520 SILT FENCE MAINTENANCE LF	628.2008 URBAN CLASS I TYPE B SY
STH 35				
STAGE 1				
8+50 - 9+55	RT	150	150	240
10+45 - 15+00	RT	525	525	880
STAGE 2				
5+50 - 9+55	LT	455	455	1470
10+45 - 12+00	LT	220	220	500
UNDISTRIBUTED	LT & RT	150	150	300
ITEM TOTALS		1500	1500	3390

TRAFFIC CONTROL

LOCATION	LOCATION	643.0300 TRAFFIC CONTROL DRUMS DAYS	643.0420 TRAFFIC CONTROL BARRICADES TYPE III EACH	643.0705 TRAFFIC CONTROL BARRICADES LIGHTS TYPE A DAYS	643.0715 TRAFFIC CONTROL BARRICADES LIGHTS TYPE C DAYS	643.0900 TRAFFIC CONTROL SIGNS DAYS	643.5000 TRAFFIC CONTROL SIGNS EACH	643.5000 TRAFFIC CONTROL CALENDAR DAYS
STH 35								
STAGE 1	LT & RT	4489	67	67	1	134	2	1876
STAGE 2	LT & RT	4154	67	62	1	124	2	1736
ITEM TOTALS		8643	129	129	2	258	4	3612

**FOR INFORMATION ONLY

3

MARKING REMOVAL

646.9000 LINE 4-INCH			
STATION	LOCATION	LF	REMARKS
STH 35			
STAGE 1			
5+00 - 7+00		400	DOUBLE YELLOW CENTERLINE
12+00 - 15+50		700	DOUBLE YELLOW CENTERLINE
6+90 - 13+90		700	SB WHITE EDGE LINE
STAGE 2			
4+00 - 5+00		200	DOUBLE YELLOW CENTERLINE
5+60 - 8+50		290	NB WHITE EDGE LINE
11+00 - 12+60		160	NB WHITE EDGE LINE
ITEM TOTALS		2450	

SAWING

690.0150 ASPHALT		
STATION	LOCATION	LF
STH 35		
STAGE 1		
8+50 - 9+55	RT	122
10+45 - 15+00	RT	402
STAGE 2		
5+50 - 9+55	LT	422
10+45 - 12+00	LT	172
ITEM TOTALS		1118

3

CONSTRUCTION STAKING

650.5500 650.9911 650.9920						
		650.4500	650.5000	650.5500	650.9911	650.9920
		SUBGRADE	BASE	CURB GUTTER AND	SUPPLEMENTAL CONTROL	SLOPE
STATION	LOCATION	LF	LF	LF	EACH	LF
STH 35						
5+50 - 9+55	LT & RT	405	405	-	1	405
8+78 - 9+37	LT	-	-	59	-	-
8+91 - 9+50	RT	-	-	59	-	-
10+45 - 15+00	LT & RT	455	455	-	-	455
ITEM TOTALS		860	860	118	1	860

INSTALLING AND MAINTAINING BIRD
DETERRENT SYSTEM

999.2000.S	
STATION	EACH
STH 35	1
ITEM TOTAL	1

TEMPORARY SIGNALS




661.0101 SPV.0060.01		
661.0101		SPV.0060.01
TEMPORARY TRAFFIC SIGNALS FOR BRIDGES		TEMPORARY VEHICLE DETECTION
STATION	EACH	EACH
STH 35	1	1
ITEM TOTALS	1	1

CRASH CUSHIONS TEMPORARY

614.0905							
CRASH CUSHION							
LOCATION	LOCATION	TEMPORARY EACH	BACK WIDTH (FT)	OBJECT MARKING PATTERN	CRASH TEST LEVEL	TRAFFIC DIRECTION	CRASH CUSHION SHIELDS
STH 35							
STAGE 1	6+50	1	2	OM-3R (W05-58R)	TL-3	ONE LANE- BIDIRECTIONAL	TEMP CONC BARRIER
STAGE 1	13+00	1	2	OM-3L (W05-58L)	TL-3	ONE LANE- BIDIRECTIONAL	TEMP CONC BARRIER
STAGE 2	5+50	1	2	OM-3R (W05-58R)	TL-3	ONE LANE- BIDIRECTIONAL	TEMP CONC BARRIER
STAGE 2	12+00	1	2	OM-3L (W05-58L)	TL-3	ONE LANE- BIDIRECTIONAL	TEMP CONC BARRIER
ITEM TOTAL		4					


BENCHMARKS			
NO.	STATION/OFFSET	ELEV.	DESCRIPTION
1	7+43, 41' RT	766.71	SPIKE IN 18-INCH ELM
2	11+09, 33' LT	767.27	SPIKE IN 22-INCH ELM
3	10+62, 17' RT	771.40	ALUM BRIDGE MON

MGS GUARDRAIL EAT POST 1 RAIL FACE LOCATIONS
 STA 5+85, 18' LT, NO FLARE
 STA 8+60, 20' RT, 2' FLARE
 STA 11+66, 18' LT, NO FLARE
 STA 14+15, 18' RT, NO FLARE



EARTHWORK SUMMARY
 STAGE 1 (RT)

CUT	383 CY
AVAILABLE	282 CY
FILL	256 CY
FILL AT 1.3 EXP	333 CY
BORROW	51 CY




EARTHWORK SUMMARY
 STAGE 2 (LT)


CUT	370 CY
AVAILABLE	295 CY
FILL	689 CY
FILL AT 1.3 EXP	896 CY
BORROW	601 CY

Standard Detail Drawing List


08D01-23A	CONCRETE CURB & GUTTER
08D01-23B	CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS
08D02-08A	CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES
08D02-08B	CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES
08D02-08C	CONCRETE SURFACE DRAINS FLUME TYPE AT STRUCTURES
08E09-06	SILT FENCE
09G02-05A	BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION
09G02-05B	BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION
09G02-05C	BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION
12A03-10	NAME PLATE (STRUCTURES)
13C19-03	HMA LONGITUDINAL JOINTS
14B07-16A	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16B	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16C	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16D	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16E	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16F	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16G	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16H	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16I	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16J	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16K	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16L	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16M	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B07-16N	CONCRETE BARRIER TEMPORARY PRECAST, 12' -6"
14B08-02A	CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS
14B08-02B	CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS
14B08-02C	CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS
14B08-02D	CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS
14B08-02E	CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS
14B42-07A	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07B	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07C	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B42-07D	MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL
14B44-04A	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04B	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B44-04C	MIDWEST GUARDRAIL SYSTEM ENERGY ABSORBING TERMINAL (MGS)
14B45-05B	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05C	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05D	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05E	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05F	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05G	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05H	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05I	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05J	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05K	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
14B45-05L	MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)
15C02-09F	ADVANCED WIDTH RESTRICTION SIGNING
15C08-23A	PERMANENT LONGITUDINAL PAVEMENT MARKINGS
15C08-23B	TEMPORARY LONGITUDINAL PAVEMENT MARKING
15C11-10B	CHANNELIZING DEVICES DRUMS, CONES, BARRICADES AND VERTICAL PANELS
15C12-09A	TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION
15D12-11B	TRAFFIC CONTROL, LANE CLOSURE, SPEED REDUCTION
15D28-04	TRAFFIC CONTROL, WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY
15D33-09	TRAFFIC CONTROL, ONE LANE ROAD WITH TEMPORARY SIGNALS




TYPES A¹ & D




6" SLOPED CURB TYPES G¹ & J




4" SLOPED CURB TYPES G¹ & J




TYPES K¹ & L
(OPTIONAL CURB SHAPE)




TYPES K¹ & L
CONCRETE CURB AND GUTTER 30"




TYPES A¹ & D
CONCRETE CURB AND GUTTER 18"



6" SLOPED CURB TYPES A¹ & D




4" SLOPED CURB TYPES A¹ & D
CONCRETE CURB AND GUTTER 36"



4" SLOPED CURB TYPES R¹ & T


TBT & TBTT	X
30"	22"
36"	28"



TYPES TBT & TBTT¹
CONCRETE CURB AND GUTTER


PAVEMENT THICKNESS AND MAXIMUM CONCRETE PANEL WIDTH TABLE

PAVEMENT THICKNESS	MAXIMUM PANEL WIDTH
LESS THAN 10"	12'
10" & ABOVE	15'



PARTIAL SECTION OF PAVEMENT* WITH INTEGRAL CURB AND GUTTER

* BIKE LANE IS NOT SHOWN



REVERSE SLOPE GUTTER⁶
(TYPICAL FOR ALL CURB & GUTTER TYPES)

GENERAL NOTES


DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.


INTEGRAL CURB AND GUTTER SHALL CONFORM TO THE DETAILS SHOWN FOR CONCRETE CURB AND GUTTER INCLUDING THE TRANSVERSE GUTTER SLOPE.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.

- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ③ USE 8" MINIMUM GUTTER THICKNESS WHEN USED WITH AN ADJACENT CONCRETE TRUCK APRON PLACED BEHIND BACK OF CURB.
- ④ THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 8" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑤ UNLESS OTHERWISE NOTED, FOR STAKING PURPOSES THE FACE OF CURB IS 6" FROM THE BACK OF CURB.
- ⑥ WHEN REVERSE SLOPE GUTTER IS REQUIRED, THE LOCATION(S) WILL BE SHOWN ELSEWHERE IN THE PLAN.
- ⑦ USE 4% GUTTER CROSS SLOPE UNLESS OTHERWISE NOTED IN THE PLANS.
- ⑧ INCLUDE LONGITUDINAL JOINT AND TIE BARS ALONG LANE EDGE WHEN CONCRETE PANEL WIDTH EXCEEDS THE MAXIMUM WIDTH PER TABLE BELOW. LONGITUDINAL JOINT(S) ARE NOT ALLOWED WITHIN TRAFFIC LANES AND BIKE LANES. LONGITUDINAL JOINT MAY BE SAWED.
- ⑨ CONCRETE CURB AND GUTTER 4-INCH SLOPED 30-INCH TYPE "R" AND "T" = 17 INCHES
CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE "R" AND "T" = 23 INCHES



END SECTION CURB AND GUTTER



DETAIL OF CURB AND GUTTER AT INLETS

(TYPICAL H INLET COVER SHOWN)


GENERAL NOTES

DETAILS OF CONSTRUCTION AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.


PAVEMENT TIES AND TIE BARS SHALL BE EPOXY COATED IN CONFORMANCE WITH SUBSECTION 505.2.6.2 OF THE STANDARD SPECIFICATIONS.

UNLESS OTHERWISE SHOWN ON THE TYPICAL CROSS SECTIONS, THE BASE AGGREGATE AND COMMON EXCAVATION LIMITS ARE 2' - 0" BEHIND THE BACK OF CURBS.


- ① TIE BARS ARE REQUIRED FOR CURB AND GUTTERS TYPES A, G, K, R, AND TBTT.
- ② THE BOTTOM OF CURB AND GUTTER MAY BE CONSTRUCTED EITHER LEVEL OR PARALLEL TO THE SLOPE OF THE SUBGRADE OR BASE AGGREGATE PROVIDED A 6" MINIMUM GUTTER THICKNESS IS MAINTAINED.
- ⑩ REFER TO SDD 08D18 AND 08D19 FOR ADDITIONAL DRIVEWAY ENTRANCE CURB DETAILS.
- ⑪ PLACE 1" THICK EXPANSION JOINT MATERIAL BETWEEN VERTICAL FACE CURB TYPES EXTENDING FROM THE TOP OF CURB TO 1 INCH BELOW THE ADJOINING CONCRETE SURFACE. RIGID CONCRETE STRUCTURES INCLUDE RAISED CONCRETE MEDIANS, CONCRETE SAFETY ISLANDS, SPLITTER ISLANDS, OR LOCATIONS IDENTIFIED ON THE PLANS.




TYPES A^① & D




**TYPES G^① & J
CONCRETE CURB**




TYPICAL TIE BAR LOCATION^①




PLAN VIEW



**DRIVEWAY ENTRANCE CURB^⑩
(WHEN DIRECTED BY THE ENGINEER)**



EXPANSION JOINT DETAIL FOR VERTICAL CURB ABUTTING A RIGID STRUCTURE^⑪



**SECTION A - A
TIE BARS DRILLED INTO EXISTING PAVEMENT**

CONCRETE CURB, TIES AND CURB AND GUTTER APPLICATIONS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE May 2023 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT ENGINEER

FHWA



GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

- ① USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ② NO. 4 X 2' - 0" TIE BARS SPACED AT 12" C-C TO BE PLACED BY BRIDGE CONTRACTOR OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PAVED CONCRETE SHOULDER (SDD 13A03) OR CONCRETE DRAINAGE SLAB.
- ④ CONCRETE PAVEMENT APPROACH SLAB (SHOWN) OR STRUCTURE APPROACH SLAB AND CONCRETE PAVEMENT APPROACH SLAB. SEE SDD 13B02.
- ⑤ PAVED CONCRETE SHOULDER (SDD 13A03) OR ASPHALT SHOULDER.

- ⑥ CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE TBT OR TBTT. USE TYPE TBTT CURB WITH NO. 4 X 2' - 0" TIE BARS SPACED AT 3' - 0" C-C ONLY WHEN ADJACENT TO CONCRETE PAVEMENTS.
- ⑦ PLACE FLUME BEFORE MSG THRIE BEAM TRANSITION POST 1 (SEE SDD 14B45)
- ⑧ CENTER FLUME BETWEEN POSTS. 6-INCH MINIMUM SEPARATION FROM OUTSIDE EDGE OF FLUME TO POSTS.
- ⑨ MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑩ SEE ROADWAY PLANS FOR FLUME LOCATION.
- ⑪ START CURB AND GUTTER TRANSITION OR END SECTION.
- ⑫ DEPRESS FLOW LINE (SEE DETAIL)



**CONCRETE SURFACE
DRAINS FLUME TYPE
AT STRUCTURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

SDD 08D02 - 08a


SDD 08D02 - 08a




SECTION A - A




SECTION G - G




SECTION H - H



SECTION I - I



PLAN VIEW PERPENDICULAR FLUME



PLAN VIEW SKEWED FLUME

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.

- ① USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ② NO. 4 X 2'-0" TIE BARS SPACED AT 12" C-C TO BE PLACED BY BRIDGE CONTRACTOR OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PAVED CONCRETE SHOULDER (SDD 13A03) OR CONCRETE DRAINAGE SLAB.
- ④ CONCRETE PAVEMENT APPROACH SLAB (SHOWN) OR STRUCTURE APPROACH SLAB AND CONCRETE PAVEMENT APPROACH SLAB. SEE SDD 13B02 AND STRUCTURE PLANS.
- ⑤ PAVED CONCRETE SHOULDER (SDD 13A03) OR ASPHALT SHOULDER.
- ⑥ CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE TBT OR TBTT. USE TYPE TBTT CURB WITH NO. 4 X 2'-0" TIE BARS SPACED AT 3'-0" C-C ONLY WHEN ADJACENT TO CONCRETE PAVEMENTS.

- ⑦ PLACE FLUME BEFORE MSG THRIE BEAM TRANSITION POST 1 (SEE SDD 14B45)
- ⑧ CENTER FLUME BETWEEN POSTS. 6-INCH MINIMUM SEPARATION FROM OUTSIDE EDGE OF FLUME TO POSTS.
- ⑨ MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C -C.
- ⑩ SEE ROADWAY PLANS FOR FLUME LOCATION.
- ⑪ START CURB AND GUTTER TRANSITION OR END SECTION.
- ⑫ DEPRESS FLOW LINE (SEE DETAIL)
- ⑬ MEDIUM RIPRAP UNLESS OTHERWISE SPECIFIED.
- ⑭ LIMITS OF ADDITIONAL RIPRAP WHEN SPECIAL DITCH AS REQUIRED.
- ⑮ GEOTEXTILE TYPE HR.

6


6

SDD 08D02 - 08b


SDD 08D02 - 08b

**CONCRETE SURFACE
DRAINS FLUME TYPE
AT STRUCTURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



**CURB AND GUTTER TRANSITION SECTION
CONCRETE CURB AND GUTTER 4-INCH SLOPED
36 INCH TYPE TBT OR TBTT**



**CURB AND GUTTER END SECTION
CONCRETE CURB AND GUTTER 4-INCH SLOPED
36 INCH TYPE TBT OR TBTT**




**CURB AND GUTTER FLOW LINE DEPRESSION
AT FLUMES CONCRETE CURB AND GUTTER
4-INCH SLOPED 36 INCH TYPE TBT OR TBTT**

GENERAL NOTES


DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND THE APPLICABLE SPECIAL PROVISIONS.

ALL STEEL REINFORCEMENT SHALL BE EMBEDDED 2 INCHES CLEAR UNLESS OTHERWISE SHOWN OR NOTED.


- ① USE A JOINT SEALANT CONFORMING TO STANDARD SPECIFICATION 415.2.6.
- ② NO. 4 X 2' - 0" TIE BARS SPACED AT 12" C-C TO BE PLACED BY BRIDGE CONTRACTOR OR DRILLED TIE BARS PLACED AS DIRECTED BY THE ENGINEER.
- ③ PAVED CONCRETE SHOULDER (SDD 13A03) OR CONCRETE DRAINAGE SLAB.
- ④ CONCRETE PAVEMENT APPROACH SLAB (SHOWN) OR STRUCTURE APPROACH SLAB AND CONCRETE PAVEMENT APPROACH SLAB. SEE SDD 13B02 AND STRUCTURE PLANS.
- ⑤ PAVED CONCRETE SHOULDER (SDD 13A03) OR ASPHALT SHOULDER.
- ⑥ CONCRETE CURB AND GUTTER 4-INCH SLOPED 36-INCH TYPE TBT OR TBTT. USE TYPE TBTT CURB WITH NO. 4 X 2' - 0" TIE BARS SPACED AT 3' - 0" C-C ONLY WHEN ADJACENT TO CONCRETE PAVEMENTS.
- ⑦ PLACE FLUME BEFORE MSG THRIE BEAM TRANSITION POST 1 (SEE SDD 14B45)
- ⑧ CENTER FLUME BETWEEN POSTS. 6-INCH MINIMUM SEPARATION FROM OUTSIDE EDGE OF FLUME TO POSTS.
- ⑨ MINIMUM REINFORCEMENT SHALL BE 4" X 4" - W3.0 X W3.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑩ SEE ROADWAY PLANS FOR FLUME LOCATION.
- ⑪ START CURB AND GUTTER TRANSITION OR END SECTION.
- ⑫ DEPRESS FLOW LINE (SEE DETAIL)
- ⑬ MEDIUM RIPRAP UNLESS OTHERWISE SPECIFIED.
- ⑭ LIMITS OF ADDITIONAL RIPRAP WHEN SPECIAL DITCH IS REQUIRED.
- ⑮ GEOTEXTILE TYPE HR.
- ⑯ MINIMUM REINFORCEMENT SHALL BE 6" X 6" - W4.0 X W4.0 OR NO. 3 BARS LONGITUDINAL AND TRANSVERSE SPACING 12" C-C.
- ⑰ MSG THRIE BEAM TRANSITION POST 1. SEE SDD 14B45 FOR ADDITIONAL CONSTRUCTION DETAILS AND ACCEPTABLE MATERIALS.
- ⑱ MAINTAIN WIDTH, THICKNESS AND CROSS SLOPE OF ADJACENT TYPE TBT OR TBTT CURB. SEE NOTE 6 FOR TIE BAR SPACING.
- ⑲ ALIGN FACE OF POST BLOCK WITH FLOW LINE.
- ⑳ MAINTAIN FLOW LINE AT EDGE OF PAVEMENT/FACE OF BEAM GUARD AS APPLICABLE.
- ㉑ DO NOT CONSTRUCT AN EXPANSION JOINT OR INSTALL DOWEL BARS WHEN ABUTTING HMA PAVEMENTS.




SECTION B-B




**SECTION C - C
JOINT DETAIL FOR BRIDGE WITH STRUCTURAL
APPROACH SLAB AND CONCRETE APPROACH SLAB**




**SECTION C - C
JOINT DETAIL FOR BRIDGE APPROACH
WITH CONCRETE SHOULDERS**



SECTION D - D



SECTION E - E



SECTION F - F

6

6

SDD08D02 - 08C


SDD08D02 - 08C

**CONCRETE SURFACE
DRAINS FLUME TYPE
AT STRUCTURES**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
ENGINEER

FHWA



PLAN VIEW
TYPICAL APPLICATION OF SILT FENCE




SITUATION 1 SITUATION 2
PLAN VIEW
SILT FENCE AT MEDIAN SURFACE DRAINS

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS AND APPLICABLE SPECIAL PROVISIONS.

- ① HORIZONTAL BRACE REQUIRED WITH 2" X 4" WOODEN FRAME OR EQUIVALENT AT TOP OF POSTS.
- ② FOR MANUAL INSTALLATIONS THE TRENCH SHALL BE A MINIMUM OF 4" WIDE & 6" DEEP TO BURY AND ANCHOR THE GEOTEXTILE FABRIC. FOLD MATERIAL TO FIT TRENCH AND BACKFILL & COMPACT TRENCH WITH EXCAVATED SOIL.
- ③ WOOD POSTS SHALL BE A MINIMUM SIZE OF 1 1/8" X 1 1/8" OF OAK OR HICKORY.
- ④ SILT FENCE TO EXTEND ACROSS THE TOP OF THE PIPE.
- ⑤ CONSTRUCT SILT FENCE FROM A CONTINUOUS ROLL IF POSSIBLE BY CUTTING LENGTHS TO AVOID JOINTS. IF A JOINT IS NECESSARY USE ONE OF THE FOLLOWING TWO METHODS; A) OVERLAP THE END POSTS AND TWIST, OR ROTATE, AT LEAST 180 DEGREES, B) HOOK THE END OF EACH SILT FENCE LENGTH.




TRENCH DETAIL


NOTE: ADDITIONAL POST DEPTH OR TIE BACKS MAY BE REQUIRED IN UNSTABLE SOILS



SILT FENCE



JOINING TWO LENGTHS OF SILT FENCE ⑤




SILT FENCE TIE BACK
(WHEN REQUIRED BY THE ENGINEER)

SILT FENCE

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
4-29-05 /S/ Beth Canestra
DATE CHIEF ROADWAY DEVELOPMENT ENGINEER
FHWA



TYPICAL BRIDGE TEMPORARY TRAFFIC SIGNAL LOCATION

LEGEND

- WOOD POLE (NON-BREAKAWAY)
- WOOD POST (BREAKAWAY)
- - - SIGNAL CABLE
- SIGNAL CABLE W/MESSENGER
- ➔ DIRECTION OF TRAFFIC
- LED TRAFFIC SIGNAL WITH BACKPLATE
3-12"

GENERAL NOTES

DETAILS OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

POLE MOUNTED TRAFFIC SIGNAL CONTROL CABINET MAY BE MOUNTED ON THE SERVICE POLE IF THE ELECTRICAL UTILITY ALLOWS THE INSTALLATION.

WHEN UTILITY POLES ARE USED TO SPAN THE TEMPORARY OVERHEAD CABLE, WRITTEN PERMISSION MUST BE OBTAINED FROM THE OWNER OF THE POLES AND GIVEN TO THE PROJECT MANAGER. ALL PERTINENT UTILITY AND CODE CLEARANCES SHALL BE MAINTAINED.

WOOD POLES (NON-BREAKAWAY) SHALL BE NO CLOSER TO EDGE OF PAVEMENT THAN OFFSET DISTANCE CHART ALLOWS OR 4 FEET BEHIND PROTECTIVE BARRIER (BEAM GUARD, ETC.).


WOOD POSTS (BREAKAWAY) SHALL BE NO CLOSER THAN 2 FEET OUTSIDE OF SHOULDER.

VERTICAL CLEARANCE ETC. PER NEC.


TRAFFIC SIGNAL FACES SHALL BE TYPICALLY PLACED 12 FEET FROM EDGE OF PAVEMENT.

EACH TRAFFIC SIGNAL SHALL HAVE A BACKPLATE.


SIGNING, PAVEMENT MARKING AND LANE CONTROL REQUIREMENTS SHALL CONFORM TO STANDARD DETAIL DRAWING 15D33.



TYPICAL DROP TO TRAFFIC SIGNAL FACE



POLE MOUNT CABINET INSTALLATION



GROUND MOUNT CABINET INSTALLATION

MINIMUM POLE LENGTHS	CLASS	POLE BURIAL DEPTHS
25'	V	5'
30'	V	6'
35'	IV	7'
40'	IV	8'
45'	IV	9'

OFFSET DISTANCES FOR TEMPORARY NON-BREAKAWAY POLES	
SPEED LIMIT	OFFSET DISTANCE*
GREATER THAN 45 MPH	18 FT
45 MPH OR LESS	12 FT
45 MPH OR LESS W/CURBS	2 FT

* NOTE: OFFSET MEASURED FROM OUTER EDGE OF OUTSIDE THRU LANE.

BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
March 2018 /S/ Ahmet Demirelek
DATE ROADWAY STANDARDS DEVELOPMENT ENGINEER

FHWA

6


6

SDD09G02 - 05a

SDD09G02 - 05a

GENERAL NOTES

USE 3/4" DRILL IN WOOD POLE TO PROVIDE FOR 5/8" BOLTS.



SPAN WIRE POLE

GUY POLE

TYPICAL DEAD-ENDINGS OR GUYING


BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED June 2015 DATE	/S/ Ahmet Demerbilek ROADWAY STANDARDS DEVELOPMENT ENGINEER
<small>FHWA</small>	

6

6

SDD09G02 - 05b

SDD09G02 - 05b




TRAILER MOUNTED TRAFFIC SIGNAL

GENERAL NOTES






DETAIL OF CONSTRUCTION, MATERIALS AND WORKMANSHIP NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE CONTRACT.

SIGNING, PAVEMENT MARKING AND LANE CONTROL REQUIREMENTS SHALL CONFORM TO STANDARD DETAIL DRAWING 15D33.



TYPICAL TRAILER MOUNTED TRAFFIC SIGNAL LOCATION

LEGEND


-  POST MOUNTED SIGN
-  TEMPORARY PRECAST CONCRETE BARRIER
-  TRAILER MOUNTED TRAFFIC SIGNAL
-  REMOVE PAVEMENT MARKINGS
-  DIRECTION OF TRAFFIC

BRIDGE TEMPORARY TRAFFIC SIGNAL INSTALLATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June 2015 /S/ Ahmet Demerbilek
DATE ROADWAY STANDARDS DEVELOPMENT
ENGINEER

FHWA




TYPICAL NAME PLATE
(BRIDGES, CULVERTS, AND RETAINING WALLS)

GENERAL NOTES


NAME PLATES TO BE INSTALLED ON BRIDGES, CULVERTS, AND RETAINING WALLS SHALL CONFORM TO THE REQUIREMENTS OF SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS.

THE BRIDGE NUMBER AND YEAR BUILT SHOWN ON THIS DRAWING ARE EXAMPLES ONLY. SEE CONSTRUCTION PLANS FOR INDIVIDUAL NUMBERING AND YEAR BUILT.

- ① EPOXY RESIN SHALL BE FROM AN APPROVED MANUFACTURER AND USED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.
- ② REHABILITATION OF AN EXISTING STRUCTURE SHOULD USE THE DATE OF ORIGINAL STRUCTURE CONSTRUCTION.



SECTION A-A



ALTERNATE LUG


6

6

FOR MULTI-UNIT STRUCTURES
LINE 3 ABOVE SHALL READ


B = BRIDGE
C = CULVERT
R = RETAINING WALL

UNIT NO. FOR MULTIPLE
UNIT BRIDGE



**NUMBERING DESIGNATION
MULTI-UNIT STRUCTURES**

- ① ADHERE ANCHOR LUG TO PRECAST RETAINING WALL WITH EPOXY RESIN.




ALTERNATE LUG
(FOR ATTACHMENT TO PRECAST STRUCTURES)


S.D.D. 12 A 3-10

S.D.D. 12 A 3-10


NAME PLATE (STRUCTURES)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED DATE 3/26/10	/S/ Scot Becker CHIEF STRUCTURAL DEVELOPMENT ENGINEER
FHWA	



**TYPICAL PAVEMENT CROSS SECTION
NOTCHED WEDGE JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT**



**TYPICAL PAVEMENT CROSS SECTION
VERTICAL JOINT (MILLED)**

GENERAL NOTES


IN ADDITION TO THE DETAILS PROVIDED IN THIS DRAWING, CONFORM TO STANDARD SPECIFICATION 450.3.2.8 FOR WHEN A NOTCHED WEDGE JOINT IS REQUIRED AND FOR GENERAL JOINT CONSTRUCTION REQUIREMENTS.

FOR ALL LONGITUDINAL JOINTS, ENSURE THE PAVER SCREED OVERLAPS THE PREVIOUSLY PLACED PAVEMENT BY $1" \pm 0.5"$ AND THE HOT SIDE OF THE JOINT REMAINS HIGHER THAN THE COLD SIDE BY APPROXIMATELY 0.1" AFTER FINAL COMPACTION. (IT WILL BE FLUSH WHEN PAVING IN ECHELON.)

ONLY REMOVE THE LONGITUDINAL NOTCHED WEDGE JOINT FOR SMA PAVEMENT OR AS DIRECTED BY THE ENGINEER TO ADDRESS SPECIFIC LENGTHS OF JOINT DAMAGED BY TRAFFIC.

WHEN MILLING BACK OR REMOVING ANY LONGITUDINAL JOINT, LIMIT THE MATERIAL REMOVED TO 2" FROM THE TOP NOTCH OR FROM THE VERTICAL JOINT EDGE ON THE COLD SIDE OF THE JOINT.

USE LONGITUDINAL MILLED JOINT AS PLANS SHOW OR THE AS THE ENGINEER DIRECTS.



OVERLAP DETAIL (TYPICAL)


6

6


SDD 13C19 - 03

SDD 13C19 - 03

HMA LONGITUDINAL JOINTS	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED November 2020 DATE	/S/ Steven Hefel HMA PAVEMENT ENGINEER
FHWA	



CROSS SECTION




PROFILE VIEW

GENERAL NOTES


PLACE BARRIER ON PAVED SURFACE. BEFORE PLACEMENT OF TEMPORARY BARRIER, REMOVE ALL LOOSE MATERIAL FROM PAVED SURFACE.

LOOP BARS C1, C2 AND C3 ARE NOT FOR PLACEMENT OR MOVEMENT OF BARRIER.


- (100) PERMANENTLY FORM INTO ONE END OF BARRIER THE FOLLOWING INFORMATION:
A. TYPE OF BARRIER: WI-CBTP
B. MANUFACTURER
C. DATE OF MANUFACTURE (MONTH AND YEAR)
- (101) 1" OPTIONAL CHAMFER
- (102) SEE LIFTING SLOT DETAIL
- (103) SEE ANCHOR BLOCK DETAIL
- (104) 1 3/4" MIN. CLEAR COVER
- (105) 2" MIN. CLEAR COVER
- (106) 1" MIN. CLEAR COVER
- (107) ± 1/8" MEASURED FROM FACE OF CONCRETE BARRIER TO OUTSIDE OF LOOP BAR (TYP.)
- (108) USE DELINEATORS CONFORMING TO SECTION 633 OF THE STANDARD SPECIFICATIONS. CONTRACTOR MY USE ALTERNATE SHAPES AND HOUSING. INSTALL DELINEATORS ACCORDING TO MANUFACTURERS INSTRUCTION. INSTALL YELLOW REFLECTORS WHEN BARRIER IS LOCATED LEFT OF TRAFFIC AND WHITE WHEN BARRIER IS LOCATED RIGHT OF TRAFFIC. SPACE DELINEATORS A MAXIMUM OF 25 FEET APART, PROVIDE TO MOUNTED DELINEATORS IN ADDITION TO SIDE MOUNTED DELINEATORS ON BARRIER INSTALLATIONS LOCATED ON A CURVED ALIGNMENT LONGER THAT 200 FEET AND ON BARRIERS USED TO SEPARATE OPPOSING TRAFFIC.






ANCHOR BLOCK DETAIL



**PLAN VIEW
TEMPORARY BARRIER**




**LIFTING SLOT DETAIL
(TYP.)**




**PROFILE VIEW
TEMPORARY BARRIER REINFORCEMENT**

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION






B4 BAR DETAIL



B5 BAR DETAIL





**PROFILE VIEW
LOOP BAR ASSEMBLY**



C BAR DETAILS






**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




GENERAL NOTES

- (300) SET WITH 3 5/8" WOOD BLOCK.
- (301) HOLE IS OPTIONAL.
- (302) CONNECTOR PIN ASSEMBLY.
- (303) CONCRETE PAVEMENT, APPROACH SLAB, OR DECK.
- (304) CONCRETE DECK.
- (305) DO NOT USE ON CONCRETE BRIDGE DECK WITH ASPHALT OVERLAY OR CONCRETE PAVEMENT WITH ASPHALT OVERLAY.
- (306) MINIMUM OF 2" OF ASPHALT.
- (307) ASPHALT ANCHOR PIN ASSEMBLY
- (308) IF DRILLING A PILOT HOLE, THE MAX. DIA. OF THE HOLE IS 3/4"
- (309) WHEN THERE IS ASPHALT OVERLAYING CONCRETE PAVEMENT, A 1 5/8" DIA. PILOT HOLE CAN BE DRILLED INTO THE OVERLAY AND CONCRETE. IF NEEDED DRILL A 3/4" PILOT HOLE IN BASE COURSE.




**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




PLAN VIEW
TRANSITION FROM FREE STANDING TO ANCHORED BARRIER




PROFILE VIEW
ANCHORED BARRIER NEAR EXPANSION JOINT




CROSS SECTION
FREE STANDING BARRIER



CROSS SECTION
ANCHORED BARRIER FOR OBJECTS ABOVE THE GRADE LINE AND NEAR THE BARRIER



CROSS SECTION
ANCHORED BARRIER NEAR VERTICAL DROP OFF



CROSS SECTION
ANCHORED BARRIER NEAR A SLOPE

GENERAL NOTES


- (400) NO SINGLE CONCRETE BARRIER SECTION SHALL BE ANCHORED TO BOTH THE BRIDGE DECK AND THE APPROACH SLAB. ALL ANCHOR BOLT LOCATIONS SHALL BE ANCHORED TO THE DECK IN ACCORDANCE WITH THE DETAIL. NO MORE THAN ONE ANCHOR BOLT SHALL BE ELIMINATED FROM A BARRIER SECTION WHEN SPANNING AN EXPANSION JOINT.
- (401) CONCRETE DECK
- (402) CONCRETE DECK OR APPROACH SLAB.
- (403) EXPANSION JOINT
- (404) ADHESIVE ANCHOR SHOWN. SEE ANCHOR DETAILS.
- (405) ANCHORED TEMPORARY BARRIER
- (406) TRANSITION FROM ANCHORED TEMPORARY BARRIER TO FREE STANDING
- (407) FREE STANDING BARRIER
- (408) REMOVE ALL ANCHORS WHEN NO LONGER NEEDED. FILL CONCRETE PAVEMENTS, DECKS AND APPROACH SLABS WITH NON-SHRINK COMMERCIAL GROUT FROM THE APPROVED PRODUCT LIST. FILL ASPHALT PAVEMENTS WITH ASTM D6690 TYPE II RUBBERIZED CRACK FILLER.
- (409) TRAFFIC SIDE
- (410) NON-TRAFFIC SIDE
- (411) ANCHOR LOCATION. SEE ANCHORING DETAILS.
- (412) WORK AREA
- (413) AREA FREE OF OBJECTS AND WORKERS
- (414) GRADE LINE
- (415) EXTENDED GRADE LINE
- (416) ANCHORED TEMPORARY BARRIER. SEE BOLT THROUGH DECK, REMOVABLE ADHESIVE ANCHOR, OR AN ASPHALT ANCHOR ROD DETAILS FOR MORE INFORMATION. ASPHALT ANCHOR ROD SHOWN.
- (417) WHEN OBJECTS EXTEND ABOVE THE GRADE. A MINIMUM OF 1 FOOT IS REQUIRED FROM BACK OF BARRIER TO OBJECT.
- (418) OBJECTS ARE NOT TO BE PLACED ON, MOUNTED TO, OR ALLOWED TO LEAN AGAINST THE BARRIER WITHOUT WRITTEN PERMISSION OF THE PROJECT ENGINEER.
- (419) DEPTHS OF 3 FEET OR MORE.
- (420) Y = 6.5'
- (421) OFFSET FROM BACK OF BARRIER EDGE:
 CONCRETE PAVEMENT 0.5'
 ASPHALT 0.5'
- (422) POSTED SPEED (MPH):
 45 OR GREATER 4.0'
 40 OR LOWER 2.0'

CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"


STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION

GENERAL NOTES


- (500) EXISTING RIGID BARRIERS (VARIES)
- (501) TEMPORARY BARRIER
- (502) SEE OTHER DETAIL ON HOW TO ANCHOR TEMPORARY BARRIER (BARRIER ASPHALT ANCHOR SHOWN).
- (503) ANCHORS ARE REQUIRED ON BOTH SIDE OF THE TEMPORARY BARRIER.
- (504) NESTED RAILS ARE REQUIRED ON BOTH SIDES OF THE TEMPORARY BARRIER FOR ALL INSTALLATIONS.
- (505) TRAFFIC TRAVELS FROM PERMANENT BARRIER TO TEMPORARY BARRIER.
- (506) TRAFFIC TRAVELS FROM TEMPORARY BARRIER TO PERMANENT BARRIER.
- (507) VERTICAL BARRIER
- (508) SAFETY SHAPE BARRIER
- (509) SINGLE SLOPE BARRIER
- (510) CAP END PLATE PLACED FLUSH WITH UPSTREAM END OF RIGID BARRIER.
- (511) BENT THRIE BEAM TO FIT.
- (512) THRIE BEAM PIECES ARE OFFSET 15 1/4" TO PREVENT INTERFERENCE FROM THE ANCHORS ON OPPOSING SIDES.
- (513) TWO (2) P1, P2 AND P3 ARE REQUIRED
- (514) FIVE (5) N1, N2 AND N3 ARE REQUIRED
- (515) TWO (2) R1, R2 AND R3 ARE REQUIRED
- (516) CUT WOOD BLOCK TO FIT.
- (517) SEE THRIE BEAM RAIL TERMINAL CONNECTOR DETAIL ASSEMBLY.
- (518) CAP ASSEMBLY
- (519) 4" MAX. GAP BETWEEN TEMPORARY BARRIER AND RIGID BARRIER.
- (520) ALL TWELVE SPLICE HOLES REQUIRE M1 AND M2




PROFILE VIEW




**PLAN VIEW
TRANSITION TO RIGID BARRIER**




**PLAN DETAIL VIEW
TRANSITION TO RIGID BARRIER**




**FRONT DETAIL VIEW
TRANSITION TO RIGID BARRIER**




**CROSS SECTION
TEMPORARY BARRIER
PLACEMENT SINGLE SLOPE**




**CROSS SECTION
TEMPORARY BARRIER
PLACEMENT SAFETY SHAPE**



**CROSS SECTION
TEMPORARY BARRIER
PLACEMENT VERTICAL**




**BACK DETAIL VIEW
TRANSITION TO RIGID BARRIER**




**(517) DETAIL PLAN VIEW
THRIE BEAM RAIL TERMINAL CONNECTOR ASSEMBLY**

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




**TOP VIEW
S1**




**ELEVATION VIEW
S1**



PLAN VIEW




BACK VIEW




SIDE VIEW (600)


42" TOP CAP ASSEMBLY




**SIDE VIEW
S3**




S2




S4



S5



S6



S7

GENERAL NOTES


STITCH WELD GUSSET PLATES AND END PLATES ON THREE SIDES

STITCH WELD TWO SIDE PLATES TO TOP PLATE, END PLATE AND GUSSETS.


(600) SIDE PLATES (S3) NOT SHOWN FOR CLARITY.

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION



SIDE VIEW T4



SIDE VIEW T3


END VIEW

END VIEW


END VIEW

GENERAL NOTES


- STITCH WELD GUSSET PLATES AND END PLATES ON THRIE SIDES
- STITCH WELD TWO SIDE PLATES TO TOP PLATE, END PLATE AND GUSSETS.
- SIDE PLATES, TOP PLATE, END PLATE AND GUSSETS ARE 12 GAUGE ASTM A36 GALVANIZED STEEL.
- (700) SIDE PLATES (T3 AND T4) NOT SHOWN FOR CLARITY.




ISOMETRIC 56 INCH TOP CAP




END VIEW 56 INCH TOP CAP




SIDE VIEW 56 INCH TOP CAP (700)




SIDE VIEW TOP PLATE T1




DETAIL "A"



DETAIL "B"




END PLATE T2



GUSSET PLATES T5 - T16



GUSSET DIMENSIONS				
GUSSET NO.	A	B	C	D
T5	22 13/16"	5 1/16"	2 5/16"	8 1/16"
T6	21"	5 7/8"	2 3/16"	8 1/16"
T7	19 3/16"	6 1/8"	1 13/16"	8 1/16"
T8	17 3/8"	6 1/4"	1 13/16"	8 1/16"
T9	15 9/16"	6 7/16"	1 1/16"	8 1/16"
T10	13 3/4"	6 5/8"	1 7/16"	8 1/16"
T11	11 15/16"	6 13/16"	1 1/4"	8 1/16"
T12	10 1/8"	7"	1 1/16"	8 1/16"
T13	8 5/16"	7 3/16"	7/8"	8 1/16"
T14	6 1/2"	7 3/8"	1 1/16"	8 1/16"
T15	4 1/16"	7 1/16"	1/2"	8"
T16	2 7/8"	7 3/4"	1/4"	8"





PLAN VIEW TOP PLATE T1

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




- GENERAL NOTES**
- 800 FREE STANDING TEMPORARY BARRIER
 - 801 GAP STIFFENER ASSEMBLY
 - 802 THRIE BEAMS ARE NESTED ON BOTH SIDES OF THE TEMPORARY BARRIER.
 - 803 SEE THRIE BEAM RAIL TERMINAL CONNECTOR DETAIL




PORTABLE CONCRETE BARRIER GAP THRIE BEAM COVER

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




**PLAN VIEW
GAP WITHIN SPACING**




**PLAN VIEW
TEMPORARY BARRIER GAP OVER 4" TO 1' MAX. 904**



**PLAN VIEW
TEMPORARY BARRIER GAP OVER 1' TO 4' MAX. 904**



**PLAN VIEW
TEMPORARY BARRIER GAP OVER 4' TO 7' MAX. 904**




**PLAN VIEW
TEMPORARY BARRIER GAP OVER 7' TO 12.5' MAX. 904**

GENERAL NOTES


- 900 SEE OTHER DETAILS FOR TEMPORARY GAP HARDWARE (TYP.)
- 901 TEMPORARY BARRIER GAP
- 902 GAP STIFFENER ASSEMBLY CENTERED IN THE GAP.
- 903 GAP STIFFENER ASSEMBLY IS OFFSET 18 3/4" FROM CENTER
- 904 MINIMUM NUMBER OF GAP STIFFENERS SHOWN FOR THE GAP RANGE SHOWN.
- 905 MINIMUM OF 8 CONTINUOUS FREE STANDING TEMPORARY BARRIERS

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




PROFILE VIEW **SIDE VIEW**
STIFFENER ASSEMBLY
CENTER PANEL U1




FLAT PATTERN **SIDE VIEW**
STIFFENER ASSEMBLY
SIDE PANEL U2




PROFILE VIEW
STIFFENER ASSEMBLY
BOTTOM PANEL U3




SECTION A - A



SECTION B - B




PLAN VIEW




PROFILE VIEW **SIDE VIEW**

GAP STIFFENER ASSEMBLY




ISOMETRIC




SIDE VIEW

PLAN VIEW
ELEVATION VIEW
W1 TOE PLATE




CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION




ELEVATION VIEW

**THRIE BEAM
TERMINAL CONNECTOR**



ELEVATION VIEW


**ADDITIONAL THRIE BEAM
TERMINAL CONNECTOR HOLE DETAIL**




**PLATE WASHER DETAIL
G2, H3**

GENERAL NOTES

- (1100) 1" DIA. HOLE
- (1101) 3/4" DIA. HOLE
- (1102) PROVIDE HOLES IN THRIE BEAM TERMINAL CONNECTOR TO LIMIT STEEL REINFORCEMENT OR LOOP BAR CONFLICT. CONTRACTOR MAY FIELD DRILL ADDITIONAL HOLE OR PROVIDE THRIE BEAM TERMINAL CONNECTOR WITH ADDITIONAL HOLES FROM SUPPLIER.




SLOTTED THRIE BEAM RAIL K1




**SECTION THROUGH
BEAM K1**

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




SIDE ELEVATION
(FOR CONNECTION TO LEFT END OF BARRIER)



SIDE ELEVATION
LOOP BAR ASSEMBLY INVERTED FOR OPPOSITE END
(FOR CONNECTION TO RIGHT END OF BARRIER)


GENERAL NOTES

(1200) SEE LIFTING SLOT DETAIL. LOCATION OF LIFTING SLOTS DETERMINED BY CONTRACTOR.




FLARE AT BARRIER END


POSTED SPEED, (MPH)	FLARE RATE
40 OR LESS	6:1
45 OR GREATER	8:1




PLAN VIEW




B12




FRONT ELEVATION



END SECTION



BENT BAR DETAIL



BAR	A	B
B6	10"	1"
B7	1'- 1"	1 1/4"
B8	1'- 5"	1 5/8"
B9	1'- 8"	1 7/8"
B10	2'- 0 1/2"	2 3/8"
B11	2'- 3"	2 3/4"

B BARS

2 OF EACH SIZE REQUIRED FOR STIRRUP ASSEMBLY

DETAILS OF BARRIER TAPER SECTION

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS - CONCRETE BARRIER PRECAST

PART	DESCRIPTION	MATERIALS SPECIFICATIONS	NOTES
A1	PRECAST TEMPORARY BARRIER - CONCRETE	MIN. = f _c 5000 PSI	
B1	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#5 REBAR, LENGTH 12'-2"
B2	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 12'-2"
B3	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#5 REBAR, LENGTH 12'-2"
B4	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 6'-0"
B5	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#6 REBAR, LENGTH 2'-11"
B6	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 1'-11"
B7	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 2'-2"
B8	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 2'-6"
B9	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 2'-9"
B10	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 3'-2"
B11	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 3'-4"
B12	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 12'-0"
B13	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#4 REBAR, LENGTH 7'-9"
B14	REBAR	STANDARD SPEC. 505.2 GRADE 60 UNCOATED REBAR	#5 REBAR, LENGTH 11'-9"
C1	LOOP BAR	ASTM A709 GRADE 70 SMOOTH BAR OR ASTM A706 GRADE 60 REBAR UNCOATED	¾" DIA.
C2	LOOP BAR	ASTM A709 GRADE 70 SMOOTH BAR OR ASTM A706 GRADE 60 REBAR UNCOATED	¾" DIA.
C3	LOOP BAR	ASTM A709 GRADE 70 SMOOTH BAR OR ASTM A706 GRADE 60 REBAR UNCOATED	¾" DIA.
D1	CONNECTION PIN - ROD	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	1 ½" DIA.
D2	CONNECTION PIN - TOP PLATE	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	
G1	BOLT THROUGH ANCHOR - THREADED ROD	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 A307 GRADE A OR SAE J429 GRADE 2 UNC	1 ½" DIA.
G2	BOLT THROUGH ANCHOR - WASHER, SQUARE	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	
G3	BOLT THROUGH ANCHOR - NUT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	
H1	ADHESIVE ANCHOR - ADHESIVE	ICC-ES-AC308 5 ¼" EMBEDMENT WITH A MIN. BOND STRENGTH OF 1,650 PSI. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS.	
H2	ADHESIVE ANCHOR - THREADED ROD	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 A307 GRADE A / SAE J429 GRADE 2 UNC	1 ½" DIA.
H3	ADHESIVE ANCHOR - WASHER, SQUARE	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	
H4	ADHESIVE ANCHOR - NUT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	
J1	ASPHALT ANCHOR PIN - ROD	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	1 ½" DIA.
J2	ASPHALT ANCHOR PIN - STOP PLATE	ASTM A36 MIN. STRENGTH 36 KSI / ASTM A529 MAX. STRENGTH 50 KSI / ASTM A572 MAX STRENGTH 50 KSI / ASTM A709 MAX STRENGTH 50 KSI / ASTM A992 MAX STRENGTH 50 KSI	
K1	THRIE BEAM RAIL	AASHTO M180 CLASS A TYPE 2 APPROVED PRODUCER	12 GAUGE
L1	THRIE BEAM RAIL - TERMINAL	AASHTO M180 CLASS A TYPE 2 APPROVED PRODUCER	12 GAUGE

PART	DESCRIPTION	MATERIALS SPECIFICATIONS	NOTES
M1	SPLICE BOLT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GAL. TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 UNC AASHTO M180 HEAD ASTM A307 GRADE B OR SAE J429 GRADE 2 OR ASTM F1554 GRADE 36	¾" DIA.
M2	SPLICE BOLT - NUT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	
N1	THRIE BEAM RAIL TERMINAL - MECHANICAL ANCHOR	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	¾" DIA. LENGTH 6"
N2	THRIE BEAM RAIL TERMINAL - WASHER	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1	
N3	THRIE BEAM RAIL TERMINAL MECHANICAL OR ADHESIVE ANCHOR	MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS: ULTIMATE TENSILE LOAD 17.9 KIPS AND ULTIMATE SHEAR LOAD 21.96 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS.	
P1	THRIE BEAM RAIL CONNECTION 1-BOLT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	¾" DIA.
P2	THRIE BEAM RAIL CONNECTION 1-WASHER	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GAL. TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1	
P3	THRIE BEAM RAIL CONNETION 1- MECHANICAL OR ADHESIVE ANCHOR	MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS: ULTIMATE TENSILE LOAD 9.48 KIPS AND ULTIMATE SHEAR LOAD 10.48 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS.	
Q1	BLOCK WOOD	SEE STANDARD SPEC. 614	
R1	CAP - BOLT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 AASHTO M180 RECESSED HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	¾" DIA.
R2	CAP - BOLT - WASHER	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GAL. TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1	
R3	CAP - BOLT - MECHANICAL ANCHOR	MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS ULTIMATE TENSILE LOAD 12.14 KIPS AND ULTIMATE SHEAR LOAD 17.5 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS.	12 GAUGE
S1	CAP 42-INCH TOP PLATE	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S2	CAP 42-INCH END PLATE	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S3	CAP 42-INCH SIDE PLATE	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S4	CAP 42-INCH GUSSET 1	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S5	CAP 42-INCH GUSSET 2	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S6	CAP 42-INCH GUSSET 3	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
S7	CAP 42-INCH GUSSET 4	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE

6

6

SDD 14B07-16m

SDD 14B07-16m

**CONCRETE BARRIER
TEMPORARY PRECAST,
12' - 6"**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS - CONCRETE BARRIER PRECAST

PART	DESCRIPTION	MATERIALS SPECIFICATIONS	NOTES
T1	CAP 56-INCH TOP PLATE	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T2	CAP 56-INCH END PLATE	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T3	CAP 56-INCH SIDE PLATE 1	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T4	CAP 56-INCH SIDE PLATE 2	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T5	CAP 56-INCH GUSSET 1	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T6	CAP 56-INCH GUSSET 2	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T7	CAP 56-INCH GUSSET 3	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T8	CAP 42-INCH GUSSET 4	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T9	CAP 42-INCH GUSSET 5	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T10	CAP 42-INCH GUSSET 6	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T11	CAP 42-INCH GUSSET 7	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T12	CAP 42-INCH GUSSET 8	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T13	CAP 42-INCH GUSSET 9	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T14	CAP 42-INCH GUSSET 10	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T15	CAP 42-INCH GUSSET 11	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
T16	CAP 42-INCH GUSSET 12	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	12 GAUGE
U1	GAP STIFFENER	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	
U2	GAP STIFFENER - CONNECTOR PLATE 1	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	
U3	GAP STIFFENER - CONNECTOR PLATE 2	AASHTO M111 / ASTM A123 ASTM A36 MIN. STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	

PART	DESCRIPTION	MATERIALS SPECIFICATIONS	NOTES
V1	THRIE BEAM RAIL TERMINAL MECHANICAL OR ADHESIVE ANCHOR	MINIMUM MECHANICAL OR ADHESIVE ANCHOR STRENGTH REQUIREMENTS ULTIMATE TENSILE LOAD 24.0 KIPS AND ULTIMATE SHEAR LOAD 21.5 KIPS. SEE 603.2 AND 603.3.1.2 OF THE WISCONSIN STANDARD SPECIFICATIONS FOR MORE INFORMATION ON ADHESIVE ANCHORS.	¾" DIA.
V2	GAP STIFFENER - BOLT - NUT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C O R MECHANICAL GALVANIZE TO AASHTO M298 CLASS 50 TYPE 1 / ASTM B695 CLASS 50 TYPE 1 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291/ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	
W1	TOE PLATE	AASHTO M111/ASTM A123 ASTM A36 MIN STRENGTH 36 KSI, OR ASTM A529 MAX. STRENGTH 50 KSI, OR ASTM A572 MAX. STRENGTH 50 KSI, OR ASTM A709 MAX. STRENGTH 50 KSI, OR ASTM A992 MAX. STRENGTH 50 KSI	
X1	TOE PLATE - CONNECTION BOLT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 UNC HEAVY HEX HEAD OR AASTHO M180 HEAD, ASTM F3125 GRADE A325 TYPE 1 HEAVY HEX HEAD OR SAE J429 GRADE 5 HEAVY HEX HEAD / ASTM A449 TYPE 1 HEAVY HEX HEAD. BOLTS MAY BE FULLY THREADED. PROVIDE ENOUGH THREADING FOR PROPER TIGHTENING OF BOLT.	¾" DIA.
X2	TOE PLATE - CONNECTION BOLT - WASHER	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 TYPE 2 F436 TYPE 1 (HARDEN WASHER ONLY)	
X3	TOE PLATE - CONNECTION BOLT - NUT	HOT DIP AASHTO M232 CLASS / ASTM A153 CLASS C / ASTM F2329 C OR MECHANICAL GALVANIZE TO AASHTO M298 CLASS 55 TYPE 2 / ASTM B695 CLASS 55 UNC OVER TAP NUTS AS SPECIFIED IN AASHTO 291 / ASTM A 563 HEAVY HEX HEAD ASTM A563DH OR SAE J995 GRADE 5	


6

6

SDD 14B07-16n

SDD 14B07-16n

CONCRETE BARRIER TEMPORARY PRECAST, 12' - 6"	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED February 2023 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT ENGINEER
FHWA	




DIMENSION A TABLE ^②

FACILITY	POSTED SPEED MPH	DIMENSION A	
		MIN. FT	MAX. FT
FREEWAY/EXPRESSWAY	ALL	15	20
NON-FREEWAY/EXPRESSWAY	GREATER THAN OR EQUAL TO 45	10	15
NON-FREEWAY/EXPRESSWAY	LESS THAN 45	8	10
AADT LESS THAN 1,500	ALL	8	10

**CRASH CUSHION/SAND BARREL ARRAY AND TEMPORARY BARRIER
INSTALLATION FOR TRAFFIC ON ONE SIDE OF BARRIER**

DIMENSION B TABLE ^②

POSTED SPEEDS MPH	DIMENSION B FT
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645



**CRASH CUSHION/SAND BARREL ARRAY AND TEMPORARY BARRIER
INSTALLATION FOR TRAFFIC ON BOTH SIDES OF BARRIER**

LEGEND

- DIRECTION OF TRAVEL
- CRASH CUSHION OR SAND BARREL ARRAY
- SEE FREE STANDING TRANSITION TO TIED-DOWN SYSTEM DETAILS
- SEE BI-DIRECTIONAL TRANSITION TO TIED-DOWN SYSTEM DETAILS
- 3 PINS PLACED ON TRAFFIC SIDE OF BARRIER
- PERMANENT CONCRETE BARRIER OR CONCRETE PARAPET
- FREE STANDING TEMPORARY BARRIER

GENERAL NOTES

SEE STANDARD DETAIL DRAWING 14B7 FOR MORE INFORMATION.

DETAILS PROVIDE A GENERAL LAYOUT OF TEMPORARY CONCRETE BARRIER, CRASH CUSHIONS, SAND BARREL ARRAYS AND TIE DOWN TRANSITIONS. DETAILS PROVIDED MAY NOT FIT ALL POSSIBLE SITUATIONS OR SITE CONDITIONS. SEE OTHER SECTIONS OF THE CONTRACT OR PROJECT ENGINEER FOR MORE DETAILS.

ADDITIONAL TEMPORARY BARRIER MAY BE REQUIRED TO PROTECT TRAVELING PUBLIC FROM HAZARDS, CONTRACTOR'S OPERATIONS OR TO CONTROL TRAFFIC.

TEMPORARY BARRIER MAY BE REQUIRED TO BE ANCHORED TO PAVEMENT OR BRIDGE DECK.

- ① FOR DEFLECTION INFORMATION SEE STANDARD DETAIL DRAWING 14B7.
- ② VALUES PROVIDED MAY NOT FIT ALL POSSIBLE SITUATIONS OR SITE CONDITIONS. SEE OTHER SECTIONS OF THE CONTRACT OR PROJECT ENGINEER FOR MORE DETAILS.
- ③ ANCHOR TEMPORARY BARRIER ACCORDING TO CRASH CUSHION OR SAND BARREL MANUFACTURER'S RECOMMENDATIONS. IF MANUFACTURER'S RECOMMENDATIONS ARE NOT PROVIDED, ANCHOR 3 PINS ON TRAFFIC SIDE.

**CRASH CUSHION/SAND BARREL
ARRAY AND OTHER TEMPORARY
BARRIER LAYOUT DETAILS**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

S.D.D. 14 B 8-2a

S.D.D. 14 B 8-2a



**CRASH CUSHION/SAND BARREL ARRAY AND TEMPORARY BARRIER
INSTALLATION FOR TRAFFIC ON ONE SIDE - FLARED INSTALLATION**




**TRANSITION FROM FREE STANDING TEMPORARY BARRIER
TO ANCHORED BARRIER**

LEGEND


- DIRECTION OF TRAVEL
- CRASH CUSHION OR SAND BARREL ARRAY
- SEE FREE STANDING TRANSITION TO TIED-DOWN SYSTEM DETAILS
- SEE BI-DIRECTIONAL TRANSITION TO TIED-DOWN SYSTEM DETAILS
- 3 PINS PLACED ON TRAFFIC SIDE OF BARRIER
- PERMANENT CONCRETE BARRIER OR CONCRETE PARAPET
- FREE STANDING TEMPORARY BARRIER

**CRASH CUSHION/SAND BARREL
ARRAY AND OTHER TEMPORARY
BARRIER LAYOUT DETAILS**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




TEMPORARY BARRIER OVERLAP - ONE-WAY TRAFFIC



TEMPORARY BARRIER OVERLAP - TWO-WAY TRAFFIC



**ENDING TEMPORARY BARRIER
DOWNSTREAM - UNANCHORED**



**ENDING TEMPORARY BARRIER
DOWNSTREAM - ANCHORED**

LEGEND

- DIRECTION OF TRAVEL
- CRASH CUSHION OR SAND BARREL ARRAY
- SEE FREE STANDING TRANSITION TO TIED-DOWN SYSTEM DETAILS
- SEE BI-DIRECTIONAL TRANSITION TO TIED-DOWN SYSTEM DETAILS
- 3 PINS PLACED ON TRAFFIC SIDE OF BARRIER
- PERMANENT CONCRETE BARRIER OR CONCRETE PARAPET
- FREE STANDING TEMPORARY BARRIER

**CRASH CUSHION/SAND BARREL
ARRAY AND OTHER TEMPORARY
BARRIER LAYOUT DETAILS**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6


6

S.D.D. 14 B 8-2c

S.D.D. 14 B 8-2c




CONNECTING TEMPORARY BARRIER TO PERMANENT CONCRETE BARRIER-TRAFFIC ON ONE SIDE




CONNECTING TEMPORARY BARRIER TO PERMANENT CONCRETE BARRIER-TRAFFIC ON BOTH SIDES

LEGEND

- DIRECTION OF TRAVEL
- CRASH CUSHION OR SAND BARREL ARRAY
- SEE FREE STANDING TRANSITION TO TIED-DOWN SYSTEM DETAILS
- SEE BI-DIRECTIONAL TRANSITION TO TIED-DOWN SYSTEM DETAILS
- 3 PINS PLACED ON TRAFFIC SIDE OF BARRIER
- PERMANENT CONCRETE BARRIER OR CONCRETE PARAPET
- FREE STANDING TEMPORARY BARRIER



OVERLAPPING TEMPORARY BARRIER AND PERMANENT BARRIER - ONE WAY TRAFFIC



OVERLAPPING TEMPORARY BARRIER AND PERMANENT BARRIER - TWO WAY TRAFFIC

CRASH CUSHION/SAND BARREL ARRAY AND OTHER TEMPORARY BARRIER LAYOUT DETAILS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

S.D.D. 14 B 8-2d


S.D.D. 14 B 8-2d

LEGEND

- DIRECTION OF TRAVEL
- CRASH CUSHION OR SAND BARREL ARRAY
- SEE FREE STANDING TRANSITION TO TIED-DOWN SYSTEM DETAILS
- SEE BI-DIRECTIONAL TRANSITION TO TIED-DOWN SYSTEM DETAILS
- 3 PINS PLACED ON TRAFFIC SIDE OF BARRIER
- PERMANENT CONCRETE BARRIER OR CONCRETE PARAPET
- FREE STANDING TEMPORARY BARRIER

DIMENSION C TABLE ²

AVAILABLE DEFLECTION DISTANCE	MINIMUM LENGTH OF BARRIER BEYOND HAZARD FT
GREATER THAN 8'	12.5
LESS THAN OR EQUAL TO 8' BUT GREATER THAN 4'	50
LESS THAN OR EQUAL TO 4'	100



6

6

S.D.D. 14 B 8-2e




S.D.D. 14 B 8-2e

**CRASH CUSHION/SAND BARREL
ARRAY AND OTHER TEMPORARY
BARRIER LAYOUT DETAILS**







STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
June, 2015 /S/ Jerry H. Zogg
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA ENGINEER

- ① WOOD OR STEEL POSTS (w6X9 OR w6X8.5) MAY BE USED. DO NOT INTERMIX WOOD AND STEEL POSTS. INSTALL STEEL POSTS WITH HOLES ON APPROACHING TRAFFIC SIDE.
- ② USE WOOD OR APPROVED PLASTIC BLOCKOUTS. WOOD BLOCKOUTS MAY BE CONSTRUCTED OUT OF TWO OR MORE WOOD BLOCKOUTS. SEE ALTERNATE WOOD BLOCKOUT DETAIL. DIMENSIONS OF APPROVED PLASTIC BLOCKOUTS MAY VARY.
- ③ IF ROCK IS ENCOUNTERED DURING EXCAVATION, PROVIDE A HOLE 12 INCHES IN DIAMETER EXTENDING 20 INCHES DEEP INTO THE ROCK. PLACE APPROXIMATELY 2 1/2" INCHES OF GRANULAR MATERIAL IN THE BOTTOM OF THE HOLE. CUT THE POSTS THE TO LENGTH AND INSTALL. BACKFILL WITH EXCAVATED MATERIAL AND COMPACT. BACKFILL IS TO BE FREE OF LARGE ROCKS.
- ④ WHEN THE DISTANCE FROM BACK OF POST TO SHOULDER HINGE POINT IS LESS THAN 2 FEET INSTALL LONGER POST AT HALF POST SPACING (K).
- ⑤ FOR NEW MGS INSTALLATION TOP OF W-BEAM RAIL TOLERANCE IS ±1". FOR EXISTING MGS INSTALLATION TOP OF W-BEAM IS BETWEEN 27 3/4" TO 32".
- ⑥ WHEN USING STEEL POST AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- ⑦ TOTAL POST LENGTH FOR TYPE K IS 7' - 0". TOTAL POST LENGTH FOR OTHER MGS TYPES IS 6' - 0".




**WOOD POST
(6" X 8") NOMINAL** ①




**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




**FRONT VIEW
POST SPACING STANDARD INSTALLATION**




**FRONT VIEW
MID-SPAN BEAM SPLICE**

GENERAL NOTES


- ⑧ DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.
 - ⑨ 25 FEET OF HALF POST SPACING IS REQUIRED ON APPROACH AND DEPARTURE ENDS OF QUARTER POST SPACING.
- POST BOLTS ARE A 5/8" DIAMETER ASTM A307 GUARDRAIL BOLT. A POST BOLT REQUIRES 3/4" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT AND 5/8" DIAMETER F844 FLAT WASHER. POST BOLTS MAY BE LONGER IF MULTIPLE BLOCKOUTS ARE BEING USED.
- GUARD RAIL SPLICE BOLTS ARE A 5/8" DIAMETER ASTM A307 GUARDRAIL HEAD BOLT. A GUARDRAIL SPLICE BOLT REQUIRES 3/4" DIAMETER A563A DOUBLE RECESSED (DR) HEAVY HEX NUT.




**FRONT VIEW
HALF POST SPACING (HS) AND
HALF POST SPACING WITH LONGER POSTS (K)**




FRONT VIEW AT STEEL POST




FRONT VIEW AT WOOD POST



SECTION THRU W-BEAM RAIL



**FRONT VIEW
QUARTER POST SPACING (QS)**



**ONE SIDED REFLECTOR DETAIL
AND TYPICAL INSTALLATION**

**MIDWEST GUARDRAIL SYSTEM
(MGS) GUARDRAIL**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6

SDD 14B42 - 07b

SDD 14B42 - 07b




DETAIL FOR 16" BLOCKOUT DEPTH

IT IS ACCEPTABLE TO USE BLOCKOUTS UP TO 16" DEEP TO INCREASE THE POST OFFSET TO AVOID UNDERGROUND OBSTACLES. THERE IS NO LIMIT TO THE NUMBER OF POSTS THAT CAN HAVE ADDITIONAL BLOCKOUTS UP TO 16" DEEP.


NOTE:

1. ALL FILLETS SHALL HAVE A MINIMUM RADIUS OF 3/16".
2. IF THE BOLT EXTENDS MORE THAN 1/4" FROM THE NUT THE BOLT SHOULD BE TRIMMED BACK.




POST BOLT TABLE


L	T (MIN.)
1 1/4"	1 1/8"
2"	1 3/4"
10"	4"
14"	4 1/16"
18"	4"
21"	4 1/16"
25"	4"




ALTERNATE BOLT HEAD




POST BOLT, SPLICE BOLT AND RECESS NUT



PLAN VIEW BEAM LAPPING DETAIL




POST DRIVING FOR CONTINUOUS UNDERGROUND OBSTRUCTION



DETAIL FOR 36" BLOCKOUT DEPTH

NOTES: UNDER SPECIAL CIRCUMSTANCES, SUCH AS AVOIDING OBSTACLES THAT ARE NOT RELOCATED, IT IS ACCEPTABLE TO INSTALL ADDITIONAL BLOCKOUTS TO OBTAIN UP TO 36" DEPTH FOR ONE OR TWO POSTS IN A SECTION OF GUARDRAIL. DO NOT USE 16" OR 36" BLOCKOUTS IF IT CAUSES THE POST TO BE DRIVEN BEYOND SHOULDER HINGE POINT OR CAUSES A FIXED OBJECT TO BE WITHIN THE DEFLECTION DISTANCE OF THE BARRIER.




ALTERNATE WOOD BLOCKOUT DETAIL


6 WHEN USING STEEL POST AND WOOD BLOCKOUTS, INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.

MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




MISSING POST IN MGS GUARDRAIL




MISSING POST IN MGS GUARDRAIL NEAR EAT




MISSING POST IN MGS GUARDRAIL NEAR AN APPROACH TRANSITION



MISSING POST IN MGS GUARDRAIL NEAR FLARED BEAM GUARD




MISSING POST IN MGS GUARDRAIL NEAR A TYPE 2 END TERMINAL




MISSING POST IN SHORT SPAN MGS GUARDRAIL NEAR CURB (SL)

- (400) MAX SPAN 12' - 6"
- (401) 2' MIN.
- (402) MGS GUARDRAIL 3
- (403) NESTING BEAM GUARD
- (404) ASYMMETRIC TRANSITION
- (405) SOIL WELL DRAINED AND COMPACTED
- (406) SEE OTHER DRAWINGS IN THIS SDD
- (407) SEE OTHER DRAWINGS FOR MIN. SPACING BETWEEN SPANS
- (408) SEE SDD 14B44
- (409) SEE SDD 14B45
- (410) SEE SDD 14B47
- (411) MINIMUM DISTANCE BETWEEN MISSING POST SPANS.



SECTION A - A



SECTION B - B

MIDWEST GUARDRAIL SYSTEM (MGS) GUARDRAIL	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2021 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
<small>FHWA</small>	

GENERAL NOTES

- (A) THE SLOPE IN THE AREA BOUNDED BY THE GRADELINE, THE HINGE POINT LINE AND THE CLEAR ZONE LIMITS (CZL) SHALL BE 4:1 OR FLATTER.
 - (B) AFTER FINAL ASSEMBLY, RECHECK CABLE TO BE SURE IT IS TAUT AND HAS NOT RELAXED
 - (C) DIFFERENT MANUFACTURERS REQUIRE DIFFERENT PERFORATED W - BEAM RAIL END PANELS. SEE MANUFACTURER'S INFORMATION.
 - (D) ATTACH ALUMINUM SHEET TO E.A.T. HEAD USING 4 STAINLESS STEEL SELF - TAPPING SCREWS. ONE SCREW PER CORNER.
 - (E) HARDWARE MAY VARY BETWEEN MANUFACTURER. SEE MANUFACTURER'S DRAWING FOR INFORMATION.
- DIMENSIONS MAY VARY, MANUFACTURER'S INFORMATION.








SEE SDD 14B42 FOR MORE INFORMATION.

* DO NOT ATTACH BLOCKOUTS TO POST 1 AND 2.

DO NOT INSTALL REFLECTORS ON THE FIRST 50 FEET OF THE APPROACH END OF THE ENERGY ABSORBING TERMINAL.

SEE MANUFACTURER'S DRAWING FOR SPLICE LOCATION, HARDWARE DIMENSIONS AND INSTALLATION INSTRUCTIONS.

THE CENTER OF THE UPPER 3 1/2" DIAMETER HOLE ON POST NUMBER 3 THROUGH POST 9 IS TO BE FLUSH WITH THE GROUND LINE UP TO A MAXIMUM OF 2" ABOVE GROUND LINE. WOOD BLOCKS ON POSTS NUMBERED 3 THROUGH 9 MAY BE ADJUSTED UP TO 3" ABOVE THE TOP OF POST.



**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

SDD 14B44 - 04a


SDD 14B44 - 04a

BILL OF MATERIALS


PART NO.	DESCRIPTION MATERIALS PROVIDED BY MGS EAT MANUFACTURER. SEE MANUFACTURER'S DETAILS FOR MORE INFORMATION.
①	UPPER POST NO. 1 6" X 6" TUBE
②	LOWER POST NO. 1
③	WOOD CRT
④	WOOD BLOCKOUT
⑤	PIPE SLEEVE
⑥	BEARING PLATE
⑦	BCT CABLE ASSEMBLY
⑧	ANCHOR CABLE BOX
⑨	GROUND STRUT
⑩	PERFORATED W-BEAM RAIL END PANEL, 12'-6" LONG.
⑪	STANDARD W-BEAM RAIL. MULTIPLE SECTIONS REQUIRED. SECTIONS VARY IN LENGTH.
⑫	IMPACT HEAD
⑬	EAT MARKER POST - YELLOW (SEE APPROVED PRODUCTS LIST)
⑭	SOIL PLATE
⑮	UPPER POST NO. 2
⑯	LOWER POST NO. 2



GENERIC GROUND STRUT ⑨ ⑤




GENERIC ANCHOR CABLE BOX ⑨ ⑤




BEARING PLATE ⑥ ⑤

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




UPPER POST NO. 1 ⁽¹⁾ (E)




LOWER POST NO. 1 ⁽²⁾ (E)




WOOD CRT POST ⁽³⁾ (E)
POSTS NUMBER 3-9



UPPER POST NO. 2 ⁽¹⁵⁾ (E)




LOWER POST NO. 2 ⁽¹⁶⁾ (E)



WOOD BLOCKOUT ⁽⁴⁾
REQ'D. AT ALL POSTS EXCEPT POST NO'S 1 & 2


6




REFLECTIVE SHEETING DETAIL ^(E)

TYPE H
YELLOW REFLECTIVE
SHEETING 3" X 9".
SEE STANDARD
SPECIFICATION 637.


E.A.T. MARKER
POST (YELLOW)



FRONT VIEW SIDE VIEW
E.A.T. MARKER POST ⁽¹³⁾



SIDE VIEW



TOP VIEW

ALTERNATE WOOD
BLOCKOUT DETAIL

6

SDD 14B44 - 04c

SDD 14B44 - 04c

**MIDWEST GUARDRAIL SYSTEM
ENERGY ABSORBING TERMINAL
(MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
7/2018 DATE /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR


FHWA

GENERAL NOTES


- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ③ WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 10D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- ④ TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".
- ⑬ STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42




**SECTION A-A
POSTS 1-5**



**SECTION B-B
POST 6**



**SECTION C-C
POSTS 7-11**



**THRIE BEAM
TERMINAL CONNECTOR**






PLATE WASHER DETAIL




SPLICE DETAIL




**SECTION THRU THRIE
BEAM RAIL ELEMENT**

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




W-BEAM TO THRIE BEAM TRANSITION SECTION




6'-3\"/>




12'-6\"/>




ALTERNATE WOOD BLOCKOUT DETAIL




STEEL POSTS 1-5




STEEL POSTS 6-17




TOP VIEW



**FRONT VIEW
BLOCKOUT
POSTS 1-5**



TOP VIEW



**FRONT VIEW
BLOCKOUT
POSTS 6-17**

GENERAL NOTES

- STEEL POSTS ARE W6X9 OR W6X8.5.
- BOLT HOLES FOR POST ARE ON FRONT AND OF SIDE OF POST.
- (3) WHEN USING STEEL POSTS AND WOOD BLOCKOUTS INSTALL FOUR 16D GALVANIZED NAILS. INSTALL NAILS AT THE BACK CORNERS OF THE BLOCK AND BEND THE NAILS OVER THE FLANGE OF THE STEEL POST.
- (5) WOOD BLOCKS MAY BE CONSTRUCTED OUT OF 2 WOOD BLOCKS. SEE ALTERNATE WOOD BLOCK DETAIL.
- (13) STEEL OR WOOD POST IS ACCEPTABLE AT POST 1. SEE SDD 14B42.

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

6

6


S.D.D. 14 B 45-5c

S.D.D. 14 B 45-5c



FRONT VIEW



THRIE BEAM CONNECTION TO BRIDGE PARAPET WITH SQUARE ENDS



SECTION E-E


GENERAL NOTES

- THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.
- (2) OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
 - (4) TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
 - (6) DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
 - (7) BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
 - (8) THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".




FRONT VIEW

**W BEAM TRANSITION AND CONNECTION TO BRIDGE PARAPETS WITH SQUARE ENDS
(USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)**



SECTION F-F



DRILL HOLE LOCATION

MIDWEST GUARDRAIL SYSTEM THRIE BEAM TRANSITION (MGS)	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED 07/2018 DATE	/S/ Rodney Taylor ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA	

6

6


S.D.D. 14 B 45-5d

S.D.D. 14 B 45-5d

GENERAL NOTES


THESE ARE TYPICAL CONNECTION DETAILS. ADJUST THE POSITION OF CONNECTIONS TO EXISTING BRIDGES TO FIT THE ACTUAL BRIDGE AND SITE DIMENSIONS.

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.
- ⑧ THE RECESS FOR A W-BEAM CONNECTION, WHICH EXISTS ON SOME PARAPETS OF THIS TYPE, SHALL BE FILLED WITH A TREATED TIMBER BLOCKOUT. BLOCKOUT SIZE IS 1'-6" X 2'-0" X 3 1/2".
- ⑨ BOLT, NUT AND WASHERS NOT REQUIRED FOR THIS LOCATION WHEN RETROFITTING AN EXISTING PAPAPET AND THE HOLE IS EITHER ABOVE PARAPET OR WITHIN 4 INCHES OF THE EDGE OF PARAPET.




FRONT VIEW

W BEAM CONNECTION TO VERTICAL FACE PARAPET (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)



SECTION G-G



FRONT VIEW

THRIE BEAM CONNECTION TO VERTICAL FACED PARAPETS


MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

ONE WAY
TRAFFIC

⑥ ⑦ 7/8" DIA. HEX HEAD CAP SCREWS INTO
THREADED INSERTS (FURNISHED WITH THE BRIDGE)
WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER
7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED
1" DIA. HOLES DRILLED THRU PARAPET
(4 REQ'D.)



W-BEAM
TERMINAL
CONNECTOR

WHEN RETROFITTING A TRANSITION
TO AN EXISTING RIGID BARRIER,
INSTALL PLATE WASHERS ON
BACKSIDE OF RIGID BARRIER.


FRONT VIEW

**W BEAM CONNECTION TO
PARAPETS WITH SLOPED ENDS**

(USE ONLY AT TRAFFIC EXIT END OF ONE WAY BRIDGE)


GENERAL NOTES

- ② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.
- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑥ DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.
- ⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



**DRILL HOLE LOCATION AND PATTERN
FOR THRIE BEAM CONNECTION**


⑥ ⑦ 7/8" DIA. HEX HEAD CAP SCREWS INTO
THREADED INSERTS (FURNISHED WITH THE BRIDGE)
WHEN RETROFITTING INTO AN EXISTING RIGID BARRIER
7/8" DIA. H.S. HEX BOLT AND WASHERS REQUIRED
1" DIA. HOLES DRILLED THRU PARAPET
(5 REQ'D.)



WHEN RETROFITTING A TRANSITION
TO AN EXISTING RIGID BARRIER,
INSTALL PLATE WASHERS ON
BACKSIDE OF RIGID BARRIER.

FRONT VIEW

**THRIE BEAM CONNECTION TO BRIDGE
PARAPETS WITH SLOPED ENDS**




SECTION I-I


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
DATE 07/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



BACK-UP PLATE DETAIL




SECTION J-J




BACK-UP PLATE MOUNTING ONTO BRIDGE RAILING

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1'$.
- ⑥ DRILLING HOLES THROUGH THE PAPER, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.




**FRONT VIEW
THRIE BEAM CONNECTION TO
STEEL RAILING TYPE "W"**



FRONT VIEW

**THRIE BEAM CONNECTION TO
TUBULAR RAILING TYPE "F"**



SECTION K-K


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
07/2018 /S/ Rodney Taylor
DATE ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

GENERAL NOTES


(4) TOLERANCE FOR TOP OF W-BEAM RAIL IS ± 1".




FRONT VIEW




**PLAN VIEW
BACK-UP PLATE DETAIL, TYPE "M"**



**FRONT VIEW
ANCHOR PLATE DETAIL,
TYPE "M"**




SECTION M-M



SECTION L-L


FRONT VIEW

ANCHOR AND BACK-UP PLATE MOUNTING TO BRIDGE RAILING, TYPE "M"



FRONT VIEW

M



PLAN VIEW

THRIE BEAM CONNECTION TO TUBULAR RAILING, TYPE "M"

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**


STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE 07/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA

GENERAL NOTES

- COVER PLATE PANELS ARE 3/16" THICK.
- ALL STIFFENERS ARE 1/4" THICK.
- CONNECTOR PLATE SHALL BE FABRICATED FROM ASTM GRADE A36 STEEL AND GALVANIZED.
- FOR GALVANIZED REQUIREMENTS, SEE SECTION 614 OF THE STANDARD SPECIFICATIONS.
- ALL HOLE DIAMETERS SHALL BE 1".
- FOR OPPOSITE SIDE INSTALLATION MIRROR DRAWINGS.

- (10) STIFFENERS LOCATED AT THE OUTSIDE EDGES OF THE COVER PLATES SHALL BE WELDED AS FOLLOWS:
SINGLE BEVEL GROOVE WELD ON EXTERNAL SIDES AND 3/16" FILLET WELD BY 1" LONG SPACED AT 2" ON INTERNAL SIDES.
- (11) STIFFENERS LOCATED ON THE INSIDE OF THE COVER PLATE SHALL BE WELDED AS FOLLOWS:
3/16" FILLET WELD BY 1" LONG SPACED AT 2".



WELDING INSTRUCTION
(VIEWED FROM BACK SIDE OF PLATE)




PLATE AND STIFFENER IDENTIFICATION
(VIEWED FROM BACK SIDE OF PLATE)

CONNECTOR PLATE DIMENSION (PER ASSEMBLY)				
PLATE	QUANTITY	SHAPE	SIZE (A x B x C x D)	THICKNESS
P1	1		20" x 20"	3/16"
P2	1		20" x 20" x 28 3/16"	3/16"
P3	1		39" x 3 5/8" x 20" x 19 5/16"	3/16"
S1	4		18 7/16" x 3 5/8" x 18 3/4"	1/4"
S2	1		10 1/4" x 2 1/16" x 10 3/8" x 1/2"	1/4"
S3	1		3" x 1 1/16" x 3 3/8" x 1/2"	1/4"
S4	1		6 1/8" x 2 7/16"	1/4"
S5	1		6 1/8" x 1 1/16"	1/4"
S6	1		7 3/4" x 1 3/4"	1/4"
S7	1		2 3/16" x 6" x 3 5/8" x 5 7/8"	1/4"
S8	1		1 5/32" x 7 1/2" x 2 1/2" x 7 3/8"	1/4"
S9	1		6 1/16" x 6 3/16" x 1 3/32"	1/4"
S10	1		1 7/8" x 9 7/8" x 3 3/8" x 9 11/16"	1/4"
S11	1		8 1/2" x 8 3/4" x 1 3/16"	1/4"

SINGLE SLOPE CONNECTION PLATE

**MIDWEST GUARDRAIL SYSTEM
THREE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED: _____ /S/ Rodney Taylor
DATE: 7/2018 ROADWAY STANDARDS DEVELOPMENT
FHWA UNIT SUPERVISOR

GENERAL NOTES


CONNECTOR PLATE, DRILLING BOLT HOLES THROUGH THE PARAPET, BOLTS, NUTS, WASHERS AND REPAIRING DAMAGED CONCRETE ARE INCIDENTAL TO THE CONTRACT.

② OPTIONAL CURB AND GUTTER OR DRAINAGE FEATURE SEE PLAN FOR INFORMATION.



⑦ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTION PLATE. BOLTS THAT EXTEND THROUGH THE PARAPET AND OUT THE BACK FACE REQUIRE A HARDENED ROUND STEEL WASHER THAT IS 2" O.D. X 5/32" THICK AND ONE PLATE WASHER. REPAIR ANY DAMAGED CONCRETE FROM BOLT INSTALLATION.



THRIE BEAM CONNECTION TO SINGLE SLOPE BARRIER



SECTION N-N




SINGLE SLOPE CONNECTION PLATE PLACEMENT


**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE 7/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT UNIT SUPERVISOR
FHWA



**ELEVATION OF DETAIL AT NY3 END POST
THRIE BEAM RAIL ATTACHMENT**



**ELEVATION OF DETAIL AT NY4 END POST
THRIE BEAM RAIL ATTACHMENT**

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS ± 1".
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND 1/2-INCH BEYOND NUT.

6

6


S.D.D. 14 B 45-5k

S.D.D. 14 B 45-5k

**MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
DATE 7/2018 /S/ Rodney Taylor
ROADWAY STANDARDS DEVELOPMENT
UNIT SUPERVISOR
FHWA



FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY3"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)

GENERAL NOTES

- ④ TOLERANCE FOR TOP OF BEAM IS $\pm 1"$.
- ⑫ BOLTS MAY BE A325 BOLTS OR A449 BOLTS. BOLT LENGTH AND THREADING LENGTH ARE TO ALLOW FOR A TIGHT CONNECTION BETWEEN RIGID BARRIER AND THRIE BEAM CONNECTION PLATE. CONTRACTOR IS TO FIELD VERIFY BOLT LENGTH AND THREAD LENGTH. ONE ROUND WASHER REQUIRED BETWEEN BOLT HEAD AND THRIE BEAM CONNECTOR PLATE. ON BACKSIDE OF PARAPET ONE ROUND WASHER, AND NUT REQUIRED. BOLT THREAD IS TO EXTEND $\frac{1}{2}$ -INCH BEYOND NUT.




FRONT VIEW
W BEAM TRANSITION AND
CONNECTION TO BRIDGE RAILING TYPE "NY4"
 (USE ONLY ON THE TRAFFIC EXIT END OF ONE WAY BRIDGES)


MIDWEST GUARDRAIL SYSTEM
THRIE BEAM TRANSITION (MGS)

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION

APPROVED
 DATE 7/2018 /S/ Rodney Taylor
 ROADWAY STANDARDS DEVELOPMENT
 UNIT SUPERVISOR
 FHWA



WIDTH RESTRICTION SIGNING



**WIDTH RESTRICTION SIGNING
2 LANE HIGHWAY**

LEGEND

⊙ SIGN ON PERMANENT SUPPORT

GENERAL NOTES

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A DESIRABLE MINIMUM OF 200 FEET CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

WIDTH ON SIGN TO BE APPROXIMATELY ONE FOOT LESS THAN AVAILABLE WIDTH.

* PLACE 500 FEET AFTER THE W20 - 1A AND 500 FEET BEFORE ADDITIONAL SIGNS FOR ROADWAYS WITH A PRE - CONSTRUCTION SPEED LIMIT OF 45 MPH OR MORE. FOR 35-40 MPH, USE 350 FOOT TYPICAL SPACING. FOR 25-30 MPH, USE 200 FOOT TYPICAL SPACING.

** SIGN SHALL BE VISIBLE FROM ROADWAY.

*** ADDITIONAL SIGNS NEEDED IF THERE IS AN ON RAMP BETWEEN SIGNS.



WIDTH ON SIGN TO BE APPROX. 1 - FOOT LESS THAN AVAILABLE WIDTH

ADVANCED WIDTH RESTRICTION SIGNING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION




APPROVED
May 2023 /S/ Andrew Heidtke
DATE WORK ZONE ENGINEER
FHWA

GENERAL NOTES


DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.

- ① LOCATE THE NO PASSING ZONE W14-3 SIGN WITHIN 50 FEET OF THE "T" MARKING
- ② MEASURE FROM EDGE OF MARKING TO JOINT LINE. THIS DOES NOT INCLUDE SPACE NEEDED FOR GROOVING OPERATIONS.


LEGEND

-  "T" MARKING
-  SIGN ON PERMANENT SUPPORT
-  DIRECTION OF TRAFFIC

* CONFIRM MARKING LINE WIDTH WITH THE MISCELLANEOUS QUANTITIES



TWO WAY TRAFFIC



ONE WAY TRAFFIC

PERMANENT PAVEMENT MARKING

6

6

SDD 15C08-23a


SDD 15C08-23a

PERMANENT LONGITUDINAL PAVEMENT MARKINGS

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2023 /S/ Jeannie Silver
DATE STATEWIDE SIGNING AND MARKING ENGINEER

FHWA



TEMPORARY BARRIER OFFSET FROM EDGELINE


GENERAL NOTES

DETAILS OF CONSTRUCTION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO STANDARD SPECIFICATIONS AND SPECIAL PROVISIONS.


LEGEND

➡ DIRECTION OF TRAFFIC


* CONFIRM MARKING LINE WIDTH WITH THE MISCELLANEOUS QUANTITIES



TWO WAY TRAFFIC



ONE WAY TRAFFIC



FREEWAYS AND EXPRESSWAYS


TEMPORARY PAVEMENT MARKING

TEMPORARY LONGITUDINAL PAVEMENT MARKING

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION


APPROVED
May 2023 /S/ Jeannie Silver
DATE STATEWIDE SIGNING AND MARKING ENGINEER

FHWA




DRUM

BALLAST WIDTHS
RANGE FROM 24"-36"



42" CONE

DO NOT USE IN TAPERS
½ SPACING OF DRUMS
BALLAST WIDTHS
RANGE FROM 14"-20"




VERTICAL PANEL

THE STRIPES SHALL SLOPE DOWNWARD TO
THE TRAFFIC SIDE FOR CHANNELIZATION.


GENERAL NOTES

- ① REFLECTIVE SHEETING SHALL FOLLOW THE REQUIREMENTS IN THE APPROVED PRODUCTS LISTING FOR SIGN SHEETING.
- ② LOCATION OF WARNING LIGHTS WHEN SHOWN ON THE PLAN.



TYPE II BARRICADE

FOR RAILS LESS THAN 36" LONG, 4" WIDE STRIPES
MAY BE USED. ALL STRIPES SHALL SLOPE DOWNWARD
TO THE TRAFFIC SIDE FOR CHANNELIZATION.



TYPE III BARRICADE

IF SIGN MOUNTED, DO NOT COVER MORE THAN 50% OF THE TOP
TWO RAILS OR 33% OF THE TOTAL AREA OF THE THREE RAILS.






* IF USED FOR A PERMANENT APPLICATION USE RED SHEETING.

**CHANNELIZING DEVICES
DRUMS, CONES, BARRICADES
AND VERTICAL PANELS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
 November 2022 /S/ Andrew Heidtke
 DATE WORK ZONE ENGINEER
 FHWA

LEGEND

-  SIGN ON PORTABLE OR PERMANENT SUPPORT
-  TEMPORARY PORTABLE RUMBLE STRIP ARRAY
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  FLAGGER, EQUIPPED WITH STOP/SLOW PADDLE FASTENED ON SUPPORT STAFF

GENERAL NOTES

DETAILS OF TRAFFIC CONTROL DEVICES AND INSTALLATION NOT SHOWN ON THIS DRAWING SHALL CONFORM TO THE PERTINENT REQUIREMENTS OF THE STANDARD SPECIFICATIONS, THE SPECIAL PROVISIONS, AND THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES.

ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

THE EXACT NUMBER, LOCATION AND SPACING OF ALL SIGNS, DEVICES, AND LOCATION OF ALL FLAGGERS SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE FIRST ADVANCE WARNING SIGN SHOULD TYPICALLY BE LOCATED IN ADVANCE OF THE ANTICIPATED TRAFFIC BACKUP OR QUEUE.


WHEN A SIDE ROAD OR RAMP INTERSECTS THE FACILITY ON WHICH THE WORK IS BEING PERFORMED, ADDITIONAL TRAFFIC CONTROLS SHALL BE PROVIDED AS SPECIFIED IN THE PLANS AND/OR THE SPECIAL PROVISIONS OR AS APPROVED BY THE ENGINEER.

FLAGGING

- FLAGGERS SHALL BE IN SIGHT OF EACH OTHER OR IN DIRECT COMMUNICATION AT ALL TIMES. THEY SHALL BE EQUIPPED WITH STOP/SLOW PADDLES FASTENED ON SUPPORT STAFFS. WHEN THE FLAGGING OPERATION IS NOT IN EFFECT REMOVE TEMPORARY PORTABLE RUMBLE STRIPS PRIOR TO COVERING OR REMOVING ALL ADVANCE SIGNING.
- ① FOR MOVING WORK OPERATIONS, POST ADDITIONAL W20-7A FLAGGER SIGNS AT APPROXIMATELY 3,500' INTERVALS IN THE MOVING WORK OPERATION OR AS APPROVED BY THE ENGINEER.
 - ② SIGN NOT REQUIRED IF FLAGGING OPERATION OCCURS WITHIN A SIGNED ROAD WORK ZONE AREA.
- WHEN THE DISTANCE BETWEEN FLAGGERS EXCEEDS 2 MILES, A PILOT CAR IS REQUIRED. WHEN CURVES REDUCE SIGHT DISTANCE BELOW 400', A PILOT CAR IS REQUIRED.

TEMPORARY PORTABLE RUMBLE STRIPS

- UTILIZE TEMPORARY PORTABLE RUMBLE STRIPS ON ALL FLAGGING OPERATIONS.
- ③ EACH TEMPORARY PORTABLE RUMBLE STRIP ARRAY CONSISTS OF THREE RUMBLE STRIPS PLACED TRANSVERSE ACROSS THE LANE AT THE LOCATIONS SHOWN. WITHIN EACH ARRAY, SPACING BETWEEN RUMBLE STRIPS SHALL BE 15 FEET ON CENTER
- ONLY USE TEMPORARY PORTABLE RUMBLE STRIPS FROM THE APPROVED PRODUCTS LIST.
- INSTALL TEMPORARY RUMBLE STRIPS PER MANUFACTURER'S RECOMMENDATIONS.
- PLACE ADVANCE SIGNING PRIOR TO INSTALLING TEMPORARY RUMBLE STRIPS.
- DO NOT INSTALL TEMPORARY PORTABLE RUMBLE STRIPS ON GRAVEL, MILLED SURFACES, OR ASPHALT THAT HAS BEEN PAVED LESS THAN 12 HOURS.




STOP/SLOW PADDLE ON SUPPORT STAFF

SIGN AND TEMPORARY RUMBLE STRIP ARRAY SPACING TABLE

SPEED LIMIT	SPACING "A"
25-30 MPH	200'
35-40 MPH	350'
45-55 MPH	500'



USE OF WO3-4 SIGN IS OPTIONAL. WHEN USED, THIS SIGN SHALL BE LOCATED BETWEEN THE W20-7A AND W20-4A SIGNS, USING SPACING "A".



TRAFFIC CONTROL FOR LANE CLOSURE WITH FLAGGING OPERATION

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
DATE: May 2022 /S/ Andrew Heidtke
WORK ZONE ENGINEER

GENERAL NOTES

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.

THE SPACING BETWEEN SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS.

THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.

ALL SIGNS ARE 48" x 48" UNLESS OTHERWISE NOTED.

"WO" SIGNS ARE THE SAME AS "W" SIGNS EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER.

CONSIDER ROADWAY GEOMETRICS WHEN LOCATING SIGNS AND ARROW BOARD SO THE DRIVER HAS A CLEAR VIEW OF THE ARROW BOARD AND LANE CLOSURE DRUMS.

FOR A LANE CLOSURE THAT IS IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS, THE ADVANCED WARNING SIGNS MAY BE MOUNTED ON PORTABLE SUPPORTS.

REMOVE PAVEMENT MARKINGS AND PLACE TEMPORARY PAVEMENT MARKING LINE IF LANE CLOSURE IS TO BE IN PLACE 4 OR MORE CONTINUOUS DAYS AND NIGHTS.










WARNING LIGHTS ARE NOT REQUIRED IF THE LANE CLOSURE IS A DAYTIME ONLY OPERATION.

IF THE HORIZONTAL ALIGNMENT IS SUCH THAT A CURVE MAY REQUIRE ADDITIONAL DELINEATION, THE DEVICE SPACING MAY BE DECREASED TO 50 FEET.

ADJUSTMENTS IN BUFFER SPACE NEED TO BE INCORPORATED WHEN THE LANE CLOSURE OCCURS NEAR AN INTERCHANGE EXIT OR ENTRANCE RAMP OR INTERSECTION. THE LANE CLOSURE MUST TAKE PLACE FAR ENOUGH IN ADVANCE OF AN EXIT OR ENTRANCE RAMP TO STILL ALLOW FOR ADEQUATE BUFFER SPACE. THE MINIMUM LENGTH OF THE BUFFER SPACE BEFORE AN EXIT RAMP SHOULD BE ONE HALF THE LENGTH OF THE TRANSITION AREA. THE ENTRANCE RAMP SHOULD BE FOLLOWED BY THE ORIGINAL BUFFER SPACE LENGTH OF 800 FEET DESIRABLE PRIOR TO ANOTHER TRAFFIC CONTROL CHANGE SUCH AS A CROSSOVER MANEUVER.


① A SPEED LIMIT SIGN SHALL BE LOCATED 1500 FEET BEYOND THE END OF THE ACCELERATION LANE OF EACH ENTRANCE RAMP. PLACE A SPEED LIMIT SIGN A MINIMUM OF EVERY 3 MILES. INCLUDE A RESUME SPEED LIMIT SIGN 200 FEET MINIMUM (500 FEET DESIRABLE) BEYOND THE "END OF ROADWORK" SIGN.

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
-  TYPE III BARRICADE WITH ATTACHED SIGN
-  TYPE "A" WARNING LIGHT (FLASHING)
-  REMOVING PAVEMENT MARKINGS
-  DIRECTION OF TRAFFIC
-  WORK AREA
-  FLASHING ARROW BOARD

6

SDD 15D12 - 11b







6

SDD 15D12 - 11b

TRAFFIC CONTROL, LANE CLOSURE, SPEED REDUCTION	
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION	
APPROVED May 2023 DATE	/S/ Andrew Heidtke WORK ZONE ENGINEER
FHWA	

LEGEND

-  SIGN ON PERMANENT SUPPORT
-  TRAFFIC CONTROL DRUM
-  DIRECTION OF TRAFFIC
-  WORK ZONE

GENERAL NOTES

ALL SIGNS ARE 48"X48" UNLESS OTHERWISE NOTED. IF NECESSARY DUE TO SPACE CONSTRAINTS IN URBAN AREAS, 36" X 36" SIGNS MAY BE USED IF APPROVED BY THE REGIONAL TRAFFIC UNIT.

"WO" SIGN IS THE SAME AS "W" SIGN EXCEPT THE BACKGROUND IS ORANGE.

ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH THE TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED AND AS APPROVED BY THE ENGINEER.

THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.


CHANNELIZING DEVICES PLACED ADJACENT TO WORK AREA SHALL BE PULLED BACK FROM THE TRAVEL LANE WHEN WORK IS NOT IN PROGRESS.

SIGNS THAT WILL BE IN PLACE LESS THAN 7 CONTINUOUS DAYS AND NIGHTS MAY BE MOUNTED ON PORTABLE SUPPORTS.

W20-1A AND G20-2A SIGNS ARE NOT REQUIRED IF THE WORK AREA IS WITHIN A LARGER WORK ZONE WHERE THESE SIGNS ARE ALREADY PRESENT. G20-2A SIGNS MAY ALSO BE OMITTED IF DURATION OF WORK IS LESS THAN 7 CONTINUOUS DAYS AND NIGHTS.

6

6



POSTED SPEED LIMIT PRIOR TO WORK STARTING (MPH)	ADVANCE WARNING SIGN SPACING (A) FEET	SHOULDER TAPER L / 3 W, LATERAL OFFSET (FT)						BUFFER SPACE (B) FEET
		3	4	5	6	7	8	
25	200'	10	14	17	21	24	28	55
30	200'	15	20	25	30	35	40	85
35	350'	20	27	34	40	47	54	120
40	350'	26	35	44	53	62	70	170
45	500'	45	59	74	89	104	119	220
50	500'	50	66	83	99	116	132	280
55	500'	54	73	91	109	127	145	335'

SDD 15D28 - 04

SDD 15D28 - 04

TRAFFIC CONTROL, WORK ON SHOULDER OR PARKING LANE, UNDIVIDED ROADWAY

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED
May 2020 /S/ Andrew Heidtke
DATE STATEWIDE WORK ZONE TRAFFIC SAFETY ENGINEER

FHWA


LEGEND

- TYPE III BARRICADE WITH ATTACHED SIGN
- SIGN ON PERMANENT SUPPORT
- TRAFFIC CONTROL DRUM WITH TYPE "C" STEADY BURN LIGHT
- TRAFFIC CONTROL DRUM
- FLAGS, 16" X 16" MIN. (ORANGE)
- REMOVING PAVEMENT MARKING
- DIRECTION OF TRAFFIC
- ASPHALTIC PAVEMENT WIDENING
- CONCRETE BARRIER TEMPORARY PRECAST
- TEMPORARY SIGNAL. SEE SDD 09G02 FOR EXACT PLACEMENT


WIDTH ON SIGN TO BE APPROX. 1-FOOT LESS THAN AVAILABLE WIDTH. (OMIT IF AVAILABLE WIDTH IS MORE THAN 16 FEET)

GENERAL NOTES

- THE EXACT NUMBER, LOCATION, AND SPACING OF ALL SIGNS AND DEVICES SHALL BE ADJUSTED TO FIT FIELD CONDITIONS AS APPROVED BY THE ENGINEER.
- THE SPACING BETWEEN TRAFFIC CONTROL SIGNS SHOULD BE ADJUSTED TO NOT CONFLICT WITH AND TO PROVIDE A MINIMUM OF 200 FEET (500 FEET DESIRABLE) CLEARANCE TO EXISTING SIGNS THAT WILL REMAIN IN PLACE..
- THIS LANE CLOSURE IS TYPICAL FOR CLOSING RIGHT LANE - REVERSE FOR CLOSING LEFT LANE.
- ALL SIGNS ARE 48" X 48" UNLESS OTHERWISE NOTED.
- "WO" IS THE SAME AS "W" EXCEPT THE BACKGROUND IS ORANGE.
- ANY SIGNS TEMPORARY OR EXISTING, WHICH CONFLICT WITH TRAFFIC CONTROL "IN USE" SHALL BE REMOVED OR COVERED AS NEEDED OR AS APPROVED BY THE ENGINEER.
- REMOVE PAVEMENT MARKING AND PLACE TEMPORARY PAVEMENT MARKING LINES IF THE CLOSURE IS TO BE IN PLACE FOR 4 OR MORE CONTINUOUS DAYS AND NIGHTS.
- INSTALL OVERHEAD TEMPORARY SIGNAL HEADS ABOVE THE MIDDLE OF THE TRAVEL LANE THEY ARE CONTROLLING.
- ① 500 FOOT SPACING SHOWN IS FOR ROADWAYS WITH A PRE-CONSTRUCTION REGULATORY SPEED LIMIT OF 45 MPH OR MORE. FOR 35 - 40 MPH, USE 350 FOOT TYPICAL SPACING. FOR 25 - 30 MPH, USE 200 FOOT TYPICAL SPACING.
 - ② USE 300 FOOT SPACING IF THE PRE - CONSTRUCTION REGULATORY SPEED IS 35 MPH OR LESS.
 - ③ DIMENSION DETERMINED BY CBTP TAPER FROM EDGE LINE TO TANGENT SECTION OF THE ROAD.
 - ④ TEMPORARY PAVEMENT MARKING LINE, 18 INCH WHITE STOP LINE.
 - ⑤ 700 FOOT TEMPORARY PAVEMENT MARKING LINE, 6 INCH DOUBLE YELLOW . WHEN THE DISTANCE FOR THE PRECEDING NO - PASSING ZONE IS LESS THAN THE MINIMUM DISTANCE BETWEEN ZONES AS INDICATED IN THE SPECIFICATIONS, THE TWO ZONES SHALL BE CONNECTED.
 - ⑥ SEE SDD 15C02 - SHEET "F" FOR ADVANCED WIDTH RESTRICTION SIGNING.



TEMPORARY PAVEMENT MARKING LINE, 6 INCH WHITE (STOPLINE TO STOPLINE). REMOVE EXISTING EDGELINE AND OFFSET THE TEMPORARY EDGELINE IF THE DISTANCE FROM THE EDGELINE TO CONCRETE BARRIER WALL IS LESS THAN 9 FEET.



**TRAFFIC CONTROL,
ONE LANE ROAD
WITH TEMPORARY SIGNALS**

STATE OF WISCONSIN
DEPARTMENT OF TRANSPORTATION

APPROVED _____ /S/ Andrew Heidtke
DATE May 2023 WORK ZONE ENGINEER

FHWA

LEGEND

- ⊙ INDICATES WING NUMBER.
- ⊗ LOCATION OF ANCHOR ASSEMBLY FOR PLATE BEAM GUARDRAIL
- ± DIMENSIONS GIVEN ARE NORMAL TO C/L OF SUBSTRUCTURE UNIT.

DESIGN DATA

LIVE LOAD: HS20
 DESIGN LOADING:
 INVENTORY RATING = HS09
 OPERATING RATING = HS34
 WISCONSIN STANDARD PERMIT VEHICLE (WIS-SPV) = 195 KIPS
 MATERIAL PROPERTIES:
 CONCRETE MASONRY - SUPERSTRUCTURE _____ f'c = 4,000 psi
 - ALL OTHER _____ f'c = 3,500 psi
 HIGH STRENGTH BAR STEEL REINFORCEMENT
 AASHTO GRADE 60 _____ fy = 60,000 psi
 ALL BAR STEEL SHALL BE EPOXY COATED

TRAFFIC DATA

ADT (2024) = 2680
 ADT (2044) = 3310
 DHV =
 DD = 60/40
 T = 9.1%
 DESIGN SPEED = 55 MPH

LIST OF DRAWINGS

- 1 GENERAL PLAN & ELEVATION
- 2 CROSS SECTION & QUANTITIES
- 3 CONSTRUCTION STAGING
- 4 REMOVAL DETAILS
- 5 WINGWALL DETAILS
- 6 ABUTMENT DETAILS & BILL OF BARS
- 7 STEEL DIAPHRAGM
- 8 SUPERSTRUCTURE PLAN
- 9 SUPERSTRUCTURE CROSS SECTION & DETAILS
- 10 SUPERSTRUCTURE BILL OF BARS
- 11 SINGLE SLOPE PARAPET 32SS
- 12 BAR SPLICER (COUPLER) DETAIL

NO.	DATE	REVISION	BY

SEH
 SHORT ELLIOTT HENDRICKSON INC.

STATE OF WISCONSIN
 DEPARTMENT OF TRANSPORTATION

ACCEPTED *[Signature]* SDR **08/15/23**
 CHIEF STRUCTURES DESIGN ENGINEER DATE


STRUCTURE B-47-42					
STH 35 OVER BIG RIVER					
COUNTY	PIERCE	TOWN/CITY/VILLAGE	OAK GROVE		
DESIGN SPEC.	REHABILITATION N/A				
DESIGNED BY	CJB	DESIGN CK'D.	MJG	DRAWN BY	RAD
PLANS CK'D.	CJB				

GENERAL PLAN & ELEVATION


SHEET 1 OF 12




SEH CONTACT: MATT GUNDRY, PE, 715.720.6246
 WISDOT BRIDGE OFFICE CONTACT: AARON BONK, PE, 608.261.0261



PLAN
 SINGLE SPAN - 45" PRESTRESSED GIRDER BRIDGE



ELEVATION



DETAIL

NOTES

ELEVATIONS AND HYDRAULIC INFORMATION
 BASED ON ORIGINAL PLANS.


PLOT TIME: 8:46:01 AM
 PLOT DATE: 7/21/2023
 FILE NAME: X:\UZ\W\ITNW\51807\5-f\indl-dsgn\51-drawings\20-struct\B-47-42\Sheet\B47042g.dgn

TOTAL ESTIMATED QUANTITIES - B-47-42

BID ITEM NUMBER	BID ITEM	UNIT	TOTALS
1	203.0270 REMOVING OLD STRUCTURE OVER WATERWAY DEBRIS CAPTURE B-47-42	EACH	1
	206.1001 EXCAVATION FOR STRUCTURES BRIDGES B-47-42	EACH	1
5	210.1500 BACKFILL STRUCTURE TYPE A	TON	35
	312.0110 SELECT CRUSHED MATERIAL	TON	50
	502.0100 CONCRETE MASONRY BRIDGES	CY	120
2	502.3200 PROTECTIVE SURFACE TREATMENT	SY	380
4 2	502.3210 PIGMENTED SURFACE SEALER	SY	100
	502.4205 ADHESIVE ANCHORS NO. 5 BAR	EACH	136
	505.0600 BAR STEEL REINFORCEMENT HS COATED STRUCTURES	LB	28,520
	505.0906 BAR COUPLERS NO. 6	EACH	289
	506.4000 STEEL DIAPHRAGMS B-47-42	EACH	10
3	509.1500 CONCRETE SURFACE REPAIR	SF	35
	516.0500 RUBBERIZED MEMBRANE WATERPROOFING	SY	10
	606.0300 RIPRAP HEAVY	CY	50
	614.0150 ANCHOR ASSEMBLIES FOR STEEL PLATE BEAM GUARD	EACH	4
	645.0111 GEOTEXTILE TYPE DF SCHEDULE A	SY	115
	645.0120 GEOTEXTILE TYPE HR	SY	70
	SPV.0060.02 FOAM VOID FILLING	EACH	1
NON-BID ITEMS			
	FILLER	SIZE	1/2"
	FILLER	SIZE	3/4"

QUANTITIES NOTES

- 1 PERTAINS TO DECK, RAILING, INTERMEDIATE DIAPHRAGMS, ABUT. DIAPHRAGM ENDS, AND WINGWALLS. PROTECT ITEMS TO REMAIN DURING REMOVAL
- 2 FURNISH AND APPLY "PIGMENTED SURFACE SEALER" TO FRONT FACE, TOP, AND ENDS OF PARAPETS. FURNISH AND APPLY "PROTECTIVE SURFACE TREATMENT" TO THE TOP SURFACE OF THE DECK INCLUDING THE PAVING NOTCH AREA. AND TOP PORTION OF WING WIDENING.
- 3 AS LOCATED BY FIELD ENGINEER.
- 4 INCLUDES PARAPETS ON WINGWALLS AND DECK.
- 5 A FACTOR OF 2.0 WAS USED TO CONVERT CUBIC YARDS TO TONS.



PROPOSED FINAL SECTION THRU B-47-42


LOOKING NORTH

GENERAL NOTES

- DRAWINGS SHALL NOT BE SCALED.
- ALL DIMENSIONS ARE IN FEET AND INCHES UNLESS OTHERWISE NOTED.
- DIMENSIONS SHOWN ARE BASED ON THE ORIGINAL STRUCTURE PLANS AND INSPECTION REPORTS. EXISTING BRIDGE PLANS AVAILABLE AT WISDOT.
- STATIONING MAY VARY BASED ON EXACT LOCATION OF BRIDGE TO PROPOSED ALIGNMENT.
- CONTRACTOR TO VERIFY EXISTING UTILITY LOCATIONS.
- ALL CONCRETE REMOVAL SHALL BE DEFINED BY A 1-INCH DEEP SAW CUT.
- THESE STRUCTURE PLANS ARE ONLY THE STRUCTURE REPAIR WORK. ANY ADDITIONAL REMOVAL REQUIRED, OUTSIDE OF THE LIMITS SHOWN IN THESE PLANS MUST BE COORDINATED WITH THE FIELD ENGINEER. FIELD ENGINEER SHOULD BE CONTACTED FOR APPROVAL OF ADDITIONAL REMOVAL.
- APPLY "PIGMENTED SURFACE SEALER" TO THE CONCRETE PARAPETS PER THE STANDARD SPECIFICATIONS AND AS SHOWN IN THIS PLAN SET.
- APPLY "PROTECTIVE SURFACE TREATMENT" TO THE TOP OF DECK, PAVING NOTCH AREA AND TOP PORTION OF THE WING WIDENING PER THE STANDARD SPECIFICATIONS AND AS SHOWN IN THIS PLAN SET.
- UTILIZE EXISTING BAR STEEL REINFORCEMENT WHERE SHOWN AND EXTEND 24 BAR DIAMETERS INTO NEW WORK, UNLESS SPECIFIED OTHERWISE.
- BAR STEEL REINFORCEMENT SHALL BE EMBEDDED 2" CLEAR UNLESS OTHERWISE SHOWN OR NOTED.
- BEVEL EXPOSED EDGES OF CONCRETE 3/4" UNLESS OTHERWISE NOTED.
- SEE ROADWAY PLAN FOR LANE STAGING AND TRAFFIC SHIFT. COORDINATE THESE STRUCTURE PLANS WITH THE ROADWAY STAGING.
- SEAL ALL EXPOSED HORIZONTAL AND VERTICAL SURFACES OF 1/2" FILLER WITH NON-STAINING GRAY NON-ASPHALTIC JOINT SEALER (1" DEEP & HOLD 1/8" BELOW SURFACE OF CONCRETE).
- THE UPPER LIMITS OF "EXCAVATION FOR STRUCTURES BRIDGES B-47-42" SHALL BE THE EXISTING GROUNDLINE.
- THE QUANTITY FOR BACKFILL STRUCTURE TYPE A IS CALCULATED BASED ON THE BACKFILL STRUCTURE LIMITS REQUIRED TO PERFORM DECK REPLACEMENT AND WING WORK AND AS PROVIDED IN THE PLAN DETAILS.
- JOINT FILLER SHALL CONFORM TO THE REQUIREMENTS OF AASHTO DESIGNATION M153 TYPE 1, 2, OR 3 OR AASHTO DESIGNATION M213.
- VARIATIONS TO THE NEW GRADE LINE OVER 1/4" MUST BE SUBMITTED BY THE FIELD ENGINEER TO THE STRUCTURES DESIGN SECTION FOR REVIEW.
- LONGITUDINAL CONSTRUCTION JOINT AND STAGING JOINT LOCATION TO BE DETERMINED BY THESE PLANS AND BY THE FIELD ENGINEER. COORDINATE WITH STAGING PLANS.
- THE CONTRACTOR SHALL SUPPLY A NEW NAMEPLATE IN ACCORDANCE WITH SECTION 502.3.11 OF THE STANDARD SPECIFICATIONS AND THE STANDARD DETAIL DRAWINGS. NAMEPLATE TO SHOW ORIGINAL CONSTRUCTION YEAR. SEE EXISTING NAMEPLATE FOR DATE.
- THE HAUNCH CONCRETE QUANTITY IS BASED ON THE AVERAGE HAUNCH SHOWN ON THE SUPERSTRUCTURE DETAILS SHEET


BENCHMARK (DATUM = NAVD 88)

NO	STATION	DESCRIPTION	ELEV
BM 1	7+43, 41'RT	SPIKE IN 18-INCH ELM	766.71
BM 2	11+09, 33'LT	SPIKE IN 22-INCH ELM	767.27




TYPICAL SECTION AT WINGWALL

▲ BACKFILL PAY LIMITS. BACKFILL BEYOND BACKFILL PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.



TYPICAL SECTION AT ABUTMENT BACKWALL

▲ BACKFILL PAY LIMITS. BACKFILL BEYOND BACKFILL PAY LIMITS SHALL BE INCIDENTAL TO EXCAVATION FOR STRUCTURES. LIMITS OF EXCAVATION SHALL BE DETERMINED BY THE CONTRACTOR.



PROFILE GRADE LINE


STA 10+00.00 EXISTING BRIDGE B-47-42
A SINGLE SPAN PRESTRESSED GIRDER BRIDGE
90'-3 5/8" OVERALL LENGTH x 36'-10" OVERALL WIDTH

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
CROSS SECTION & QUANTITIES			SHEET 2 OF 12

PLOT TIME: 8:46:04 AM


PLOT DATE: 7/21/2023

FILE NAME : X:\UZ\W\ITNW\518075-findi-dsgn\20-struct\B-47-42\Sheet\B47042g3.dgn



STAGE 1 CONSTRUCTION

LOOKING NORTH




STAGE 2 CONSTRUCTION

LOOKING NORTH



NOTES

SEE ROADWAY PLANS FOR ADDITIONAL STAGING DETAILS

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
CONSTRUCTION STAGING			SHEET 3 OF 12



PART LONGITUDINAL SECTION




WINGWALL REMOVAL
TYPICAL AT ALL (4) WINGWALLS

LEGEND

- REMOVAL LIMITS
- ‡ EXISTING BARS ARE LIKELY TO BE CORRODED AND/OR DAMAGED DURING CONCRETE REMOVAL. PRESERVE AND INCORPORATE AS MUCH REBAR AS PRACTICAL INTO NEW WORK.
- ** SEE ROADWAY PLANS FOR TRAFFIC CONTROL STAGING.


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
REMOVAL DETAILS			SHEET 4 OF 12

FILE NAME : X:\UZ\W\IT\NW\51807\5-f\ndi-dsgn\51-drawings\20-struct\B-47-42\Sheet\B47042r1.dgn PLOT DATE: 7/21/2023 PLOT TIME: 8:46:06 AM




WINGWALL 1 ELEVATION

(LOOKING AT FF OF WINGWALL)
PARAPET NOT SHOWN FOR CLARITY




WINGWALL 2 ELEVATION

(LOOKING AT FF OF WINGWALL)
PARAPET NOT SHOWN FOR CLARITY




WINGWALL 3 ELEVATION

(LOOKING AT FF OF WINGWALL)
PARAPET NOT SHOWN FOR CLARITY



WINGWALL 4 ELEVATION

(LOOKING AT FF OF WINGWALL)
PARAPET NOT SHOWN FOR CLARITY



SECTION H-H

LEGEND

▲ ADHESIVE ANCHORS NO. 5 BAR,
EMBED 8" INTO CONCRETE.

NOTES

SEE SHEET 6 FOR SECTIONS E-E, F-F, & G-G

EF = EACH FACE
FF = FRONT FACE
BF = BACK FACE
OC = ON CENTER

PLOT TIME: 8:46:07 AM

PLOT DATE: 7/21/2023


FILE NAME : X:\UZ\W\IT\NW\51807\5-f\indl-dsgn\51-drawings\20-Struct\B-47-42\Sheet\B47042.dgn

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
WINGWALL DETAILS			SHEET 5 OF 12




BILL OF BARS						SOUTH ABUTMENT
BAR MARK	COAT	* NO. REQ'D.	LENGTH (FT-IN)	BAR SERIES	BENT	LOCATION
A500	X	68	2 - 11		X	WINGWALL DOWELS
A501	X	34	7 - 6		X	WINGWALL STIRRUPS ABUT END
A402	X	5	11 - 2			WINGWALL LONGITUDINAL FF
A603	X	2	11 - 2			WINGWALL LONGITUDINAL FF TOP

BILL OF BARS						NORTH ABUTMENT
BAR MARK	COAT	* NO. REQ'D.	LENGTH (FT-IN)	BAR SERIES	BENT	LOCATION
B500	X	68	2 - 11		X	WINGWALL DOWELS
B501	X	34	7 - 6		X	WINGWALL STIRRUPS ABUT END
B402	X	5	11 - 2			WINGWALL LONGITUDINAL FF
B603	X	2	11 - 2			WINGWALL LONGITUDINAL FF TOP

NOTE:
THE FIRST DIGIT OF THE BAR MARK SIGNIFIES THE ENGLISH BAR DIAMETER SIZE.
DIMENSIONS IN BENDING DETAILS ARE OUT TO OUT.



LEGEND
 † EXISTING BARS ARE LIKELY TO BE CORRODED AND/OR DAMAGED DURING CONCRETE REMOVAL. PRESERVE AND INCORPORATE AS MUCH REBAR AS PRACTICAL.
 ● CONSTRUCTION JOINT - STRIKE OFF AS SHOWN.
 ▲ ADHESIVE ANCHORS NO. 5 BAR. EMBED 8" IN CONCRETE.
NOTE
 SEE SHEET 11 FOR SECTIONS THRU PARAPET ON WINGWALLS



PLOT TIME: 8:46:14 AM

PLOT DATE: 7/21/2023

FILE NAME : X:\UZ\W\IT\NW\51807\5-f\indl-dsgn\51-drawings\20-struct\B-47-42\Sheet\B4704202.dgn


8

8


NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
ABUTMENT DETAILS & BILL OF BARS			SHEET 6 OF 12

TABLE


GIRDER HEIGHT	DIM. "A"	DIM. "B"	DIM. "L"	* DIM. "X"
45"	1'-5 3/8"	1'-1 7/8"	1'-5 1/2"	2 1/4"




SECTION THRU DIAPHRAGM



PART TRANSVERSE SECTION AT DIAPHRAGM




DETAIL B



DIAPHRAGM SUPPORT

* 2 1/2" FOR ALTERNATE PLATE DIAPHRAGM



DIAPHRAGM PLAN

NOTES

ALL DIAPHRAGM MATERIAL NOT EMBEDDED IN THE CONCRETE GIRDER SHALL BE PAID FOR AT THE UNIT PRICE BID FOR "STEEL DIAPHRAGMS B-47-42", EACH.

EACH DIAPHRAGM BETWEEN GIRDERS SHALL CONSTITUTE ONE UNIT.

ALL DIAPHRAGM STRUCTURAL STEEL SHALL BE ASTM A709 GRADE 36.

ALL DIAPHRAGM MATERIAL INCLUDING BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED AFTER FABRICATION.

STEEL DIAPHRAGM TO CONCRETE WEB CONNECTION SHALL BE SNUG-TIGHT PLUS 1/4 TURN, UNLESS NOTED OTHERWISE. HIGH STRENGTH BOLTS FOR WEB CONNECTION SHALL MEET THE REQUIREMENTS FOR ASTM A325 OR ASTM A449.

PLOT TIME: 8:46:15 AM


PLOT DATE: 7/21/2023

FILE NAME : X:\UZ\W\IT\NW\51807\5-f\nd-d\sgn\51-drawings\20-struct\B-47-42\Sheet\B47042gs1diamt.dgn


8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
STEEL DIAPHRAGM		SHEET 7 OF 12	



DECK PLAN



PARAPET '32SS' REINFORCING ELEVATION

LEGEND

◆ BAR COUPLER IS REQUIRED, NUMBER (#) INDICATES SIZE. BAR LENGTHS ARE COMPUTED TO THE CENTERLINE OF THE CONSTRUCTION JOINT AND SHALL BE MODIFIED BY THE BAR COUPLER MANUFACTURER'S RECOMMENDATIONS. SEE SHEET 12 FOR DETAILS.


NOTES

SEE SHEET 9 FOR SECTION J-J


T = TOP
B = BOTTOM
EF = EACH FACE
FF = FRONT FACE
BF = BACK FACE

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
SUPERSTRUCTURE PLAN		SHEET 8 OF 12	


SEH CONTACT: MATT GUNDRY, PE, 715.720.6246
WISDOT BRIDGE OFFICE CONTACT: AARON BONK, PE, 608.261.0261




PROPOSED FINAL SECTION THRU B-47-42
LOOKING NORTH



SECTION J-J EDGE OF DECK DETAIL
PARAPET NOT SHOWN FOR CLARITY




PART LONGITUDINAL SECTION



SECTION THRU LONGITUDINAL JOINT

SECTION K-K



SECTION THRU '32SS' PARAPET ON BRIDGE

LEGEND

- CONSTRUCTION JOINT - STRIKE OFF AS SHOWN
- * DIMENSION IS TAKEN NORMAL TO C/L SUBSTRUCTURE UNITS.
- ** BARS PLACED PARALLEL TO GIRDERS SPACING PERPENDICULAR TO C/L GIRDERS
- ‡ EXISTING BARS ARE LIKELY TO BE CORRODED AND/OR DAMAGED DURING CONCRETE REMOVAL. PRESERVE AND INCORPORATE AS MUCH REBAR AS PRACTICAL.
- ⊠ BAR COUPLER IS REQUIRED, NUMBER (#) INDICATES SIZE. BAR LENGTHS ARE COMPUTED TO THE CENTERLINE OF THE CONSTRUCTION JOINT AND SHALL BE MODIFIED BY THE BAR COUPLER MANUFACTURER'S RECOMMENDATIONS. SEE SHEET 12 FOR DETAILS.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
SUPERSTRUCTURE CROSS SECTION & DETAILS		SHEET 9 OF 12	

BILL OF BARS							STAGE 1 SUPERSTRUCTURE						
BAR MARK	COAT	NO. REQ'D.	LENGTH (FT-IN)	BAR SERIES	BENT	LOCATION	BAR MARK	COAT	NO. REQ'D.	LENGTH (FT-IN)	BAR SERIES	BENT	LOCATION
S601	X	147	20 - 3			DECK TRANSVERSE - BOTTOM	S651	X	147	20 - 3			DECK TRANSVERSE - BOTTOM
S402	X	36	31 - 1			DECK LONGITUDINAL - BOTTOM	S452	X	36	31 - 1			DECK LONGITUDINAL - BOTTOM
S403	X	35	31 - 1			DECK LONGITUDINAL - TOP	S453	X	35	31 - 1			DECK LONGITUDINAL - TOP
S604	X	142	20 - 3			DECK TRANSVERSE - TOP	S654	X	142	20 - 3			DECK TRANSVERSE - TOP
S405	X	141	6 - 5		X	DECK TRANSVERSE - TOP EXTERIOR	S455	X	141	6 - 5		X	DECK TRANSVERSE - TOP EXTERIOR
S506	X	135	4 - 5		X	PARAPET DOWEL	S556	X	135	4 - 5		X	PARAPET DOWEL
S507	X	135	5 - 0		X	PARAPET VERTICAL	S557	X	135	5 - 0		X	PARAPET VERTICAL
S508	X	18	31 - 2			PARAPET LONGITUDINAL	S558	X	18	31 - 2			PARAPET LONGITUDINAL
S409	X	88	3 - 1		X	GIRDER 6 HAUNCH VERTICAL	S459	X	88	3 - 1		X	GIRDER 1 HAUNCH VERTICAL
S410	X	88	3 - 3		X	GIRDER 5 HAUNCH VERTICAL	S460	X	88	3 - 3		X	GIRDER 2 HAUNCH VERTICAL
S411	X	88	3 - 5		X	GIRDER 4 HAUNCH VERTICAL	S461	X	88	3 - 5		X	GIRDER 3 HAUNCH VERTICAL
S412	X	18	29 - 11			GIRDER HAUNCH LONGITUDINAL	S462	X	18	29 - 11			GIRDER HAUNCH LONGITUDINAL



BILL OF BARS							STAGE 2 SUPERSTRUCTURE						
BAR MARK	COAT	NO. REQ'D.	LENGTH (FT-IN)	BAR SERIES	BENT	LOCATION	BAR MARK	COAT	NO. REQ'D.	LENGTH (FT-IN)	BAR SERIES	BENT	LOCATION
S601	X	147	20 - 3			DECK TRANSVERSE - BOTTOM	S651	X	147	20 - 3			DECK TRANSVERSE - BOTTOM
S402	X	36	31 - 1			DECK LONGITUDINAL - BOTTOM	S452	X	36	31 - 1			DECK LONGITUDINAL - BOTTOM
S403	X	35	31 - 1			DECK LONGITUDINAL - TOP	S453	X	35	31 - 1			DECK LONGITUDINAL - TOP
S604	X	142	20 - 3			DECK TRANSVERSE - TOP	S654	X	142	20 - 3			DECK TRANSVERSE - TOP
S405	X	141	6 - 5		X	DECK TRANSVERSE - TOP EXTERIOR	S455	X	141	6 - 5		X	DECK TRANSVERSE - TOP EXTERIOR
S506	X	135	4 - 5		X	PARAPET DOWEL	S556	X	135	4 - 5		X	PARAPET DOWEL
S507	X	135	5 - 0		X	PARAPET VERTICAL	S557	X	135	5 - 0		X	PARAPET VERTICAL
S508	X	18	31 - 2			PARAPET LONGITUDINAL	S558	X	18	31 - 2			PARAPET LONGITUDINAL
S409	X	88	3 - 1		X	GIRDER 6 HAUNCH VERTICAL	S459	X	88	3 - 1		X	GIRDER 1 HAUNCH VERTICAL
S410	X	88	3 - 3		X	GIRDER 5 HAUNCH VERTICAL	S460	X	88	3 - 3		X	GIRDER 2 HAUNCH VERTICAL
S411	X	88	3 - 5		X	GIRDER 4 HAUNCH VERTICAL	S461	X	88	3 - 5		X	GIRDER 3 HAUNCH VERTICAL
S412	X	18	29 - 11			GIRDER HAUNCH LONGITUDINAL	S462	X	18	29 - 11			GIRDER HAUNCH LONGITUDINAL

LEGEND

- ⊕ BAR COUPLER IS REQUIRED, NUMBER (#) INDICATES SIZE. BAR LENGTHS ARE COMPUTED TO THE CENTERLINE OF THE CONSTRUCTION JOINT AND SHALL BE MODIFIED BY THE BAR COUPLER MANUFACTURER'S RECOMMENDATIONS. SEE SHEET 12 FOR DETAILS.
- ◆ WHERE THE SPACING OF THE EXISTING SHEAR STIRRUPS IS EQUAL TO OR LESS THAN 1'-0", SPACING HAT BARS TO MATCH. WHERE THE SPACING OF THE EXISTING SHEAR STIRRUPS IS MORE THAN 1'-0", SPACE HAT BARS AT 1'-0" MAX.

NOTE:
THE FIRST DIGIT OF THE BAR MARK SIGNIFIES THE ENGLISH BAR DIAMETER SIZE.


ELEVATIONS AT TOP OF DECK (T.O.D.)											
	SOUTH C/L ABUTMENT	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	NORTH C/L ABUTMENT
WEST EDGE	770.73	770.77	770.81	770.85	770.90	770.95	771.00	771.06	771.12	771.19	771.26
GIRDER 1	770.78	770.82	770.86	770.90	770.95	771.00	771.06	771.12	771.18	771.24	771.31
GIRDER 2	770.92	770.96	771.00	771.04	771.09	771.14	771.20	771.26	771.32	771.39	771.46
GIRDER 3	771.05	771.09	771.13	771.18	771.23	771.28	771.34	771.40	771.46	771.53	771.60
CROWN & C.J.	771.12	771.16	771.20	771.25	771.30	771.35	771.41	771.47	771.53	771.60	771.67
GIRDER 4	771.06	771.10	771.14	771.19	771.24	771.29	771.35	771.41	771.48	771.55	771.62
GIRDER 5	770.95	770.99	771.03	771.08	771.13	771.18	771.24	771.31	771.37	771.44	771.52
GIRDER 6	770.83	770.87	770.92	770.97	771.02	771.07	771.13	771.20	771.26	771.34	771.41
EAST EDGE	770.79	770.83	770.87	770.92	770.98	771.03	771.09	771.16	771.22	771.29	771.37



DEAD LOAD DEFLECTION DIAGRAM

SPAN		DEAD LOAD DEFLECTIONS								
SPAN	GIRDER NO.	DEAD LOAD DEFL. (IN.)								
		1/10	2/10	3/10	4/10	5/10	6/10	7/10	8/10	9/10
1	1 & 6	0.44	0.87	1.20	1.41	1.48	1.41	1.20	0.87	0.44
1	2 - 5	0.42	0.81	1.12	1.32	1.39	1.32	1.12	0.81	0.42


DEFLECTIONS ARE DUE TO WEIGHT OF CONCRETE DECK AND PARAPETS. DEFLECTIONS ARE THEORETICAL AND MAY VARY IN THE FIELD.



S506, S556


S507, S557

**S409 THRU S411
S456 THRU S461**



S405, S455

NOTE:
ALL DIMENSIONS IN THE BAR BENDS ARE OUT TO OUT



DECK HAUNCH DETAIL

IF 1/4" MINIMUM HAUNCH HEIGHT AT EDGE OF GIRDER CANNOT BE MAINTAINED, THE GRADE LINE MAY BE REVISED BY THE ENGINEER AT THE OPTION OF THE CONTRACTOR. THE PLAN DECK THICKNESS SHALL BE HELD. NOTIFY THE STRUCTURES SECTION IF THE GRADE LINE IS RAISED FROM THE PLAN PROFILE BY MORE THAN 1/4" OR, ** IF 3" MINIMUM DECK EMBEDMENT OF TIE BAR CANNOT BE OBTAINED.

TO DETERMINE 'T', ELEV. OF TOP OF GIR'S. AT C OF SUBSTRUCTURE UNITS & AT 1/10 POINTS OF EACH SPAN SHALL BE TAKEN. THEN FOLLOW THIS PROCESS:

- TOP OF DECK ELEV. AT FINAL GRADE
- TOP OF GIRDER ELEVATION
- + DEAD LOAD DEFLECTION
- DECK THICKNESS
- = HAUNCH HEIGHT 'T'



NOTE: AN AVERAGE HAUNCH ('T') OF 3 3/4" WAS USED IN THE QUANTITY "CONCRETE MASONRY BRIDGES".

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
SUPERSTRUCTURE BILL OF BARS		SHEET 10 OF 12	






BILL OF BARS

FOR ABUTMENT PARAPETS

BAR MARK	COAT	SOUTH ABUT.	NORTH ABUT.	LENGTH	BENT	BAR SERIES	LOCATION
R501	X	7	7	5'-10"	X		PARAPET VERT.
R502	X	7	7	5'-0"	X		PARAPET VERT.
R503	X	24	24	3'-0"	X		PARAPET VERT.
R504	X	34	34	5'-7"	X		PARAPET VERT.
R505	X	22	22	4'-9"	X		PARAPET VERT.
R506	X	12	12	4'-10"	X		PARAPET VERT.
R507	X	2	2	11'-1"	X		PARAPET HORIZ.
R508	X	10	10	11'-2"			PARAPET HORIZ.



OPTIONAL CONSTRUCTION JOINTS IN THE PARAPETS MAY BE USED. RUN BAR REINF. THRU THE JOINT. LAP LONGIT. BARS A MIN. OF 1'-9\"/>



■ BENCH MARK CAP (WHEN SUPPLIED). AVOID PLACING A BENCH MARK CAP BELOW A RAIL OR FENCE SYSTEM THAT IS ATTACHED TO THE TOP OF THE PARAPET.


● CONST. JOINT - STRIKE OFF AS SHOWN

■ R503 BARS MAY BE PLACED AFTER CONCRETE IS POURED BUT BEFORE INITIAL SET HAS TAKEN PLACE. USE CARE TO PLACE R503 BARS CORRECTLY ALONG TRANSITION OF PARAPET.

▽ R501 AND R504 BARS TO BE TIED TO WING STEEL BEFORE WING IS POURED.

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
SINGLE SLOPE PARAPET 32SS			SHEET 11 OF 12

PLOT TIME: 8:48:53 AM
PLOT DATE: 7/21/2023
FILE NAME: X:\UZ\W\IT\NW\51807\5-f\indl-dsgn\51-drawings\20-Struct\B-47-42\Sheet\B47042r.dwg




SECTION THRU DECK
ONE-PIECE THREADED COUPLER SHOWN


NOTES

FOR DOWEL BAR COUPLERS, ALL DOWEL BARS SHALL BE LAPPED AND TIED TO THE REINFORCEMENT BARS.

BAR LENGTH COMPUTED TO THE C/L OF THE CONSTRUCTION JOINT AND SHALL BE MODIFIED BY THE BAR COUPLER MANUFACTURERS RECOMMENDATIONS.



DOWEL BAR COUPLER
STAGE 2 DOWEL SCREWS INTO
COUPLER PLACED IN STAGE 1



ONE-PIECE THREADED COUPLER

BAR COUPLER ALTERNATIVES

PLOT TIME: 8:48:56 AM

PLOT DATE: 7/21/2023

FILE NAME : X:\UZ\W\WITNW\518075-f\ndi-dsgn\51-drawings\20-Struct\B-47-42\Sheet\B-47-42\Sheet\B-47-42\m1scld.dgn

8

8

NO.	DATE	REVISION	BY
STATE OF WISCONSIN DEPARTMENT OF TRANSPORTATION			
STRUCTURE B-47-42			
DRAWN BY		RAD	PLANS CK'D. CJB
BAR SPLICER (COUPLER) DETAIL			SHEET 12 OF 12


STH 35 - RT (STAGE 1)											
Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)				Mass Ordinate Note 5
		Cut Note 1	Fill	Cut Note 2,6	Unusable Pavement Material	Fill	Cut 1.00 Note 2	Unusable Pavement Material Note 3	Available Material 1.00 Note 3	Expanded Fill 1.30 Note 4	
5+50	0.0	0.0	0.0	0	0	0	0	0	0	0	0
5+85	34.7	0.0	0.0	0.0	0.0	0.0	0	0	0	0	0
6+10	25.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0	0
6+35	25.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0	0
7+00	65.3	0.0	0.0	0.0	0.0	0.0	0	0	0	0	0
8+00	100.0	0.0	0.0	0.0	0.0	0.0	0	0	0	0	0
8+50	49.9	0.0	0.0	0.0	0.0	0.0	0	0	0	0	0
8+50	0.1	34.8	2.3	0.1	0.0	0.0	0	0	0	0	0
8+60	9.5	33.6	10.8	12.1	2.9	2.3	12	3	9	3	6
8+85	25.5	33.4	11.0	31.6	7.9	10.3	44	11	33	16	16
8+94	9.0	35.0	4.0	11.4	2.8	2.5	55	14	42	20	22
9+06	12.3	38.2	1.9	16.7	3.8	1.3	72	17	54	21	33
9+09	3.1	34.3	1.7	4.2	1.0	0.2	76	18	58	22	36
9+37	27.7	26.7	9.0	31.3	8.6	5.5	107	27	80	29	52
9+50	12.3	24.6	27.9	11.7	0.0	8.4	119	27	92	40	52
9+50	0.5	0.0	0.0	0.2	0.0	0.3	119	27	92	40	52
10+50	100.0	0.0	0.0	0.0	0.0	0.0	119	27	92	40	52
10+50	0.5	0.0	0.0	0.0	0.2	0.0	119	27	92	40	52
10+63	12.2	24.1	32.0	5.4	3.8	7.2	125	31	94	49	44
11+00	37.2	29.2	5.6	36.8	11.5	25.9	161	42	119	83	36
11+00	0.1	14.1	5.5	0.1	0.0	0.0	162	42	119	83	36
11+41	40.7	16.5	4.2	23.1	12.6	7.3	185	55	130	93	37
11+53	12.5	18.2	0.0	8.0	3.9	1.0	193	59	134	94	40
11+66	12.5	19.6	0.0	8.8	3.9	0.0	201	63	139	94	45
12+00	34.3	20.6	0.0	25.6	10.6	0.0	227	73	154	94	60
12+00	0.1	20.6	0.0	0.1	0.0	0.0	227	73	154	94	60
13+00	99.9	17.2	0.0	69.8	9.3	0.0	297	82	214	94	120
13+65	65.2	16.1	0.0	40.2	6.0	0.0	337	89	248	94	155
13+90	25.0	15.7	68.0	14.7	2.3	31.5	352	91	261	135	126
14+15	25.0	13.2	64.9	13.4	2.3	61.5	365	93	272	215	57
14+30	15.0	5.3	46.5	5.1	1.4	30.9	370	95	276	255	21
15+00	69.8	4.8	0.0	13.0	6.5	60.1	383	101	282	333	-51

Notes:
1) Unusable Pavement Material is included in Cut.
2) Excavation Common is the sum of the Cut column. Item number 205.0100
3) Does not include Unusable Pavement Excavation volume.
4) Will be backfilled with Excavation Common or Borrow.
5) Plus quantity indicates an excess of material. Minus indicates a shortage of material. Borrow item number 208.0100
6) Additional cut required within excavation for structures limits (Sta 9+50 to Sta 10+50). See structure plans for additional information.

STH 35 - LT (STAGE 2)												
Station	Distance	AREA (SF)		Incremental Vol (CY) (Unadjusted)			Cumulative Vol (CY)				Mass Ordinate Note 5	
		Cut Note 1	Fill	Cut Note 2,6	Unusable Pavement Material	Fill	Cut 1.00 Note 2	Unusable Pavement Material Note 3	Available Material 1.00 Note 3	Expanded Fill 1.30 Note 4		
5+50	0.0	13.2	0.0	0	0.0	0	0	0	0	0	0	0
5+85	34.7	15.1	76.0	18.2	3.2	48.8	18	3	15	63	-48	
6+10	25.0	15.9	62.7	14.3	2.3	64.2	33	6	27	147	-120	
6+35	25.0	16.3	13.7	14.9	2.3	35.4	47	8	40	193	-153	
7+00	65.3	15.1	33.1	38.0	6.0	56.6	85	14	72	266	-195	
8+00	100.0	14.9	24.5	55.6	9.3	106.6	141	23	118	405	-287	
8+50	49.9	14.3	25.1	27.0	4.6	45.8	168	28	140	465	-324	
8+50	0.1	29.6	25.2	0.1	0.0	0.1	168	28	140	465	-324	
8+60	9.5	28.9	26.0	10.3	2.9	9.0	178	31	148	476	-329	
8+85	25.5	26.5	38.8	26.1	7.9	30.5	205	39	166	516	-350	
8+94	9.0	36.0	38.4	10.5	2.8	12.9	215	41	174	533	-359	
9+06	12.3	29.1	38.9	14.8	3.8	17.6	230	45	185	556	-371	
9+09	3.1	24.3	39.4	3.1	1.0	4.5	233	46	187	562	-375	
9+37	27.7	28.3	49.5	27.0	8.6	45.6	260	55	205	621	-416	
9+50	12.3	0.0	0.0	6.5	3.8	11.3	266	59	208	636	-428	
9+50	0.5	0.0	0.0	0.0	0.0	0.0	266	59	208	636	-428	
10+50	100.0	0.0	0.0	0.0	0.0	0.0	266	59	208	636	-428	
10+50	0.5	29.6	42.8	0.3	0.2	0.4	267	59	208	636	-428	
10+63	12.2	31.5	23.7	13.8	3.8	15.0	280	62	218	656	-438	
11+00	37.2	28.3	21.3	41.2	3.4	31.0	322	66	256	696	-440	
11+00	0.1	13.2	21.1	0.1	0.0	0.1	322	66	256	696	-440	
11+41	40.7	13.7	23.5	20.3	3.8	33.5	342	70	272	740	-467	
11+53	12.5	14.0	81.8	6.4	1.2	24.4	348	71	278	771	-494	
11+66	12.5	12.8	89.0	6.2	1.2	39.5	355	72	283	823	-540	
12+00	34.3	11.1	0.0	15.2	3.2	56.6	370	75	295	896	-602	
12+00	0.1	0.0	0.0	0.0	0.0	0.0	370	75	295	896	-602	
13+00	99.9	0.0	0.0	0.0	0.0	0.0	370	75	295	896	-602	
13+65	65.2	0.0	0.0	0.0	0.0	0.0	370	75	295	896	-602	
13+90	25.0	0.0	0.0	0.0	0.0	0.0	370	75	295	896	-602	
14+15	25.0	0.0	0.0	0.0	0.0	0.0	370	75	295	896	-602	
14+30	15.0	0.0	0.0	0.0	0.0	0.0	370	75	295	896	-602	
15+00	69.8	0.0	0.0	0.0	0.0	0.0	370	75	295	896	-601	

Notes:
1) Unusable Pavement Material is included in Cut.
2) Excavation Common is the sum of the Cut column. Item number 205.0100
3) Does not include Unusable Pavement Excavation volume.
4) Will be backfilled with Excavation Common or Borrow.
5) Plus quantity indicates an excess of material. Minus indicates a shortage of material. Borrow item number 208.0100
6) Additional cut required within excavation for structures limits (Sta 9+50 to Sta 10+50). See structure plans for additional information.

UTILITY LOCATIONS ARE APPROXIMATE.
ACTUAL LOCATIONS MUST BE FIELD VERIFIED.





PROJECT NO: 7180-02-72 HWY: STH 35 COUNTY: PIERCE CROSS SECTIONS SHEET E

FILE NAME: \\SEHCF1\PROJECTS\U2\W\WITNW\151807\5-FINAL-DSGN\CIVIL3D-STH35-BIGRIVERBRIDGE\SHEETS\PLAN\090201-XS.DWG PLOT DATE: 7/25/2023 11:51 AM PLOT BY: JUSTIN SHAVLIK PLOT NAME: PLOT SCALE: 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49

9

9

UTILITY LOCATIONS ARE APPROXIMATE.
ACTUAL LOCATIONS MUST BE FIELD VERIFIED.




9

9


PROJECT NO: 7180-02-72 HWY: STH 35 COUNTY: PIERCE CROSS SECTIONS SHEET E

FILE NAME: \\SEHCF1\PROJECTS\U2\W\WITNW\151807\5-FINAL-DSGN\CIVIL3D-STH35-BIGRIVERBRIDGE\SHEETSPLAN\090201-XS.DWG PLOT DATE: 7/25/2023 11:51 AM PLOT BY: JUSTIN SHAVLIK PLOT NAME: PLOT SCALE: 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49

UTILITY LOCATIONS ARE APPROXIMATE.
ACTUAL LOCATIONS MUST BE FIELD VERIFIED.




PROJECT NO: 7180-02-72 HWY: STH 35 COUNTY: PIERCE CROSS SECTIONS SHEET E



PROJECT NO: 7180-02-72 HWY: STH 35 COUNTY: PIERCE CROSS SECTIONS SHEET E

UTILITY LOCATIONS ARE APPROXIMATE.
ACTUAL LOCATIONS MUST BE FIELD VERIFIED.




9

PROJECT NO: 7180-02-72 HWY: STH 35 COUNTY: PIERCE CROSS SECTIONS SHEET E

FILE NAME: \\SEHCF1\PROJECTS\U2\W\WITNW\151807\5-FINAL-DSGN\CIVIL3D-STH35-BIGRIVERBRIDGE\SHEETSP\LAN\090201-XS.DWG PLOT DATE: 7/25/2023 11:51 AM PLOT BY: JUSTIN SHAVLIK PLOT NAME: PLOT SCALE: 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49




LAYOUT NAME - 05

UTILITY LOCATIONS ARE APPROXIMATE.
ACTUAL LOCATIONS MUST BE FIELD VERIFIED.




PROJECT NO: 7180-02-72	HWY: STH 35	COUNTY: PIERCE	CROSS SECTIONS	SHEET	E
------------------------	-------------	----------------	----------------	-------	---

UTILITY LOCATIONS ARE APPROXIMATE.
ACTUAL LOCATIONS MUST BE FIELD VERIFIED.



PROJECT NO: 7180-02-72 HWY: STH 35 COUNTY: PIERCE CROSS SECTIONS SHEET E




UTILITY LOCATIONS ARE APPROXIMATE.
ACTUAL LOCATIONS MUST BE FIELD VERIFIED.



PROJECT NO: 7180-02-72 HWY: STH 35 COUNTY: PIERCE CROSS SECTIONS SHEET E

FILE NAME: \\SEHCF1\PROJECTS\U2\W\WITNW\151807\5-FINAL-DSGN\CIVIL3D-STH35-BIGRIVERBRIDGE\SHEETS\PLAN\090201-XS.DWG PLOT DATE: 7/25/2023 11:51 AM PLOT BY: JUSTIN SHAVLIK PLOT NAME: PLOT SCALE: 1 IN:10 FT HORZ. / 1 IN:10 FT VERT. WISDOT/CADD SHEET 49

UTILITY LOCATIONS ARE APPROXIMATE.
ACTUAL LOCATIONS MUST BE FIELD VERIFIED.



PROJECT NO: 7180-02-72 HWY: STH 35 COUNTY: PIERCE CROSS SECTIONS SHEET E

9

9

Notes



Wisconsin Department of Transportation

Dedicated people creating transportation solutions through innovation and exceptional service.

<http://www.dot.wisconsin.gov>