



# Wisconsin Department of Transportation

## Division of Transportation Systems Development

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

December 5, 2023

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #32: 1580-04-72, WISC 2024079**  
**Ladysmith - Hawkins**  
**River Avenue to Prentice Street**  
**USH 8**  
**Rusk County**

**1580-04-73, WISC 2024080**  
**Ladysmith - Prentice**  
**Prentice Street to Rusk/Price Co Ln**  
**USH 8**  
**Rusk County**

### Letting of December 12, 2023

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
26	Adjusting Sanitary Manhole Covers, Item SPV.0060.03

Added Special Provisions	
Article No.	Description
32	Removing and Connecting Wall Modular Block, Item SPV.0060.04

#### Schedule of Items:

Added Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Quantity Added	Proposal Total After Addendum
SPV.0060.04	Removing and Connecting Wall Modular Block	Each	0	1	1

**Plan Sheets:**

<b>Revised Plan Sheets</b>	
<b>Plan Sheet</b>	<b>Plan Sheet Title (brief description of changes to sheet)</b>
64	Added the bid item for Removing and Connecting Wall Modular Block to the miscellaneous quantity table for the retaining wall.

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**  
**1580-04-72, 1580-04-73**  
**December 5, 2023**

**Special Provisions**

**26. Adjusting Sanitary Manhole Covers, Item SPV.0060.03.**

*Replace the table in the Payment section:*

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.03	Adjusting Sanitary Manhole Covers	EACH

**32. Removing and Connecting Wall Modular Block, Item SPV.0060.04.**

**A Description**

This special provision describes removing a portion of the existing modular block retaining wall conforming to standard spec 204 and connecting to the proposed Wall Modular Block Gravity Landscape.

**B (Vacant)**

**C Construction**

Use equipment and methods that provide a finished connection between the existing and proposed retaining wall acceptable to the engineer.

Perform the removal operations and cut existing wall components, as necessary, to avoid damage to the remaining retaining wall. Salvage and reinstall portions of the existing retaining wall as required to produce an acceptable interface between the existing and proposed retaining wall.

**D Measurement**

The department will measure Removing and Connecting Wall Modular Block by Each location, acceptably completed.

**E Payment**

ITEM NUMBER	DESCRIPTION	UNIT
SPV.0060.04	Removing and Connecting Wall Modular Block	EACH

Payment is full compensation for partially removing, sawing, salvaging, reinstalling, connecting existing retaining wall to the proposed retaining wall, excavating, backfilling and disposing of materials.

**Schedule of Items**

Attached, dated December 1, 2023, are the revised Schedule of Items Page 9.

**Plan Sheets**

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:  
Revised: 64.

END OF ADDENDUM





Proposal Schedule of Items

Proposal ID: 20231212032 Project(s): 1580-04-72, 1580-04-73

Federal ID(s): WISC 2024080, WISC 2024079

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0242	SPV.0060 Special 03. Adjusting Sanitary Manhole Covers	9.000 EACH	_____.	_____.
0244	SPV.0090 Special 01. Concrete Curb & Gutter Cure and Seal Treatment	3,879.000 LF	_____.	_____.
0246	SPV.0090 Special 02. Marking Stop Line Epoxy 24-Inch	419.000 LF	_____.	_____.
0248	SPV.0165 Special 01. Concrete Sidewalk Cure and Seal Treatment	4,386.000 SF	_____.	_____.
0250	SPV.0165 Special 02. Wall Modular Block Gravity Landscape (370+60, RT)	55.000 SF	_____.	_____.
0252	SPV.0180 Special 01. Concrete Driveway Cure and Seal Treatment	77.000 SY	_____.	_____.
0254	SPV.0060 Special 04. Removing and Connecting Wall Modular Block	1.000 EACH	_____.	_____.
<b>Section: 0001</b>			<b>Total:</b>	_____.
			<b>Total Bid:</b>	_____.

