



Wisconsin Department of Transportation

Division of Transportation Systems Development

Bureau of Project Development
4822 Madison Yards Way, 4th Floor South
Madison, WI 53705

December 7, 2023

Telephone: (608) 266-1631
Facsimile (FAX): (608) 266-8459

NOTICE TO ALL CONTRACTORS:

Proposal #34: 7560-05-74, WISC 20231212034
Blair - Merrilan
Trempealeau/Jackson Co Ln to IH 94
STH 95
Jackson County

Letting of December 12, 2023

This is Addendum No. 02, which provides for the following:

Schedule of Items:

Revised Bid Item Quantities					
Bid Item	Item Description	Unit	Proposal Total Prior to Addendum	Proposal Quantity Change (-)	Proposal Total After Addendum
205.0100	Excavation Common	CY	3816	836	4652
690.0150	Sawing Asphalt	LF	500	140	640

Plan Sheets:

Revised Plan Sheets	
Plan Sheet	Plan Sheet Title (brief description of changes to sheet)
33	Miscellaneous Quantities – Updated Excavation Common in Excavation Summary Table
42	Miscellaneous Quantities – updated Sawing Asphalt item quantity
154	Earthwork Summary – Updated quantities in tables
155	Earthwork Summary – Updated quantities in tables
156	Earthwork Summary – Updated quantities in tables

Schedule of Items

Attached, dated December 7, 2023, are the revised Schedule of Items Pages 1 and 8.

Plan Sheets

The following 8½ x 11-inch sheets are attached and made part of the plans for this proposal:

Revised: 33, 42, 154, 155 & 156

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

Mike Coleman

Proposal Development Specialist
Proposal Management Section

END OF ADDENDUM

BASE AGGREGATE DENSE 1 1/4-INCH

CATEGORY	STATION	LOCATION	REMARKS	TON	REMARKS
0010	PROJECT LIMITS	STH 95	SHOULDERS	3,792	
0010	PROJECT LIMITS	STH 95	DRIVEWAYS	140	
PROJECT TOTAL =				3,932	

CATEGORY	STATION	LOCATION	REMARKS	TON	REMARKS
0010	280+01	- 281+06	STH 95	373	CULVERT REPLACEMENT
0010	313+37	- 314+74	STH 95	486	CULVERT REPLACEMENT
0010	318+14	- 319+18	STH 95	369	CULVERT REPLACEMENT
0010	322+61	- 323+71	STH 95	390	CULVERT REPLACEMENT
0010	682+37	- 683+55	STH 95	419	CULVERT REPLACEMENT
0010				100	UNDISTRIBUTED
PROJECT TOTALS =				2,137	

305.0120

Addendum No. 02
ID 7560-05-74
Revised Sheet 33
December 7, 2023

SHAPING SHOULDERS

CATEGORY	STATION	LOCATION	REMARKS	TON	REMARKS
0010	748+75	- 756+52	END PROJECT	16	
PROJECT TOTALS =				16	

305.0500

BASE AGGREGATE DENSE 3/4-INCH

CATEGORY	STATION	LOCATION	REMARKS	TON	REMARKS
0010	PROJECT LIMITS	STH 95	SHOULDERS	3,792	
0010	PROJECT LIMITS	STH 95	DRIVEWAYS	140	
PROJECT TOTAL =				3,932	

CATEGORY	STATION	LOCATION	REMARKS	TON	REMARKS
0010	280+01	- 281+06	STH 95	373	CULVERT REPLACEMENT
0010	313+37	- 314+74	STH 95	486	CULVERT REPLACEMENT
0010	318+14	- 319+18	STH 95	369	CULVERT REPLACEMENT
0010	322+61	- 323+71	STH 95	390	CULVERT REPLACEMENT
0010	682+37	- 683+55	STH 95	419	CULVERT REPLACEMENT
0010				100	UNDISTRIBUTED
PROJECT TOTALS =				2,137	

305.0110

DIVISION	FROM/TO STATION	LOCATION	COMMON EXCAVATION (1)		SALVAGED/UNUSABLE PAVEMENT MATERIAL (4)	AVAILABLE MATERIAL (5)	UNEXPANDED FILL	EXPANDED FILL (6)	MASS ORDNATE +/- (7)	WASTE
			CUT (2)	EBS EXCAVATION (3)						
DIVISION 1 SUBTOTAL	258+00	262+00	0	0	0	0	22	29	-29	0
DIVISION 2 SUBTOTAL	280+00	281+00	792	0	36	756	539	701	55	55
DIVISION 3 SUBTOTAL	313+50	314+50	766	0	45	721	391	508	213	213
DIVISION 4 SUBTOTAL	318+50	319+00	935	0	36	899	649	844	55	55
DIVISION 5 SUBTOTAL	323+00	323+50	1,171	0	38	1,133	506	658	475	475
DIVISION 6 SUBTOTAL	394+50	401+00	0	0	0	0	243	316	-316	0
DIVISION 7 SUBTOTAL	434+00	439+00	0	0	0	0	103	134	-134	0
DIVISION 8 SUBTOTAL	509+00	516+00	0	0	0	0	164	213	-213	0
DIVISION 9 SUBTOTAL	682+50	683+50	988	0	43	945	671	872	73	73
DIVISION 10 SUBTOTAL	687+50	693+00	0	0	0	0	122	159	-159	0
GRAND TOTAL			4,652	0	198	4,454	3,410	4,433	21	21
TOTAL COMMON EXC			4,652							

- NOTES:
- (1) COMMON EXCAVATION IS THE SUM OF THE CUT AND EBS EXCAVATION COLUMNS. ITEM NUMBER 205.0100
 - (2) SALVAGED/UNUSABLE PAVEMENT MATERIAL IS INCLUDED IN CUT.
 - (3) EBS EXCAVATION TO BE BACKFILLED WITH SELECT BORROW MATERIAL. NOTE: THIS IS DESIGNERS CHOICE, CAN BE BACKFILLED WITH BORROW, OR CUT AS WELL.
 - (4) SALVAGED/UNUSABLE PAVEMENT MATERIAL
 - (5) AVAILABLE MATERIAL = CUT - SALVAGED/UNUSABLE PAVEMENT MATERIAL
 - (6) EXPANDED FILL FACTOR = 1.3
 - (7) THE MASS ORDNATE +OR -QTY CALCULATED FOR THE DIVISION. PLUS QUANTITY INDICATES AN EXCESS OF MATERIAL WITHIN THE DIVISION. MINUS INDICATES A SHORTAGE OF MATERIAL WITHIN THE DIVISION.
 - (8) FACTORS USED TO COMPUTE ANTICIPATED WASTE AND THE COMPUTED WASTE VOLUME IDENTIFIED ARE FOR GENERAL INFORMATION ONLY.
 - (9) ALL QUANTITIES FROM THE ABOVE TABLE ARE IN CUBIC YARDS (CY) UNLESS NOTED OTHERWISE.

PAVEMENT MARKING SUMMARY

CATEGORY	STATION	TO STATION	LOCATION	MARKING ARROW EPOXY EACH	646.5020	MARKING WORD EPOXY EACH	646.5120	MARKING RAILROAD CROSSINGS EPOXY EACH	646.5320	MARKING STOP LINE EPOXY INCH LF	646.6020	MARKING CROSSWALK EPOXY TRANSVERSE LINE 6-INCH LF	646.7420	MARKING ISLAND NOSE EPOXY LF	646.8120	MARKING EPOXY LF	646.8220	REMARKS					
0010	386+81	-	394+31	-	-	-	-	1	-	-	-	-	-	-	-	-	-	-					
0010	394+95	-	402+45	-	-	-	1	-	-	-	-	-	-	-	-	-	-	-					
0010	729+92	-	729+92	1	1	1	-	-	-	-	-	-	-	-	-	-	-	-					
0010	730+47	-	730+47	1	1	1	-	-	-	-	-	-	-	-	-	-	-	-					
0010	733+68	-	733+93	-	-	-	-	-	-	-	-	-	-	-	56	-	-	3					
0010	733+78	-	100M+35	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3 STOP LINES AT INTERSECTION					
0010	733+81	-	100M+31	-	-	-	-	-	-	54	-	-	-	-	-	-	-	ALL CROSSWALKS AT INTERSECTION					
0010	738+58	-	739+22	-	-	-	-	-	-	19	-	390	-	-	-	-	-	-					
0010												106											
PROJECT TOTALS =																1	1	1	2	73	496	56	3

CONSTRUCTION STAKING SUMMARY

CATEGORY	STATION TO STATION	LOCATION	RESURFACING REFERENCE LF	SIDEWALK (PROJECT) LF	01.7560-05-74	SUPPLEMENTAL CONTROL (PROJECT) LF	01.7560-05-74
0010	243+08	- 756+52	51,344	1	1	1	1
PROJECT TOTAL = 51,344							

SAWING CONCRETE

CATEGORY	LOCATION	690.0250 LF	REMARKS
0010	NW STATE ST INT	5	CURB & GUTTER
0010	SE STATE ST INT	5	CURB & GUTTER
0010	PARK DR	5	CURB & GUTTER
0010	HOFFMAN ST	5	CURB & GUTTER
0010	DEPOT ST	5	CURB & GUTTER
PROJECT TOTAL =			25

Addendum No. 02
 ID 7560-05-74
 Revised Sheet 42
 December 7, 2023

SAWING ASPHALT

CATEGORY	STATION TO STATION	LOCATION	690.0150 LF	REMARKS
0010	279+04	- 281+06	20	DRIVEWAY LT
0010	280+00	- 314+68	60	STH 95
0010	313+43	- 319+18	60	STH 95
0010	318+14	- 323+70	60	STH 95
0010	322+62	- 323+70	60	STH 95
0010	344+43	- 344+43	61	DRIVEWAY LT
0010	369+06	- 369+06	53	DRIVEWAY RT
0010	377+05	- 377+05	13	DRIVEWAY RT
0010	417+45	- 417+45	21	DRIVEWAY LT
0010	601+24	- 601+24	33	DRIVEWAY LT
0010	682+36	- 683+55	60	STH 95
0010	689+61	- 689+61	12	DRIVEWAY LT
0010	693+00	- 693+00	44	DRIVEWAY LT
0010	694+47	- 694+47	35	DRIVEWAY LT
0010	697+80	- 697+80	23	DRIVEWAY LT
0010	710+85	- 710+85	25	DRIVEWAY LT
PROJECT TOTAL =				640

CLEANING DITCH

CATEGORY	STATION TO STATION	LOCATION	SPV.0060.01 EACH	REMARKS
0010	274+55	- 274+85	2	STH 95
0010	334+00	- 334+30	2	STH 95
0010	366+00	- 366+30	2	STH 95
0010	476+90	- 477+20	1	STH 95
0010	491+85	- 492+15	2	STH 95
0010	650+65	- 650+95	2	STH 95
0010	657+75	- 658+05	2	STH 95
0010	666+90	- 667+20	2	STH 95
PROJECT TOTALS =				15

DIVISION 1 - ALIGNMENT - STH95																							
STATION	REAL STATION	DISTANCE	AREA (SF)			INCREMENTAL VOL (CY) (UNADJUSTED)			CUMULATIVE VOL (CY)				MASS ORDNATE	NOTE 8									
			SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	MARSH EXC	ROCK EXC	EBS	CUT	SALVAGED/UNUSABLE PAVEMENT MATERIAL	FILL	MARSH EXC	ROCK EXC			EBS	CUT	EXPANDED FILL	EXPANDED MARSH BACKFILL	EXPANDED ROCK	EXPANDED BACKFILL	REDUCED MARSH IN FILL	REDUCED EBS IN FILL	
258+00	25800.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
258+22.636	25822.64	22.64	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
258+50	25850.00	27.36	0.00	0.00	0.16	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
259+00	25900.00	50.00	0.00	0.00	3.54	0.00	0.00	0.00	0	0	0	0	0	4	0	0	0	0	0	0	0	0	-4
259+50	25950.00	50.00	0.00	0.00	6.56	0.00	0.00	0.00	0	0	0	0	0	16	0	0	0	0	0	0	0	0	-16
260+00	26000.00	50.00	0.00	0.00	1.97	0.00	0.00	0.00	0	0	0	0	0	26	0	0	0	0	0	0	0	0	-26
260+50	26050.00	50.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	29	0	0	0	0	0	0	0	0	-29
261+00	26100.00	50.00	0.00	0.00	0.01	0.00	0.00	0.00	0	0	0	0	0	29	0	0	0	0	0	0	0	0	-29
261+48.552	26148.55	48.55	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	29	0	0	0	0	0	0	0	0	-29
262+00	26200.00	51.45	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	29	0	0	0	0	0	0	0	0	-29
DIVISION 2 - ALIGNMENT - STH95																							
280+00	28000.00	1800.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	-29
280+53.35	28053.35	53.35	403.49	12.50	274.51	0.00	0.00	0.00	399	12	271	0	0	399	381	0	0	0	0	0	0	0	6
281+06	28106.00	52.65	0.00	12.50	0.00	0.00	0.00	0.00	393	24	268	0	0	792	729	0	0	0	0	0	0	0	27
DIVISION 3 - ALIGNMENT - STH95																							
313+43	31343.00	3237.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	792	729	0	0	0	0	0	0	0	27
314+00	31400.00	57.00	306.47	12.50	156.10	0.00	0.00	0.00	323	13	165	0	0	1,115	944	0	0	0	0	0	0	0	122
314+10	31410.00	10.00	306.47	12.50	156.10	0.00	0.00	0.00	114	5	58	0	0	1,229	1,019	0	0	0	0	0	0	0	156
314+68	31468.00	58.00	0.00	12.50	0.00	0.00	0.00	0.00	329	27	168	0	0	1,558	1,238	0	0	0	0	0	0	0	239
DIVISION 4 - ALIGNMENT - STH95																							
318+14	31814.00	346.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	1,558	1,238	0	0	0	0	0	0	0	239
318+65.93	31865.93	51.93	485.60	12.50	337.07	0.00	0.00	0.00	467	12	324	0	0	2,025	1,659	0	0	0	0	0	0	0	273
319+18	31918.00	52.07	0.00	12.50	0.00	0.00	0.00	0.00	468	24	325	0	0	2,493	2,081	0	0	0	0	0	0	0	295
DIVISION 5 - ALIGNMENT - STH95																							
322+62	32262.00	344.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	2,493	2,081	0	0	0	0	0	0	0	295
323+16.799	32316.80	54.80	585.29	12.50	253.15	0.00	0.00	0.00	594	13	257	0	0	3,087	2,415	0	0	0	0	0	0	0	542
323+70	32370.00	53.20	0.00	12.50	0.00	0.00	0.00	0.00	577	25	249	0	0	3,664	2,739	0	0	0	0	0	0	0	770
DIVISION 6 - ALIGNMENT - STH95																							
394+50	39450.00	7080.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	0	0	0	3,664	2,739	0	0	0	0	0	0	0	770
394+72.972	39472.97	27.97	0.00	0.00	2.56	0.00	0.00	0.00	0	0	1	0	0	3,664	2,740	0	0	0	0	0	0	0	769
395+00	39500.00	22.03	0.00	0.00	2.13	0.00	0.00	0.00	0	0	2	0	0	3,664	2,743	0	0	0	0	0	0	0	766
395+50	39550.00	50.00	0.00	0.00	1.80	0.00	0.00	0.00	0	0	4	0	0	3,664	2,748	0	0	0	0	0	0	0	761
396+00	39600.00	50.00	0.00	0.00	3.18	0.00	0.00	0.00	0	0	5	0	0	3,664	2,755	0	0	0	0	0	0	0	754
396+50	39650.00	50.00	0.00	0.00	16.82	0.00	0.00	0.00	0	0	19	0	0	3,664	2,779	0	0	0	0	0	0	0	740
397+00	39700.00	50.00	0.00	0.00	15.16	0.00	0.00	0.00	0	0	30	0	0	3,664	2,818	0	0	0	0	0	0	0	691
397+50	39750.00	50.00	0.00	0.00	7.72	0.00	0.00	0.00	0	0	21	0	0	3,664	2,846	0	0	0	0	0	0	0	663
398+00	39800.00	50.00	0.00	0.00	0.00	0.00	0.00	0.00	0	0	7	0	0	3,664	2,855	0	0	0	0	0	0	0	654
398+50	39850.00	50.00	0.00	0.00	11.77	0.00	0.00	0.00	0	0	11	0	0	3,664	2,869	0	0	0	0	0	0	0	640
399+00	39900.00	50.00	0.00	0.00	29.84	0.00	0.00	0.00	0	0	39	0	0	3,664	2,920	0	0	0	0	0	0	0	589
399+50	39950.00	50.00	0.00	0.00	30.70	0.00	0.00	0.00	0	0	56	0	0	3,664	2,993	0	0	0	0	0	0	0	516
400+00	40000.00	50.00	0.00	0.00	9.85	0.00	0.00	0.00	0	0	38	0	0	3,664	3,042	0	0	0	0	0	0	0	467
400+47.631	40047.63	47.63	0.00	0.00	0.60	0.00	0.00	0.00	0	0	9	0	0	3,664	3,054	0	0	0	0	0	0	0	455
401+00	40100.00	52.37	0.00	0.00	0.00	0.00	0.00	0.00	0	0	1	0	0	3,664	3,055	0	0	0	0	0	0	0	454

PROJECT NO: 7560-05-74

COUNTY: JACKSON

HWY: STH 95

EARTHWORK SUMMARY

SHEET NO: 154

E

FILE NAME: _____

PLOT BY: _____

PLOT NAME: _____

PLOT SCALE: 1:11

TOR: DIST. _____

9

Addendum No. 02
 ID 7560-05-74
 Revised Sheet 154
 December 7, 2023

Addendum No. 02
ID 7560-05-74
Revised Sheet 156
December 7, 2023

Notes:

1 - CUT	CUT INCLUDES SALVAGED/UNUSABLE PAVEMENT MATERIAL
2 - SALVAGED/UNUSABLE PAVEMENT MATERIAL	THIS DOES NOT SHOW UP IN CROSS SECTIONS
3 - FILL	DOES NOT INCLUDE UNUSABLE PAVEMENT EXC VOLUME
4 - EXPANDED MARSH BACKFILL	WILL BE BACKFILLED WITH GRANULAR BACKFILL (OR CUT, OR BORROW)
5 - EXPANDED EBS	WILL BE BACKFILLED WITH GRANULAR BACKFILL (OR CUT, OR BORROW)
6 - REDUCED MARSH IN FILL	REDUCED MARSH EXCAVATION THAT CAN BE USED IN FILL
7 - REDUCED EBS IN FILL	REDUCED EBS EXCAVATION THAT CAN BE USED IN FILL
8 - MASS ORDINATE	IF MARSH OR EBS TO BE BACKFILLED WITH COMMON OR BORROW: [(CUT - SALVAGED PAVT - EXPANDED MARSH EXC - EXPANDED EBS) - (FILL - REDUCED MARSH IN FILL - REDUCED EBS IN FILL - EXPANDED ROCK) * FILL FACTOR]]
8 - MASS ORDINATE	IF MARSH AND EBS TO BE BACKFILLED WITH GRANULAR: [(CUT - SALVAGED PAVT - (FILL - REDUCED MARSH IN FILL - REDUCED EBS IN FILL - EXPANDED ROCK) * FILL FACTOR)]
8 - MASS ORDINATE	IF MARSH AND EBS TO BE BACKFILLED WITH COMMON OR BORROW: [(CUT - SALVAGED PAVT - EXPANDED MARSH EXC - EXPANDED EBS) - (FILL - EXPANDED ROCK) * FILL FACTOR]]
	IF MARSH AND EBS TO BE BACKFILLED WITH GRANULAR: [(CUT - SALVAGED PAVT - (FILL - EXPANDED ROCK) * FILL FACTOR)]

NOTE 4 - SELECT ONE BASED ON INPUT DIALOG SELECTION
 NOTE 5 - SELECT ONE BASED ON INPUT DIALOG SELECTION
 NOTE 6 - IF EXCAVATED MARSH CAN BE USED IN FILL
 NOTE 7 - IF EXCAVATED EBS CAN BE USED IN FILL
 NOTE 8 - SELECT ONE BASED ON MASS HAUL INPUT DIALOG SELECTION. EBS AND MARSH EXC USED OUTSIDE 1:1 IN FILL SLOPES
 EBS AND MARSH EXC USED OUTSIDE 1:1 IN FILL SLOPES
 MARSH AND EBS ARE NOT USABLE OUTSIDE THE 1:1 SLOPES
 MARSH AND EBS ARE NOT USABLE OUTSIDE THE 1:1 SLOPES

PROJECT NO: 7560-05-74	HWY: STH 95	COUNTY: JACKSON	EARTHWORK SUMMARY	SHEET NO: 156	E
FILE NAME:	PLOT DATE:	PLOT BY:	PLOT NAME:	ORIGINATOR: DIST.	PLOT SCALE: 1:1



Proposal Schedule of Items

Proposal ID: 20231212034 Project(s): 7560-05-74

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0002	201.0105 Clearing	5.000 STA	_____.	_____.
0004	201.0205 Grubbing	5.000 STA	_____.	_____.
0006	203.0100 Removing Small Pipe Culverts	6.000 EACH	_____.	_____.
0008	204.0110 Removing Asphaltic Surface	241.000 SY	_____.	_____.
0010	204.0115 Removing Asphaltic Surface Butt Joints	2,815.000 SY	_____.	_____.
0012	204.0120 Removing Asphaltic Surface Milling	181,483.000 SY	_____.	_____.
0014	204.0150 Removing Curb & Gutter	294.000 LF	_____.	_____.
0016	204.0155 Removing Concrete Sidewalk	121.000 SY	_____.	_____.
0018	205.0100 Excavation Common	4,652.000 CY	_____.	_____.
0020	208.1500.S Temporary Lane Shift During Culvert Work	6.000 EACH	_____.	_____.
0022	211.0101 Prepare Foundation for Asphaltic Paving (project) 01. 7560-05-74	1.000 EACH	_____.	_____.
0024	213.0100 Finishing Roadway (project) 01. 7560-05-74	1.000 EACH	_____.	_____.
0026	305.0110 Base Aggregate Dense 3/4-Inch	3,932.000 TON	_____.	_____.
0028	305.0120 Base Aggregate Dense 1 1/4-Inch	2,137.000 TON	_____.	_____.
0030	305.0500 Shaping Shoulders	16.000 STA	_____.	_____.



Proposal Schedule of Items

Proposal ID: 20231212034 Project(s): 7560-05-74

Federal ID(s): N/A

SECTION: 0001 Contract Items

Alt Set ID: Alt Mbr ID:

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price	Bid Amount
0214	650.9911 Construction Staking Supplemental Control (project) 01. 7560-05-74	1.000 EACH	_____.	_____.
0216	690.0150 Sawing Asphalt	640.000 LF	_____.	_____.
0218	690.0250 Sawing Concrete	25.000 LF	_____.	_____.
0220	740.0440 Incentive IRI Ride	38,538.000 DOL	1.00000	38,538.00
0222	SPV.0060 Special 01. Cleaning Ditch	15.000 EACH	_____.	_____.
Section: 0001			Total:	_____.
			Total Bid:	_____.

