



## Wisconsin Department of Transportation

---

February 8, 2024

**Division of Transportation Systems  
Development**

Bureau of Project Development  
4822 Madison Yards Way, 4<sup>th</sup> Floor South  
Madison, WI 53705

Telephone: (608) 266-1631  
Facsimile (FAX): (608) 266-8459

### NOTICE TO ALL CONTRACTORS:

**Proposal #12: 2711-06-70, WISC 2024224**  
**Polk - Jackson**  
**STH 145 to Sherman Road**  
**CTH P**  
**Washington County**

### Letting of February 13, 2024

This is Addendum No. 01, which provides for the following:

#### Special Provisions:

Revised Special Provisions	
Article No.	Description
6	Utilities
18	Paving in Echelon

The responsibility for notifying potential subcontractors and suppliers of these changes remains with the prime contractor.

Sincerely,

*Mike Coleman*

Proposal Development Specialist  
Proposal Management Section

**ADDENDUM NO. 01**

**2711-06-70**

**February 8, 2024**

**Special Provisions**

**6. Utilities**

*Replace paragraph three under section titled **AT&T Wisconsin** with the following:*

AT&T Wisconsin plans to discontinue their underground facilities in place along the east side of the road from 527+40 to 577+00, and the crossings of CTH P at 481+25, 494+45, 521+50, and 574+44. AT&T Wisconsin plans to install new underground facilities from the existing manhole at 30+60, LT to the existing handhole at 574+75, RT, then north to the end of the project, placed 1' inside the east r/w line. AT&T Wisconsin plans to install new underground facilities crossing CTH P along the north side of Western Avenue from 18+00 to 21+00, crossing CTH P at 521+20; from the existing manhole at 30+60, LT west to 28+00; and from the existing handhole at 574+75, RT west to their overhead facilities on We Energies – Electric poles. AT&T Wisconsin plans to complete this work prior to May 3, 2024.

*Replace the last paragraph under section titled **Midwest Fiber Networks** with the following:*

Midwest Fiber Networks plans to complete their work prior to May 3, 2024.

**18. Paving in Echelon**

*Replace entire article language with the following:*

Echelon paving shall be completed on the upper layer for all mainline travel lane and any adjacent outside shoulders, turn lanes, bypass lanes or intersections in on direction at a time and shall be incidental to the bid item HMA Pavement 4 MT 58-28 S and 4 MT 58-28 H.

END OF ADDENDUM